

Generation and Transmission Planning

Overview

Planned Generation and Retirements

- **Planned Generation.** As of June 30, 2015, 77,461.3 MW of capacity were in generation request queues for construction through 2024, compared to an average installed capacity of 192,864.9 MW as of June 30, 2015. Of the capacity in queues, 8,242.9 MW, or 10.6 percent, are uprates and the rest are new generation. Wind projects account for 15,297.5 MW of nameplate capacity or 19.7 percent of the capacity in the queues. Combined-cycle projects account for 49,851.5 MW of capacity or 64.4 percent of the capacity in the queues.
- **Generation Retirements.** As shown in Table 12-6, 26,967.6 MW have been, or are planned to be, retired between 2011 and 2019. Of that, 3,203.3 MW are planned to retire after 2015. In the first two quarters of 2015, 9,717.0 MW were retired, of which 7,537.8 MW were coal units. The coal unit retirements were a result of the EPA's Mercury and Air Toxics Standards (MATS) and low gas prices.
- **Generation Mix.** A significant shift in the distribution of unit types within the PJM footprint continues as natural gas fired units enter the queue and steam units retire. While only 1,936.0 MW of coal fired steam capacity are currently in the queue, 53,050.5 MW of gas fired capacity are in the queue. The replacement of coal steam units by units burning natural gas could significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

Generation and Transmission Interconnection Planning Process

- Any entity that requests interconnection of a new generating facility, including increases to the capacity of an existing generating unit, or that requests interconnection of a merchant transmission facility, must follow the process defined in the PJM tariff to obtain interconnection

service.¹ The process is complex and time consuming at least in part as a result of the required analyses. The cost, time and uncertainty associated with interconnecting to the grid may create barriers to entry for potential entrants.

- The queue contains a substantial number of projects that are not likely to be built. Excluding currently active projects and projects currently under construction, 2,182 projects, representing 262,424 MW, have completed the queue process since its inception. Of those, 566 projects, 32,622 MW, went into service. Of the projects that have completed the queue process, 87.6 percent of the MW that entered the queue withdrew at some point in the process. These projects may create barriers to entry for projects that would otherwise be completed by taking up queue positions, increasing interconnection costs and creating uncertainty.
- Many feasibility, impact and facilities studies are delayed for reasons including disputes with developers, circuit and network issues, retooling as a result of projects being withdrawn, and the backlog of incomplete studies.
- Where the transmission owner is a vertically integrated company that also owns generation, there is a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is a competitor to the generation of the parent company of the transmission owner or the interconnection requirements of a merchant transmission developer which is a competitor of the transmission owner. There is also a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is part of the same company as the transmission owner.

Regional Transmission Expansion Plan (RTEP)

- Artificial Island is an area in southern New Jersey that includes nuclear units at Salem and at Hope Creek in the PSEG Zone. On April 29, 2013, PJM issued a request for proposal (RFP), seeking technical solutions to improve stability issues, operational performance under a range of anticipated system conditions, and the elimination of potential planning

¹ See PJM, OAIT Parts IV & VI.

criteria violations in this area. PJM staff announced on April 28, 2015, that they will recommend that the Board approve the Artificial Island project being designated to LS Power, PSEG, and PHI with a total cost estimate between \$263M and \$283M.²

Backbone Facilities

- PJM baseline transmission projects are implemented to resolve reliability criteria violations. PJM backbone transmission projects are a subset of significant baseline projects, which are intended to resolve multiple reliability criteria violations and congestion issues and which have substantial impacts on energy and capacity markets. The current backbone projects are Mount Storm-Doubs, Jacks Mountain, Susquehanna-Roseland, and Surry Skiffes Creek 500kV.

Transmission Facility Outages

- PJM maintains a list of reportable transmission facilities. When the reportable transmission facilities need to be taken out of service, PJM transmission owners are required to report planned transmission facility outages as early as possible. PJM processes the transmission facility outages according to rules in PJM's Manual 3 to decide if the outage is on time, late, or past its deadline.³

Recommendations

The MMU recommends improvements to the planning process.

- The MMU recommends the creation of a mechanism to permit a direct comparison, or competition, between transmission and generation alternatives, including which alternative is less costly and who bears the risks associated with each alternative. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that rules be implemented to permit competition to provide financing for transmission projects. This competition could

reduce the cost of capital for transmission projects and significantly reduce total costs to customers. (Priority: Low. First reported 2013. Status: Not adopted.)

- The MMU recommends that the question of whether Capacity Injection Rights (CIRs) should persist after the retirement of a unit be addressed. Even if the treatment of CIRs remains unchanged, the rules need to ensure that incumbents cannot exploit control of CIRs to block or postpone entry of competitors.⁴ (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends outsourcing interconnection studies to an independent party to avoid potential conflicts of interest. Currently, these studies are performed by incumbent transmission owners under PJM's direction. This creates potential conflicts of interest, particularly when transmission owners are vertically integrated and the owner of transmission also owns generation. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends improvements in queue management including that PJM establish a review process to ensure that projects are removed from the queue if they are not viable, as well as a process to allow commercially viable projects to advance in the queue ahead of projects which have failed to make progress, subject to rules to prevent gaming. (Priority: Medium. First reported 2013. Status: Not Adopted.)
- The MMU recommends an analysis of the study phase of PJM's transmission planning to reduce the need for postponements of study results, to decrease study completion times, and to improve the likelihood that a project at a given phase in the study process will successfully go into service. (Priority: Medium. First reported Q1, 2014. Status: Partially adopted, 2014.)
- The MMU recommends that PJM enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. (Priority: Medium. New recommendation. Status: Not adopted.)

² See PJM. "Artificial Island Recommendations," at <<http://www.pjm.com/~media/committees-groups/committees/teac/20150428-aj/20150428-artificial-island-recommendations.ashx>>

³ PJM. "Manual 03: Transmission Operations," Revision 46 (December 1, 2014), Section 4.

⁴ See "Comments of the Independent Market Monitor for PJM," <http://www.monitoringanalytics.com/reports/Reports/2012/IMM_Comments_ER12-1177-000_20120312.pdf>.

- The MMU recommends that PJM establish fair terms of access to rights of way and property, such as at substations, in order to remove any barriers to entry and permit competition between incumbent transmission providers and merchant transmission providers in the Regional Transmission Expansion Plan. (Priority: Medium. First reported 2014. Status: Not adopted.)
- The MMU recommends that PJM reevaluate all transmission outage tickets as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages. (Priority: Low. First reported 2014. Status: Not adopted.)

Conclusion

The goal of PJM market design should be to enhance competition and to ensure that competition is the driver for all the key elements of PJM markets. But transmission investments have not been fully incorporated into competitive markets. The construction of new transmission facilities has significant impacts on the energy and capacity markets. But when generating units retire or load increases, there is no market mechanism in place that would require direct competition between transmission and generation to meet loads in the affected area. In addition, despite Order No. 1000, there is not yet a transparent, robust and clearly defined mechanism to permit competition to build transmission projects, to ensure that competitors provide total project cost cap, or to obtain least cost financing through the capital markets.

The addition of a planned transmission project changes the parameters of the capacity auction for the area, changes the amount of capacity needed in the area, changes the capacity market supply and demand fundamentals in the area and may effectively forestall the ability of generation to compete. But there is no mechanism to permit a direct comparison, let alone competition, between transmission and generation alternatives. There is no mechanism to evaluate whether the generation or transmission alternative is less costly, whether there is more risk associated with the generation or transmission alternatives, or who bears the risks associated with each alternative. Creating such a mechanism should be an explicit goal of PJM market design.

The PJM queue evaluation process should be improved to ensure that barriers to competition for new generation investments are not created. Issues that need to be addressed include the ownership rights to CIRs, whether transmission owners should perform interconnection studies, and improvements in queue management.

The PJM rules for competitive transmission development through the Regional Transmission Expansion Plan should build upon Order No. 1000 to create real competition between incumbent transmission providers and merchant transmission providers. PJM should enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. Another element of opening competition would be to consider transmission owners' ownership of property and rights of way at or around transmission substations. In many cases, the land acquired included property intended to support future expansion of the grid. Incumbents have included the costs of the property in their rate base. Because PJM now has the responsibility for planning the development of the grid under its RTEP process, property bought to facilitate future expansion should be a part of that process and be made available to all providers on equal terms.

The process for the submission of planned transmission outages needs to be carefully reviewed and redesigned to limit the ability of transmission owners to submit transmission outages that are late for FTR Auction bid submission dates and are late for the Day Ahead Energy Market. The submission of late transmission outages can inappropriately affect market outcomes when market participants do not have the ability to modify market bids and offers.

Planned Generation and Retirements

Planned Generation Additions

Net revenues provide incentives to build new generation to serve PJM markets. While these incentives operate with a significant time lag and are based on expectations of future net revenue, the amount of planned new generation in PJM reflects investors' perception of the incentives provided by the combination of revenues from the PJM Energy, Capacity and Ancillary Service Markets. On June 30, 2015, 77,461.3 MW of capacity were in generation request queues for construction through 2024, compared to an average installed capacity of 192,864.9 MW as of June 30, 2015. Although it is clear that not all generation in the queues will be built, PJM has added capacity annually since 2000 (Table 12-1). In the first six months of 2015, 2,505.8 MW of nameplate capacity went into service in PJM.

Table 12-1 Year-to-year capacity additions from PJM generation queue: Calendar years 2000 through June 30, 2015

	MW
2000	505.0
2001	872.0
2002	3,841.0
2003	3,524.0
2004	1,935.0
2005	819.0
2006	471.0
2007	1,265.0
2008	2,776.7
2009	2,515.9
2010	2,097.4
2011	5,007.8
2012	2,669.4
2013	1,126.8
2014	2,659.0
2015	2,505.8

PJM Generation Queues

Generation request queues are groups of proposed projects, including new units, reratings of existing units, capacity resources and energy only resources. Each queue is open for a fixed amount of time. Studies commence on all projects in a given queue when that queue closes. The duration of the queue period has varied. Queues A and B were open for a year. Queues C-T were open for six months. Starting in February 2008, Queues U-Y1 were open for three months. Starting in May 2012, the duration of the queue period was reset to six months, starting with Queue Y2. Queue AB1 is currently open.

All projects that have been entered in a queue have a status assigned. Projects listed as active are undergoing one of the studies (feasibility, system impact, facility) required to proceed. Other status options are under construction, suspended, and in-service. Withdrawn projects are removed from the queue and listed separately. A project cannot be suspended until it has reached the status of under construction. Any project that entered the queue before February 1, 2011, can be suspended for up to three years. Projects that entered the queue after February 1, 2011, face an additional restriction in that the suspension period is reduced to one year if they affect any project later in the queue.⁵ When a project is suspended, PJM extends the scheduled milestones by the duration of the suspension. If, at any time, a milestone is not met, PJM will initiate the termination of the Interconnection Service Agreement (ISA) and the corresponding cancellation costs must be paid by the customer.

Table 12-2 shows MW in queues by expected completion date and MW changes in the queues between March 31, 2015, and June 30, 2015, for ongoing projects, i.e. projects with the status active, under construction or suspended.⁶ Projects that are already in service are not included here. The total MW in queues increased by 10,193.3 MW, or 15.2 percent, from 67,268.0 MW at the end of the first quarter of 2015. The change was the result of 15,803.5 MW in new projects entering the queue, 3,087.0 MW in existing projects withdrawing, and 1,827.0 MW going into service. The remaining difference is the result of projects adjusting their expected MW.

⁵ See PJM. Manual 14C. "Generation and Transmission Interconnection Process," Revision 8 (December 20, 2012), Section 3.7, <<http://www.pjm.com/~media/documents/manuals/m14c.ashx>>.

⁶ Expected completion dates are entered when the project enters the queue. Actual completion dates are generally different than expected completion dates.

Table 12-2 Queue comparison by expected completion year (MW): March 31, 2015 vs. June 30, 2015⁷

Year	Quarterly Change			
	As of 3/31/2015	As of 6/30/2015	MW	Percent
2015	15,609.4	12,632.6	(2,976.8)	(19.1%)
2016	17,453.7	16,466.5	(987.2)	(6.0%)
2017	12,878.1	13,821.4	943.3	6.8%
2018	14,139.0	14,603.1	464.1	3.2%
2019	4,191.8	12,274.8	8,083.0	65.9%
2020	1,152.0	4,442.0	3,290.0	74.1%
2021	250.0	1,377.0	1,127.0	81.8%
2022	0.0	250.0	250.0	100.0%
2024	1,594.0	1,594.0	0.0	0.0%
Total	67,268.0	77,461.3	10,193.3	15.2%

Table 12-3 shows the yearly project status changes in more detail and how scheduled queue capacity has changed between March 31, 2015, and June 30, 2015. For example, 27,814.9 MW entered the queue in the second quarter of 2015, 15,803.5 MW of which are currently active and 12,011.5 MW of which were withdrawn before the quarter ended. Of the total 39,974.8 MW marked as active at the beginning of the quarter, 3,034.0 MW were withdrawn, 1,745.3 MW started construction, and 225.1 MW went into service by the end of the second quarter. The Under Construction column shows that 964.0 MW came out of suspension and 1,745.3 MW began construction in the second quarter of 2015, in addition to the 20,254.1 MW of capacity that maintained the status under construction from the previous quarter.

Table 12-3 Change in project status (MW): March 31, 2015 vs. June 30, 2015

Status at 3/31/2015	Total at 3/31/2015	Status at 6/30/2015				
		Active	Suspended	Under Construction	In Service	Withdrawn
(Entered in Q2 2015)		15,803.5	0.0	0.0	0.0	12,011.5
Active	39,974.8	34,288.1	0.0	1,745.3	225.1	3,034.0
Suspended	5,224.8	0.0	4,036.8	964.0	200.0	24.0
Under Construction	22,068.4	0.0	369.5	20,254.1	1,401.8	29.0
In Service	38,975.3	0.0	0.0	0.0	38,969.6	0.0
Withdrawn	277,444.8	0.0	0.0	0.0	0.0	265,939.1
Total at 6/30/2015		50,091.6	4,406.3	22,963.4	40,796.5	281,037.5

⁷ Wind and solar capacity in Table 12-2 through Table 12-5 have not been adjusted to reflect derating.

Table 12-4 shows the amount of capacity active, in-service, under construction, suspended, or withdrawn for each queue since the beginning of the RTEP process and the total amount of capacity that had been included in each queue. All items in queues A-L are either in service or have been withdrawn. As of June 30, 2015, there are 77,461.3 MW of capacity in queues that are not yet in service, of which 5.7 percent are suspended, 29.6 percent are under construction and 64.7 percent have not begun construction.

Table 12-4 Capacity in PJM queues (MW): At June 30, 2015⁸

Queue	Active	Under				Total
		In Service	Construction	Suspended	Withdrawn	
A Expired 31-Jan-98	0.0	8,103.0	0.0	0.0	17,347.0	25,450.0
B Expired 31-Jan-99	0.0	4,465.0	0.0	0.0	14,620.7	19,085.7
C Expired 31-Jul-99	0.0	531.0	0.0	0.0	3,470.7	4,001.7
D Expired 31-Jan-00	0.0	850.6	0.0	0.0	7,182.0	8,032.6
E Expired 31-Jul-00	0.0	778.2	0.0	0.0	8,021.8	8,800.0
F Expired 31-Jan-01	0.0	52.0	0.0	0.0	3,092.5	3,144.5
G Expired 31-Jul-01	0.0	1,189.6	0.0	0.0	17,962.3	19,151.9
H Expired 31-Jan-02	0.0	702.5	0.0	0.0	8,421.9	9,124.4
I Expired 31-Jul-02	0.0	103.0	0.0	0.0	3,728.4	3,831.4
J Expired 31-Jan-03	0.0	40.0	0.0	0.0	846.0	886.0
K Expired 31-Jul-03	0.0	200.0	0.0	0.0	2,425.4	2,625.4
L Expired 31-Jan-04	0.0	252.5	0.0	0.0	4,033.7	4,286.2
M Expired 31-Jul-04	0.0	477.8	150.0	0.0	3,705.6	4,333.4
N Expired 31-Jan-05	0.0	2,382.8	38.0	0.0	8,090.3	10,511.0
O Expired 31-Jul-05	0.0	1,668.2	437.0	0.0	5,466.8	7,572.0
P Expired 31-Jan-06	0.0	3,255.2	62.5	210.0	5,110.5	8,638.2
Q Expired 31-Jul-06	105.0	3,147.9	1,594.0	0.0	9,686.7	14,533.6
R Expired 31-Jan-07	0.0	2,046.4	988.3	300.0	19,420.6	22,755.3
S Expired 31-Jul-07	0.0	3,536.3	458.3	420.0	12,706.5	17,121.0
T Expired 31-Jan-08	675.0	1,911.0	2,011.8	428.0	22,488.3	27,514.1
U Expired 31-Jan-09	1,410.0	1,072.8	401.9	300.0	30,119.6	33,304.3
V Expired 31-Jan-10	1,249.2	1,812.8	1,774.3	148.0	12,016.4	17,000.7
W Expired 31-Jan-11	2,018.0	1,159.6	1,603.7	1,564.0	17,942.6	24,287.9
X Expired 31-Jan-12	3,045.5	359.0	8,993.9	383.8	17,586.0	30,368.2
Y Expired 30-Apr-13	3,623.5	474.0	3,910.9	630.8	17,336.3	25,975.3
Z Expired 30-Apr-14	8,392.7	220.3	457.5	21.7	5,579.9	14,672.0
AA1 Expired 31-Oct-14	10,919.6	5.3	81.5	0.0	1,243.8	12,250.2
AA2 Expired 30-Apr-15	15,661.8	0.0	0.0	0.0	1,383.8	17,045.6
AB1 Through 30-Jun-15	2,991.3	0.0	0.0	0.0	1.5	2,992.8
Total	50,091.6	40,796.5	22,963.4	4,406.3	281,037.5	399,295.4

⁸ Projects listed as partially in-service are counted as in-service for the purposes of this analysis.

Table 12-5 Queue capacity by control zone and fuel (MW) at June 30, 2015⁹

Zone	CC	CT	Diesel	Hydro	Nuclear	Solar	Steam	Storage	Wind	Total Queue Capacity	Planned Retirements
AECO	1,276.0	295.3	0.0	0.0	0.0	73.2	0.0	20.0	373.0	2,037.5	8.0
AEP	6,111.0	51.0	17.8	46.5	102.0	118.4	209.0	72.0	7,312.0	14,039.7	0.0
AP	4,767.4	0.0	119.5	68.2	0.0	184.3	1,724.2	31.0	723.6	7,618.2	0.0
ATSI	4,052.0	0.8	21.6	0.0	0.0	0.0	0.0	0.0	518.0	4,592.4	6.3
BGE	0.0	0.0	30.3	0.4	0.0	23.1	132.0	0.0	0.0	185.8	209.0
ComEd	1,720.8	603.3	15.3	22.7	0.0	14.0	27.0	140.6	3,562.0	6,105.7	0.0
DAY	0.0	0.0	1.9	112.0	0.0	23.4	12.0	20.0	300.0	469.3	0.0
DEOK	513.0	0.0	6.4	0.0	0.0	125.0	50.0	18.0	0.0	712.4	0.0
DLCO	205.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	205.0	124.0
Dominion	5,465.3	0.0	3.6	0.0	1,594.0	1,571.4	62.5	128.0	1,322.1	10,146.9	323.0
DPL	901.0	17.0	2.0	0.0	0.0	455.5	0.0	20.0	250.0	1,645.5	34.0
EKPC	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	149.0
JCPL	3,034.0	0.0	0.0	0.0	0.0	574.1	0.0	180.0	0.0	3,788.1	614.5
Met-Ed	1,250.0	86.6	0.0	0.0	16.8	3.0	401.0	0.0	0.0	1,757.4	0.0
PECO	4,229.5	0.0	3.7	0.0	330.0	0.0	0.0	0.0	0.0	4,563.2	50.8
PENELEC	3,841.0	592.3	181.2	40.0	0.0	13.5	0.0	68.4	413.3	5,149.7	0.0
Pepco	2,725.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,725.6	1,204.0
PPL	6,100.0	0.0	5.0	0.0	0.0	129.0	16.0	30.0	523.5	6,803.5	0.0
PSEG	3,659.9	1,096.1	13.6	0.0	0.0	145.9	0.0	0.0	0.0	4,915.5	611.0
RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total	49,851.5	2,742.4	421.9	289.8	2,042.8	3,453.8	2,633.7	728.0	15,297.5	77,461.3	3,333.6

Distribution of Units in the Queues

Table 12-5 shows the projects under construction, suspended, or active, by unit type, and control zone.¹⁰ As of June 30, 2015, 77,461.3 MW of capacity were in generation request queues for construction through 2024, compared to 67,268.0 MW at March 31, 2015.¹¹ Table 12-5 also shows the planned retirements for each zone. A significant change in the distribution of unit types within the PJM footprint is likely as natural gas fired units continue to be developed and steam units continue to be retired. A significant shift in the distribution of unit types within the PJM footprint continues as natural gas fired units enter the queue and steam units retire. While 53,050.5 MW of gas

fired capacity are in the queue, only 1,936.0 MW of coal fired steam capacity are in the queue. The only new coal project since the second quarter a year ago is the new Hatfield unit, with 1,710 MW of capacity. This project entered the queue in October, 2014 and is intended to replace three coal units retired in October 2013 at the same location. With respect to retirements, 1,935.0 MW of coal fired steam capacity and 1,572.0 MW of natural gas capacity are slated for deactivation. The replacement of coal steam units by units burning natural gas could significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

Planned Retirements

As shown in Table 12-6, 26,967.6 MW have been, or are planned to be, retired between 2011 and 2019. Of that, 3,203.3 MW are planned to retire after 2015.

⁹ This data includes only projects with a status of active, under-construction, or suspended.

¹⁰ Unit types designated as reciprocating engines are classified as diesel.

¹¹ Since wind resources cannot be dispatched on demand, PJM rules previously required that the unforced capacity of wind resources be derated to 20 percent of installed capacity until actual generation data are available. Beginning with Queue U, PJM derates wind resources to 13 percent of installed capacity until there is operational data to support a different conclusion. PJM derates solar resources to 38 percent of installed capacity. Based on the derating of 15,297.5 MW of wind resources and 3,453.8 MW of solar resources, the 77,461.3 MW currently active in the queue would be reduced to 62,011.1 MW.


In the first two quarters of 2015, 9,717.0 MW were retired, of which 7,537.8 MW were coal units. The coal unit retirements were a result of the EPA's Mercury and Air Toxics Standards (MATS) and low gas prices.

Table 12-6 Summary of PJM unit retirements by fuel (MW): 2011 through 2019

	Coal	Diesel	Heavy Oil	Kerosene	Landfill Gas	Light Oil	Natural Gas	Nuclear	Wood Waste	Total
Retirements 2011	543.0	0.0	0.0	0.0	0.0	63.7	522.5	0.0	0.0	1,129.2
Retirements 2012	5,907.9	0.0	0.0	0.0	0.0	788.0	250.0	0.0	16.0	6,961.9
Retirements 2013	2,589.9	2.9	166.0	0.0	3.8	85.0	0.0	0.0	8.0	2,855.6
Retirements 2014	2,427.0	50.0	0.0	184.0	15.3	0.0	294.0	0.0	0.0	2,970.3
Retirements 2015	7,537.8	4.0	0.0	644.2	0.0	212.0	1,319.0	0.0	0.0	9,717.0
Planned Retirements 2015	124.0	6.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	130.3
Planned Retirements Post-2015	1,811.0	8.0	108.0	0.0	0.0	0.0	661.8	614.5	0.0	3,203.3
Total	20,940.6	71.2	274.0	828.2	19.1	1,148.7	3,047.3	614.5	24.0	26,967.6

A map of these retirements between 2011 and 2019 is shown in Figure 12-1.

Figure 12-1 Map of PJM unit retirements: 2011 through 2019



The list of pending deactivations is shown in Table 12-7.

Table 12-7 Planned deactivations of PJM units, as of June 30, 2015

Unit	Zone	MW	Fuel	Unit Type	Projected Deactivation Date
AES Beaver Valley	DLCO	124.0	Coal	Steam	01-Sep-15
Burger EMD	ATSI	6.3	Diesel	Diesel	18-Sep-15
Yorktown 1-2	Dominion	323.0	Coal	Steam	31-Mar-16
Dale 3-4	EKPC	149.0	Coal	Steam	16-Apr-16
BL England Diesels	AECO	8.0	Diesel	Diesel	31-May-16
Riverside 4	BGE	74.0	Natural gas	Steam	01-Jun-16
McKee 1-2	DPL	34.0	Heavy Oil	Combustion Turbine	31-May-17
Sewaren 1-4	PSEG	453.0	Kerosene	Combustion Turbine	01-Nov-17
Bayonne Cogen Plant (CC)	PSEG	158.0	Natural gas	Steam	01-Nov-18
MH50 Marcus Hook Co-gen	PECO	50.8	Natural gas	Steam	13-May-19
Chalk Point 1-2	Pepco	667.0	Coal	Steam	31-May-19
Dickerson 1-3	Pepco	537.0	Coal	Steam	31-May-19
Oyster Creek	JCPL	614.5	Nuclear	Nuclear	31-Dec-19
Wagner 2	BGE	135.0	Coal	Steam	01-Jun-20
Total		3,333.6			

Table 12-8 shows the capacity, average size, and average age of units retiring in PJM, from 2011 through 2019, while Table 12-9 shows these retirements by state. The majority, 77.5 percent of all MW retiring during this period are coal steam units. These units have an average age of 56.2 years and an average size of 165.9 MW. More than half of them, 51.6 percent, are located in either Ohio or Pennsylvania. Retirements have generally consisted of smaller sub-critical coal steam units and those without adequate environmental controls to remain viable beyond 2015.

Table 12-8 Retirements by fuel type, 2011 through 2019

	Number of Units	Avg. Size (MW)	Avg. Age at Retirement (Years)	Total MW	Percent
Coal	126	165.9	56.2	20,909.6	77.5%
Diesel	6	11.9	42.5	71.2	0.3%
Heavy Oil	4	68.5	57.5	274.0	1.0%
Kerosene	20	41.4	45.5	828.2	3.1%
Landfill Gas	4	4.8	14.8	19.1	0.1%
Light Oil	15	76.6	43.8	1,148.7	4.3%
Natural Gas	51	59.8	46.3	3,047.3	11.3%
Nuclear	1	614.5	50.0	614.5	2.3%
Waste Coal	1	31.0	20.0	31.0	0.1%
Wood Waste	2	12.0	23.5	24.0	0.1%
Total	230	117.3	50.8	26,967.6	100.0%

Table 12-9 Retirements (MW) by fuel type and state, 2011 through 2019

State	Coal	Diesel	Heavy Oil	Kerosene	Landfill Gas	Light Oil	Natural Gas	Nuclear	Wood Waste	Total
Delaware	254.0	0.0	34.0	0.0	0.0	0.0	0.0	0.0	0.0	288.0
Illinois	1,624.0	0.0	0.0	0.0	6.4	0.0	0.0	0.0	0.0	1,630.4
Indiana	982.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	982.0
Kentucky	995.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	995.0
Maryland	1,454.0	0.0	74.0	0.0	0.0	0.0	115.0	0.0	0.0	1,643.0
Michigan	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
New Jersey	136.0	8.0	0.0	828.2	4.7	212.0	2,680.5	614.5	0.0	4,483.9
North Carolina	0.0	0.0	0.0	0.0	0.0	31.0	0.0	0.0	0.0	31.0
Ohio	5,658.6	60.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5,718.9
Pennsylvania	5,145.0	0.0	166.0	0.0	8.0	117.7	251.8	0.0	24.0	5,712.5
Tennessee	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Virginia	2,051.0	2.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,053.9
West Virginia	2,641.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,641.0
Washington, DC	0.0	0.0	0.0	0.0	0.0	788.0	0.0	0.0	0.0	788.0
Total	20,940.6	71.2	274.0	828.2	19.1	1,148.7	3,047.3	614.5	24.0	26,967.6

Actual Generation Deactivations in 2015

Table 12-10 shows the units that were deactivated in 2015.

Table 12-10 Unit deactivations in 2015

Company	Unit Name	ICAP (MW)	Primary Fuel	Zone Name	Average Age (Years)	Retirement Date
Calpine Corporation	Cedar 1	44.0	Kerosene	AECO	43	28-Jan-15
First Energy	Eastlake 2	109.0	Coal	ATSI	62	06-Apr-15
First Energy	Eastlake 1	109.0	Coal	ATSI	62	09-Apr-15
First Energy	Eastlake 3	109.0	Coal	ATSI	61	10-Apr-15
First Energy	Ashtabula 5	210.0	Coal	ATSI	57	11-Apr-15
First Energy	Lake Shore 18	190.0	Coal	ATSI	53	13-Apr-15
First Energy	Lake Shore EMD	4.0	Diesel	ATSI	49	15-Apr-15
NRG Energy	Will County	251.0	Coal	Comed	58	15-Apr-15
EKPC	Dale 1-2	46.0	Coal	EKPC	61	16-Apr-15
Calpine Corporation	Cedar 2	21.6	Kerosene	AECO	43	01-May-15
NRG Energy	Gilbert 1-4	98.0	Natural gas	JCPL	45	01-May-15
NRG Energy	Glen Gardner 1-8	160.0	Natural gas	JCPL	44	01-May-15
Calpine Corporation	Middle 1-3	74.7	Kerosene	AECO	45	01-May-15
Calpine Corporation	Missouri Ave B, C, D	57.9	Kerosene	AECO	46	01-May-15
NRG Energy	Werner 1-4	212.0	Light oil	JCPL	43	01-May-15
PSEG	Bergen 3	21.0	Natural gas	PSEG	48	01-Jun-15
AEP	Big Sandy 2	800.0	Coal	AEP	46	01-Jun-15
PSEG	Burlington 8, 11	205.0	Kerosene	PSEG	48	01-Jun-15
AEP	Clinch River 3	230.0	Coal	AEP	54	01-Jun-15
PSEG	Edison 1-3	504.0	Natural gas	PSEG	44	01-Jun-15
PSEG	Essex 10-11	352.0	Natural gas	PSEG	44	01-Jun-15
PSEG	Essex 12	184.0	Natural gas	PSEG	43	01-Jun-15
AEP	Glen Lyn 5-6	325.0	Coal	AEP	65	01-Jun-15
AES Corporation	Hutchings 1-3, 5-6	271.8	Coal	DAY	65	01-Jun-15
AEP	Kammer 1-3	600.0	Coal	AEP	57	01-Jun-15
AEP	Kanawha River 1-2	400.0	Coal	AEP	62	01-Jun-15
PSEG	Mercer 3	115.0	Kerosene	PSEG	48	01-Jun-15
Duke Energy Kentucky	Miami Fort 6	163.0	Coal	DEOK	55	01-Jun-15
AEP	Muskingum River 1-5	1,355.0	Coal	AEP	60	01-Jun-15
PSEG	National Park 1	21.0	Kerosene	PSEG	46	01-Jun-15
AEP	Picway 5	95.0	Coal	AEP	60	01-Jun-15
PSEG	Sewaren 6	105.0	Kerosene	PSEG	50	01-Jun-15
AEP	Sporn 1-4	580.0	Coal	AEP	64	01-Jun-15
AEP	Tanners Creek 1-4	982.0	Coal	AEP	60	01-Jun-15
NRG Energy	Shawville 4	175.0	Coal	PENELEC	55	02-Jun-15
NRG Energy	Shawville 3	175.0	Coal	PENELEC	56	07-Jun-15
NRG Energy	Shawville 1	122.0	Coal	PENELEC	61	12-Jun-15
NRG Energy	Shawville 2	125.0	Coal	PENELEC	61	14-Jun-15
Portsmouth Genco	Lake Kingman	115.0	Coal	Dominion	27	19-Jun-15
Total		9,717.0				

Generation Mix

As of June 30, 2015, PJM had an installed capacity of 192,864.9 MW (Table 12-11). This measure differs from capacity market installed capacity because it includes energy-only units and uses non-derated values for solar and wind resources.

Table 12-11 Existing PJM capacity: At June 30, 2015 (By zone and unit type (MW))¹²

Zone	CC	CT	Diesel	Fuel Cell	Hydroelectric	Nuclear	Solar	Steam	Storage	Wind	Total
AECO	901.9	507.7	22.6	0.0	0.0	0.0	41.7	815.9	0.0	7.5	2,297.3
AEP	4,900.0	3,682.2	77.1	0.0	1,071.9	2,071.0	0.0	18,897.8	4.0	1,953.2	32,657.2
AP	1,129.0	1,214.9	47.9	0.0	86.0	0.0	36.1	5,409.0	27.4	1,058.5	9,008.8
ATSI	685.0	1,617.4	74.0	0.0	0.0	2,134.0	0.0	5,813.0	0.0	0.0	10,323.4
BGE	0.0	840.0	18.4	0.0	0.0	1,716.0	0.0	2,995.5	0.0	0.0	5,569.9
ComEd	3,146.1	7,244.0	93.8	0.0	0.0	10,473.5	9.0	5,166.1	4.5	2,431.9	28,568.9
DAY	0.0	1,368.5	47.5	0.0	0.0	0.0	1.1	2,908.0	40.0	0.0	4,365.1
DEOK	47.2	654.0	0.0	0.0	0.0	0.0	0.0	3,730.0	2.0	0.0	4,433.2
DLCO	244.0	15.0	0.0	0.0	6.3	1,777.0	0.0	784.0	0.0	0.0	2,826.3
Dominion	5,493.6	3,874.8	153.8	0.0	3,589.3	3,581.3	22.7	7,890.0	0.0	0.0	24,605.5
DPL	1,498.5	1,820.4	96.1	30.0	0.0	0.0	4.0	1,620.0	0.0	0.0	5,069.0
EKPC	0.0	774.0	0.0	0.0	70.0	0.0	0.0	1,882.0	0.0	0.0	2,726.0
EXT	1,471.0	297.9	0.0	0.0	269.1	12.5	0.0	5,253.5	0.0	0.0	7,304.0
JCPL	1,692.5	763.1	19.9	0.0	400.0	614.5	96.3	10.0	0.0	0.0	3,596.3
Met-Ed	2,111.0	406.5	41.4	0.0	19.0	805.0	0.0	200.0	0.0	0.0	3,582.9
PECO	3,209.0	836.0	2.9	0.0	1,642.0	4,546.8	3.0	979.1	1.0	0.0	11,219.8
PENELEC	0.0	407.5	45.8	0.0	512.8	0.0	0.0	6,793.5	0.0	930.9	8,690.5
Pepco	230.0	1,091.7	9.9	0.0	0.0	0.0	0.0	3,649.1	0.0	0.0	4,980.7
PPL	1,807.9	616.2	55.5	0.0	706.6	2,520.0	15.0	5,169.9	20.0	219.7	11,130.8
PSEG	3,091.3	1,132.0	11.1	0.0	5.0	3,493.0	124.8	2,050.1	2.0	0.0	9,909.3
RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total	31,658.0	29,163.8	817.7	30.0	8,378.0	33,744.6	353.7	82,016.5	100.9	6,601.7	192,864.9

Figure 12-2 and Table 12-12 show the age of PJM generators by unit type. Units older than 40 years comprise 69,760.2 MW, or 36.2 percent, of the total capacity of 192,864.9 MW.

Table 12-12 PJM capacity (MW) by age (years): At June 30, 2015

Age (years)	CC	CT	Diesel	Fuel Cell	Hydroelectric	Nuclear	Solar	Steam	Storage	Wind	Total
Less than 20	27,279.5	21,754.9	557.0	30.0	189.6	0.0	353.7	5,212.9	100.9	6,601.7	62,080.2
20 to 40	3,936.5	2,913.9	88.8	0.0	3,557.2	22,906.4	0.0	27,621.7	0.0	0.0	61,024.5
40 to 60	442.0	4,495.0	169.9	0.0	3,010.0	10,838.2	0.0	47,545.4	0.0	0.0	66,500.5
More than 60	0.0	0.0	2.0	0.0	1,621.2	0.0	0.0	1,636.5	0.0	0.0	3,259.7
Total	31,658.0	29,163.8	817.7	30.0	8,378.0	33,744.6	353.7	82,016.5	100.9	6,601.7	192,864.9

¹² The capacity described in this section refers to all non-derated installed capacity in PJM, regardless of whether the capacity entered the RPM auction.

Figure 12-2 PJM capacity (MW) by age (years): At June 30, 2015




Table 12-13 shows the effect that expected retirements and new generation in the queues would have on the existing generation mix five years from now. Even though 69,760.2 MW of the total capacity are more than 40 years old, only 3,333.6 MW are planned to retire within the next five years. The expected role of gas-fired generation depends on projects in the queues and retirement of coal-fired generation. Existing capacity is 42.5 percent steam, which will be reduced to 31.9 percent by 2020 as a result of the addition of 44,498.5 MW of planned CC capacity. The percentage of CC capacity would increase from 16.4 percent to 29.7 percent of total capacity in PJM in 2020.

Table 12-13 Expected capacity (MW) in five years, as of June 30, 2015¹³

Unit Type	Current Generator Capacity	Percent of Area Total	Planned Additions	Planned Retirements	Estimated Capacity in 5 Years	Percent of Area Total
Combined Cycle	31,658.0	16.4%	44,498.5	0.0	76,156.5	29.7%
Combustion Turbine	29,163.8	15.1%	2,742.4	0.0	31,906.2	12.4%
Diesel	817.7	0.4%	415.5	14.3	1,218.9	0.5%
Fuel Cell	30.0	0.0%	0.0	0.0	30.0	0.0%
Hydroelectric	8,378.0	4.3%	154.7	0.0	8,532.7	3.3%
Nuclear	33,744.6	17.5%	448.8	614.5	33,578.9	13.1%
Solar	353.7	0.2%	3,170.8	0.0	3,524.5	1.4%
Steam	82,016.5	42.5%	2,633.7	2,704.8	81,945.4	31.9%
Storage	100.9	0.1%	311.6	0.0	412.5	0.2%
Wind	6,601.7	3.4%	12,657.4	0.0	19,259.1	7.5%
Total	192,864.9	100.0%	67,033.3	3,333.6	256,564.6	100.0%

¹³ Percentages shown in Table 12-12 are based on unrounded, underlying data and may differ from calculations based on the rounded values in the tables.

Generation and Transmission Interconnection Planning Process

PJM made changes to the queue process in May 2012.¹⁴ These changes included reducing the length of the queues, creating an alternate queue for some small projects, and adjustments to the rules regarding suspension rights and Capacity Interconnection Rights (CIR). PJM staff reported on June 11, 2015, that the study backlog has been significantly reduced.¹⁵

Interconnection Study Phase

In the study phase of the interconnection planning process, a series of studies are performed to determine the feasibility, impact, and cost of projects in the queue. Table 12-14 is an overview of PJM's study process. System impact and facilities studies are often redone when a project is withdrawn in order to determine the impact on the projects remaining in the queue.

Table 12-14 PJM generation planning process

Process Step	Start on	Financial Obligation	Days for PJM to Complete	Days for Applicant to Decide Whether to Continue
Feasibility Study	Close of current queue	Cost of study (partially refundable deposit)	90	30
System Impact Study	Upon acceptance of the System Impact Study Agreement	Cost of study (partially refundable deposit)	120	30
Facilities Study	Upon acceptance of the Facilities Study Agreement	Cost of study (refundable deposit)	Varies	60
Schedule of Work	Upon acceptance of Interconnection Service Agreement (ISA)	Letter of credit for upgrade costs	Varies	37
Construction (only for new generation)	Upon acceptance of Interconnection Construction Service Agreement (ICSA)	None	Varies	NA

¹⁴ See letter from PJM to Secretary Kimberly Bose, Docket No. ER12-1177-000, <<http://www.pjm.com/~media/documents/ferc/2012-filings/20120229-er12-1177-000.ashx>>.

¹⁵ See PJM. Planning Committee "PJM Interconnection Queue Status & Statistics Update, Database Snapshot on 5/27/2015," at <<http://www.pjm.com/~media/committees-groups/committees/pc/20150611/20150611-item-09-queue-status-update.ashx>>

Manual 14B requires PJM to apply a commercial probability factor at the feasibility study stage to improve the accuracy of capacity and cost estimates. The commercial probability factor is based on the historical incidence of projects dropping out of the queue at the impact study stage.¹⁶ The impact and facilities studies are performed using the full amount of planned generation in the queues. The actual withdrawal rate is shown in Table 12-15. Disregarding projects still active or under construction, Table 12-15 shows the rate at which projects drop out of the queue as they move through the process. Out of 262,424 MW that entered the queue, 32,622 went into service, while the remaining 229,801 MW withdrew at some point. Of the withdrawals, 53.9 percent happened after the Feasibility study was completed, before proceeding to the next milestone.

Table 12-15 Completed (withdrawn or in service) queue MW (January 1, 1997 through June 30, 2015)

Milestone Completed	MW in Queue	Percent of Total in Queue	MW Withdrawn	Percent of Total Withdrawn
Enter Queue	262,424.1	100.0%	20,335.5	8.8%
Feasibility Study	242,088.6	92.3%	123,973.5	53.9%
System Impact Study	118,115.1	45.0%	48,040.5	20.9%
Facility Study	70,074.7	26.7%	22,860.8	9.9%
ISA/WMPA	47,213.9	18.0%	8,151.5	3.5%
CSA	39,062.4	14.9%	6,439.8	2.8%
In Service	32,622.6	12.4%	0.0	0.0%

Table 12-16 shows the milestone due when projects were withdrawn, for all withdrawn projects. Of the projects withdrawn, 48.1 percent were withdrawn before the Impact Study was completed. Once an Interconnection Service Agreement (ISA), or a Wholesale Market Participation Agreement (WMPA), is executed, the financial obligation for any necessary transmission upgrades cannot be retracted.^{17 18} As expected, withdrawing at or beyond this point is uncommon; 201 projects, or 12.4 percent, of all projects withdrawn were withdrawn after reaching this milestone.

¹⁶ See PJM Manual 14B. "PJM Region Transmission Planning Process," Revision 30 (February 26, 2015), p.70.

¹⁷ "Generators planning to connect to the local distribution systems at locations that are not under FERC jurisdiction and wish to participate in PJM's market need to execute a PJM Wholesale Market Participation Agreement (WMPA)..." instead of an ISA. See PJM Manual 14C. "Generation and Transmission Interconnection Facility Construction," Revision 08 (December 20, 2012), p.8.

¹⁸ See PJM Manual 14C. "Generation and Transmission Interconnection Facility Construction," Revision 08 (December 20, 2012), p.22.

Table 12-16 Last milestone completed at time of withdrawal (January 1, 1997 through June 30, 2015)

Milestone Completed	Projects Withdrawn	Percent
Never Started	171	10.6%
Feasibility Study	607	37.6%
Impact Study	532	32.9%
Facilities Study	105	6.5%
Interconnection Service Agreement (ISA)	37	2.3%
Wholesale Market Participation Agreement (WMPA)	110	6.8%
Construction Service Agreement (CSA) or beyond	54	3.3%
Total	1,616	100.0%

Table 12-17 and Table 12-18 show the time spent at various stages in the queue process and the completion time for the studies performed. For completed projects, there is an average time of 937 days, or 2.6 years, between entering a queue and going into service. Nuclear, hydro, and wind projects tend to take longer to go into service. The average time to go into service for all other fuel types is 700 days. For withdrawn projects, there is an average time of 658 days between entering a queue and withdrawing.

Table 12-17 Average project queue times (days): At June 30, 2015

Status	Average (Days)	Standard Deviation	Minimum	Maximum
Active	976	687	15	3,890
In Service	937	683	1	4,024
Suspended	1,987	765	509	4,149
Under Construction	1,787	906	428	6,380
Withdrawn	658	656	1	4,249

Table 12-18 presents information on the time in the stages of the queue for those projects not yet in service. Of the 577 projects in the queue as of June 30, 2015, 68 had a completed feasibility study and 191 were under construction.

Table 12-18 PJM generation planning summary: At June 30, 2015

Milestone Completed	Number of Projects	Percent of Total Projects	Average Days	Maximum Days
Not Started	130	22.5%	713	2,555
Feasibility Study	68	11.8%	780	2,223
Impact Study	85	14.7%	1,366	3,890
Facilities Study	21	3.6%	1,773	3,291
Interconnection Service Agreement (ISA)	13	2.3%	780	1,858
Wholesale Market Participation Agreement (WMPA)	1	0.2%	427	427
Construction Service Agreement (CSA)	1	0.2%	1,554	1,554
Under Construction	191	33.1%	1,787	6,380
Suspended	67	11.6%	1,987	4,149
Total	577	100.0%		

The time it takes to complete a study depends on the backlog and the number of projects in the queue. The time it takes to complete a study does not necessarily depend on the size of the project. Renewable projects (solar, hydro, storage, biomass, wind) account for 61.4 percent of the total number of projects in the queue but only 25.6 percent of the non-derated MW. See Table 12-19.

Table 12-19 Queue details by fuel group: At June 30, 2015

Fuel Group	Number of Projects	Percent of Projects	MW	Percent MW
Nuclear	6	1.0%	2,042.8	2.6%
Renewable	354	61.4%	19,806.5	25.6%
Traditional	217	37.6%	55,612.0	71.8%
Total	577	100.0%	77,461.3	100.0%

Role of Transmission Owners in Transmission Planning Study Phase

According to PJM Manual 14A, PJM, in coordination with the TOs, conducts the feasibility, system impact and facilities studies for every interconnection queue project. It is clear that the TOs perform the studies.¹⁹ The coordination begins with PJM identifying transmission issues resulting from the generation projects. The TOs perform the studies and provide the mitigation requirements for each issue. A facilities study is required only for new generation and significant generation additions and is the study in which the TO is most involved. For a facilities study, the interconnected TO (ITO), as well as any other affected TOs, is required to conduct their own facilities study and provide a summary and results to PJM. PJM compiles these results, along with inputs from the developer, into PJM's models to confirm that the TOs' defined upgrades will resolve the issue. PJM writes the final facilities report, which includes the inputs, a description of the issues to be resolved, and the findings of all contributing TOs.²⁰

Of 577 active projects analyzed, the developer and TO are part of the same company for 41 of the projects, or 11,390.5 MW of a total 59,225.2 MW, 19.2 percent of the MW. Where the TO is a vertically integrated company that also owns generation, there is a potential conflict of interest when the TO evaluates the interconnection requirements of new generation which is part of the same company. There is also a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is a competitor to the generation of its parent company.

Table 12-20 is a summary of the number of projects and total MW, by transmission owner parent company, which identifies the number of projects for which the developer and transmission owner are part of the same company. The Dominion Zone has eight related projects which account for 5,881.3 MW, 58.0 percent of the total MW currently in the queue in the Dominion Zone. Renewable projects comprise 3,075.6 MW, 72.1 percent, of unrelated projects in the queue in the Dominion Zone while natural gas projects total 5,465.3

MW, 53.9 percent of total MW in the queue. In contrast, the AEP Zone has 12 related projects, but they account for only 2.6 percent of its total MW currently in the queue.

Table 12-20 Summary of project developer relationship to transmission owner

Parent Company	Number of Projects			Total MW		
	Related	Unrelated	Percent Related	Related	Unrelated	Percent Related
AEP	12	73	14.1%	369.7	13,670.0	2.6%
AES	2	6	25.0%	32.0	437.3	6.8%
DLCO	0	1	0.0%		205.0	0.0%
Dominion	8	53	13.1%	5,881.3	4,265.6	58.0%
Duke	2	6	25.0%	52.0	660.4	7.3%
Exelon	7	66	9.6%	3,100.0	7,754.7	28.6%
First Energy	2	198	1.0%	1,736.0	21,169.8	7.6%
Pepco	0	80	0.0%		6,408.5	0.0%
PPL	0	26	0.0%		6,803.5	0.0%
PSEG	11	24	31.4%	1,923.1	2,992.4	39.1%
Total	44	533	7.6%	13,094.1	64,367.2	16.9%

These projects are shown by fuel type in Table 12-21. Natural gas generators comprise 69.6 percent of the total related MW in this table. Developers of coal and nuclear projects are almost entirely related to the TO, with 95.2 percent and 99.1 percent of MW. Developers are related to the TO for 17.2 percent of the natural gas project MW in the queue and 12.2 percent of the coal project MW. Wind and solar projects have no more than 1.0 percent of MW in development related to the TO.

¹⁹ See PJM, OATT, Part VI, § 210

²⁰ See PJM, "Manual 14A, "Generation and Transmission Interconnection Process," Revision 17, (January 22, 2015), < <http://www.pjm.com/documents/manuals.aspx>>

Table 12-21 Developer-transmission owner relationship by fuel type

Parent Company	Transmission Owner	Related to Developer	Number of Projects	MW by Fuel Type										Total MW		
				Biomass	Coal	Hydro	Landfill Gas	Natural Gas	Nuclear	Oil	Other	Solar	Storage		Wind	
AEP	AEP	Related	12		72.0	34.0			137.0	102.0			14.7	10.0		369.7
		Unrelated	73	45.0	92.0	12.5	23.8	6,019.0					103.7	62.0	7,312.0	13,670.0
AES	DAY	Related	2		12.0									20.0		32.0
		Unrelated	6	1.9		112.0							23.4		300.0	437.3
DLCO	DLCO	Unrelated	1					205.0								205.0
Dominion	Dominion	Related	8					4,275.3	1,594.0						12.0	5,881.3
		Unrelated	53	62.5			3.6	1,190.0					1,571.4	128.0	1,310.1	4,265.6
Duke	DEOK	Related	2		50.0									2.0		52.0
		Unrelated	6				6.4	513.0					125.0	16.0		660.4
Exelon	BGE	Related	1										20.0			20.0
		Unrelated	7	25.0		0.4	4.0	1.3				132.0	3.1			165.8
	ComEd	Unrelated	48			22.7	28.6	2,337.8					10.0	144.6	3,562.0	6,105.7
	PECO	Related	6					2,750.0	330.0							
Unrelated		11				3.2	1,480.0									1,483.2
First Energy	APS	Related	2		1,710.0			26.0								1,736.0
		Unrelated	55			68.2	9.2	4,865.9				184.3	31.0	723.6		5,882.2
	ATSI	Unrelated	12				2.5	4,071.9							518.0	4,592.4
	JCPL	Unrelated	83					3,034.0				574.1	180.0			3,788.1
	Met-Ed	Unrelated	8					1,336.6	16.8	401.0		3.0				1,757.4
	PENELEC	Unrelated	40			40.0	4.0	4,610.5				13.5	68.4	413.3		5,149.7
Pepco	AECO	Unrelated	22				0.3	1,571.0				73.2	20.0	373.0		2,037.5
	DPL	Unrelated	50				2.0	918.0				455.4	20.0	250.0		1,645.4
	Pepco	Unrelated	8					2,725.6								2,725.6
PPL	PPL	Unrelated	26	16.0		5.0	6,213.0					16.0	30.0	523.5		6,803.5
PSEG	PSEG	Related	11					1,922.1				1.0				1,923.1
		Unrelated	24					2,847.5				144.9				
Total		Related	44		1,844.0	34.0		9,110.4	2,026.0			15.7	32.0	12.0		13,074.1
		Unrelated	533	150.4	92.0	255.8	92.6	43,940.1	16.8	401.0	132.0	3,321.1	700.0	15,285.5		64,387.2

Regional Transmission Expansion Plan (RTEP)

PJM's Transmission Expansion Advisory Committee (TEAC), made up of PJM staff, is responsible for the Regional Transmission Expansion Plan (RTEP).²¹ Transmission upgrades can be divided into three categories: network, supplemental, and baseline. Network upgrades are initiated by generation queue projects and are funded by the developers of the generation projects. Supplemental upgrades are initiated and funded by the TOs. Baseline upgrades are initiated by the TEAC to resolve reliability criteria violations not addressed

in other ways. The costs of the baseline projects are allocated proportionally to all TOs who will benefit from the upgrade. The TEAC solicits proposals via fixed proposal windows to address these needs. The TEAC evaluates the proposals and recommends proposals to the PJM Board of Managers for approval. The TEAC typically makes these recommendations three times a year: in February, mid-summer and late fall.

On February 17, 2015, baseline projects with an estimated cost of \$551.4 million were presented to and approved by the Board. New projects account

²¹ See PJM Manual 14B. "PJM Region Transmission Planning Process," Revision 30 (February 26, 2015), Section 2, p.14

for \$474.4 million of this amount and adjustments to previously approved baseline projects were \$77.0 million.²² Table 12-22 shows a summary of the new baseline upgrade costs for each TO.

Table 12-22 2015 Board approved new baseline upgrades by transmission owner

Transmission Owner	Baseline Upgrades (\$ millions)
AEP	312.6
AP	1.7
ComEd	0.7
Dominion	118.0
EKPC	2.1
JCPL	14.8
Met-Ed	1.0
PECO	1.5
PENELEC	5.8
PPL	0.8
PSEG	15.6
Total	474.4

The 2015 RTEP Proposal Window 1 opened on June 19, 2015, and will close on July 20, 2015. The scope for these proposals includes baseline N-1, generation deliverability and common mode outage, N-1-1, and load deliverability.²³

Artificial Island Update

Artificial Island is an area in the PSEG Zone in southern New Jersey that includes nuclear units at Salem and at Hope Creek. On April 29, 2013, PJM issued a request for proposal (RFP), seeking technical solutions to improve stability issues, operational performance under a range of anticipated system conditions, and the elimination of potential planning criteria violations in this area. PJM received 26 individual proposals from seven entities, including proposals from the incumbent transmission owner, PSEG, and from non-incumbents. PJM staff announced on April 28, 2015, that they will recommend that the Board approve the assignment of the Artificial Island project to LS Power, a non-incumbent, PSEG, and PHI with a total cost estimate between \$263M and \$283M. Table 12-23 shows the details of the project allocation.

²² See PJM Staff Whitepaper, "Transmission Expansion Advisory Committee (TEAC) Recommendations to the PJM Board," <<http://www.pjm.com/-/media/committees-groups/committees/teac/20150409/20150409-february-2015-board-approval-of-rtep-whitepaper.ashx>>

²³ See TEAC webcast, June 24, 2015 at <<http://mediastream.pjm.com/2015/0624/teac/2015-rtep-proposal/index.htm>>

Table 12-23 Artificial Island recommended work and cost allocation

Project Task	Designated Developer	Cost Estimate (\$ million)
230kV transmission line under the Delaware River from Salem to a new substation near the 230kV transmission RoW in Delaware utilizing HDD under the river	LS Power	146.0 (cost cap)
Associated substation work at Salem	PSEG	61.0-74.0
Associated work on the 230kV RoW	PHI	
SVC at New Freedom	PSEG	31.0-38.0
OPGW upgrades designated to PSEG and PHI & Artificial Island GSU tap settings upgrade	PSEG	25.0
Total		263.0-283.0

PJM received comments from PSEG & PSEG Nuclear, contesting the selection of LS Power for the construction of a 230kV line over the PSEG proposal. They argued that the PSEG proposal was inappropriately modified, resulting in a higher cost and a lower score and that several performance factors, including stability, installation complexity, long term maintenance and operational costs, and operational complexity were excluded. PSEG also argued that LS Power's cost cap is misleading and was misinterpreted by PJM staff to be more robust than it actually is. Atlantic Grid Holdings also questioned the robustness of the recommended design. The Delaware Riverkeeper Network raised environmental concerns.

On July 30, 2015, the PJM Board of Managers accepted PJM's recommendation.²⁴

The inclusion of a cost cap in some of the offers and the inclusion of a cost cap in the decision criteria is an important step in the development of meaningful competition to build transmission projects. Such cost caps should include minimum exceptions and be enforceable.

Cost Estimates and Allocations

Con Edison and Linden VFT

Following the RTEP Baseline upgrade filings, ER14-972-000 on January 10, 2014, and ER14-1485-000 on March 13, 2014, Con Edison and Linden VFT took issue with their cost allocations for two specific upgrades (Bergen-Linden

²⁴ See PJM, "Artificial Island Project," July 29, 2015 <<http://www.pjm.com/-/media/documents/reports/board-statement-on-artificial-island-project.ashx>>

Corridor and Sewaren.) Both filed complaints (ConEd on November 7, 2014, and Linden on May 22, 2015) that the allocations violated Schedule 12 of the tariff and Schedule 6 of the PJM Operating Agreement, which address unreasonable cost allocations. Schedule 12 of the tariff states “If Transmission Provider determines in its reasonable engineering judgment that, as a result of applying the provisions of this Section (b)(iii), the DFAX analysis cannot be performed or that the results of such DFAX analysis are objectively unreasonable, the Transmission Provider may use an appropriate substitute proxy for the Required Transmission Enhancement in conducting the DFAX analysis.” Schedule 6 of the PJM Operating Agreement requires PJM to avoid an allocation of unreasonable costs in the RTEP project selection process.^{25 26} Finally, Order 1000 states that “costs must be allocated in a way that is roughly commensurate with benefits.”²⁷

ConEd argued, using the tariff language, that the cost allocation is “objectively unreasonable” and requested “an appropriate substitute proxy.” ConEd’s complaint was not that the solution-based DFAX method was necessarily faulty, but that the assumptions and inputs that PJM used to model ConEd were inaccurate and resulted in an over allocation to ConEd, Linden VFT, and Hudson Transmission Partners (HTP), and an under allocation to PSEG. PJM’s response was that the substitute proxy was to be used when a DFAX could not otherwise be calculated, which did not apply in this case.²⁸ PJM also argued that ConEd had a chance to question the cost allocation during numerous TEAC meetings. ConEd replied that detailed information was not made available and thus ConEd was not aware of the significant allocation at that point. PSEG commented in support of the allocation. The FERC decision on June 18, 2015, accepted the PJM allocation and found that the DFAX method, as applied, was not faulty.²⁹

Linden VFT commented in support of ConEd’s complaint and filed a separate complaint on May 22, 2015.³⁰ In addition to the two upgrades that were the focus of the ConEd complaint, Linden added a third (Edison Rebuild).

²⁵ See PJM, Intra-PJM Tariffs, OATT, Schedule 12 § (b)(iii)(G)

²⁶ See PJM Operating Agreement, § 1.4(d)(ii)

²⁷ See FERC Order 1000-B, §3, Paragraph 66

²⁸ See PJM, Intra-PJM Tariffs, OATT, Schedule 12 § (b)(iii)(I)

²⁹ See 151 FERC ¶ 61,227 (2015). <<http://www.pjm.com/~media/documents/ferc/2015-orders/20150618-er14-972-002.ashx>>.

³⁰ See “Motion for Leave to Answer and Limited Answer of Linden VFT, LLC,” Docket No. EL15-18-000 (November 19, 2014)

The allocations in dispute were a result of a new approach to transmission upgrade cost allocation, applied for the first time to the transmission costs resulting from the 2013 RTEP.³¹ Linden VFT argued that the DFAX calculations assume peak conditions and therefore maximum firm transmission withdrawal rights (FTWRs), but during peak periods, Linden VFT is least likely to use its full FTWRs because the flow is going in the other direction.³²

Artificial Island

After the Artificial Island recommendation was presented by PJM Staff on April 28, 2015, Delaware Public Service Commission, Delaware Division of the Public Advocate, Old Dominion Electric Cooperative (ODEC), the Maryland Public Service Commission (MD PSC), and Delaware Governor Jack Markell raised concerns regarding the allocation of 99.9 percent of the costs for the 230kV line portion of the Artificial Island project to PHI.³³

TransSource

TransSource LLC stated, in a complaint filed on June 23, 2015, that PJM is not being transparent with respect to the development of its cost estimates in the System Impact Study (SIS) phase of three TransSource queue projects. TransSource seeks an order directing PJM to provide data and working papers related to the SIS sufficient to fully evaluate the basis of cost estimates that TransSource considers excessive. PJM responded that it has provided all work papers relevant to the SIS and objects to the complaint on procedural grounds.³⁴

³¹ See *PJM Interconnection, LLC*, 142 FERC ¶ 61,214 (2013)

³² See “Complaint and Request for Fast Track Processing of Linden VFT, LLC,” Docket no. EL15-67-000 (May 22, 2015)

³³ See PJM Board Communications. Responses at <<http://www.pjm.com/about-pjm/who-we-are/pjm-board/public-disclosures.aspx>>

³⁴ See Motion to Dismiss Complaint and Answer to Complaint Submitted on Behalf of PJM Interconnection, LLC., Docket No. EL15-79-000 (July 10, 2015).

Backbone Facilities

PJM backbone projects are a subset of baseline upgrade projects that have been given the informal designation of backbone due to their relative significance. Backbone upgrades are on the extra high voltage (EHV) system and resolve a wide range of reliability criteria violations and market congestion issues. The current backbone projects are Mount Storm-Doubs, Jacks Mountain, Susquehanna-Roseland, and Surry Skiffes Creek 500kV. Figure 12-3 shows the location of these four projects.

Figure 12-3 PJM Backbone Projects



The Mount Storm-Doubs transmission line, which serves West Virginia, Virginia, and Maryland, was originally built in 1966. The structures and equipment are approaching the end of their expected service life and require replacement to ensure reliability. The first two phases, the line rebuild and the energizing of the Mount Storm switchyard, are complete. Construction plans for Phase 3, consisting of additional upgrades to the Mount Storm switchyard, are under development. Completion of this phase is expected by the end of 2015.³⁵

³⁵ See Dominion "Mt. Storm-Doubs," which can be accessed at: <<http://www.pjm.com/planning/rtep-upgrades-status/backbone-status/mount-storm-doubs.aspx>>

The Jacks Mountain project is required to resolve voltage problems for load deliverability starting June 1, 2017. Jacks Mountain will be a new 500kV substation connected to the existing Conemaugh-Juniata and Keystone-Juniata 500kV circuits. This project is currently in the engineering and design phase. Transmission foundations are planned for fall 2015. Below grade construction of the sub-station is scheduled to be completed by September 2016, and above grade, relay/control construction, is planned for October 2016-June 2017.³⁶

The Susquehanna-Roseland project is required to resolve reliability criteria violations starting June 1, 2012. Susquehanna-Roseland is a new 101-mile 500 kV transmission line connecting the Susquehanna, Lackawanna, Hopatcong, and Roseland buses. PPL is responsible for the first two legs and PSEG for the third. The Susquehanna-Lackawanna portion went into service on September 23, 2014, and the Lackawanna-Hopatcong portion was energized on May 11, 2015. The Hopatcong - Roseland leg was placed in service on April 1, 2014.³⁷ This project is now complete.

The Surry Skiffes Creek 500kV was initiated in the fall of 2014 to relieve the overload of the James River Crossing Double Circuit Towerline anticipated to result from the retirement of Chesapeake units 1-4, which occurred in December 2014, and Yorktown 1, which is pending. It will include a new 7.7 mile 500kV line between Surry and Skiffes, a new 20.25 mile 230kV line between Skiffes Creek and Whealton, and a new Skiffes Creek 500/230kV switching station. PJM's required in service date for the 500kv portion was June 1, 2015. This project has been delayed by legal challenges. BASF Corporation raised environmental concerns with the siting and the design. James City County and James River Association (JCC) argued that the switching station is not part of the transmission line and therefore should be subject to local zoning ordinances. In an April 16, 2015, ruling, the Supreme Court of Virginia rejected BASF's claim but agreed with JCC.³⁸ On April 30, 2015, Dominion filed a petition for rehearing and will wait for the follow-

³⁶ See "Jacks Mountain," which can be accessed at: <<http://www.pjm.com/planning/rtep-upgrades-status/backbone-status/jacks-mountain.aspx>>.

³⁷ See "Susquehanna-Roseland," which can be accessed at: <<http://www.pjm.com/planning/rtep-upgrades-status/backbone-status/susquehanna-roseland.aspx>>.

³⁸ BASF Corporation v SCC, et al., Record No. 141009 et al.

up ruling before they will begin construction but they are proceeding with the planning.³⁹ Dominion anticipates beginning construction in the summer of 2015 and expects to energize both the 230kV line and the 500kV line by January 31, 2017.⁴⁰

Transmission Facility Outages

Scheduling Transmission Facility Outage Requests

PJM designates some transmission facilities as reportable. A transmission facility is reportable if a change in its status can affect a transmission constraint on any Monitored Transmission Facility or could impede free-flowing ties within the PJM RTO and/or adjacent areas. If a transmission facility is not modeled in the PJM EMS or the facility is not expected to significantly impact PJM system security or congestion management, it is not reportable.⁴¹ When one of the reportable transmission facilities needs to be taken out of service, the TO is required to submit an outage request as early as possible. The outages are categorized by duration: greater than 30 calendar days; less than or equal to 30 calendar days and greater than five calendar days; or less than or equal to five calendar days. Table 12-24 shows that 78.5 percent of the requested outages were planned for five days or shorter and 5.3 percent of requested outages were planned for longer than 30 days in the first six months of 2015. All of the outage data in this section are for outages scheduled to occur in the first six months of 2015, regardless of when they were initially submitted.

Table 12-24 Transmission facility outage request summary by planned duration: January through June of 2014 and 2015

Planned Duration (Days)	2014 (Jan - Jun)		2015 (Jan - Jun)	
	Outage Requests	Percent	Outage Requests	Percent
<=5	8,039	79.8%	8,279	78.5%
>5 <=30	1,537	15.3%	1,705	16.2%
>30	493	4.9%	564	5.3%
Total	10,069	100.0%	10,548	100.0%

39 See "Surry-Skiffes Creek 500kV," which can be accessed at: <<http://www.pjm.com/planning/rtep-upgrades-status/backbone-status/surry-skiffes-creek.aspx>>

40 See "Surry-Skiffes Creek 500kV and Skiffes Creek-Wheaton 230kV Projects," which can be accessed at: <<https://www.dom.com/corporate/what-we-do/electricity/transmission-lines-and-projects/surry-skiffes-creek-500kv-and-skiffes-creek-wheaton-230kv-projects>>.

41 See PJM. "Manual 3a: Energy Management System (EMS) Model Updates and Quality Assurance (QA), Revision 9 (January 22, 2015).

After receiving a transmission facility outage request from a TO, PJM assigns a received status to the request, based on its submission date, outage planned starting and ending date, and outage planned duration. The received status can be on time, late or past deadline, as defined in Table 12-25.⁴² The purpose of the rules is to require the TOs to submit transmission facility outages prior to the Financial Transmission Right ("FTR") auctions so that market participants have complete information on which to base their FTR bids.⁴³

Table 12-25 PJM transmission facility outage request received status definition

Planned Duration (Days)	Ticket Submission Date	Received Status
<=5	Before the 1st of the month one month prior to the starting month of the outage	On Time
	After or on the 1st of the month one month prior to the starting month of the outage	Late
	After 8:00AM three days prior to the outage	Past Deadline
> 5 <=30	Before the 1st of the month six months prior to the starting month of the outage	On Time
	After or on the 1st of the month six months prior to the starting month of the outage	Late
	After 8:00AM three days prior to the outage	Past Deadline
>30	The earlier of either February 1st or the 1st of the month six months prior to the starting month of the outage	On Time
	After or on the earlier of either February 1st or the 1st of the month six months prior to the starting month of the outage	Late
	After 8:00AM three days prior to the outage	Past Deadline

Table 12-26 shows a summary of requests by received status. In the first six months of 2015, 52.8 percent of outage requests received were late.

Table 12-26 Transmission facility outage request summary by received status: January through June of 2014 and 2015

Planned Duration (Days)	2014 (Jan - Jun)				2015 (Jan - Jun)			
	On Time	Late	Total	Percent Late	On Time	Late	Total	Percent Late
<=5	4,214	3,825	8,039	52.4%	4,545	3,734	8,279	54.9%
>5 <=30	771	766	1,537	50.2%	846	859	1,705	49.6%
>30	172	321	493	34.9%	183	381	564	32.4%
Total	5,157	4,912	10,069	51.2%	5,574	4,974	10,548	52.8%

42 See "PJM. "Manual 3: Transmission Operations," Revision 46 (December 1, 2014), p.58.

43 See 97 FERC ¶ 61,010 (October 3, 2001).

Once received, PJM processes the request according to its priority, which is determined by its submission date. If a request has an emergency flag, it has the highest priority and will be approved even if submitted past its deadline. Table 12-27 is a summary of outage requests by emergency status. Of all outage requests submitted in the first six months of 2015, 13.0 percent were for emergency outages.

Table 12-27 Transmission facility outage request summary by emergency: January through June of 2014 and 2015

Planned Duration (Days)	2014 (Jan - Jun)				2015 (Jan - Jun)			
	Emergency	Non Emergency	Total	Percent Emergency	Emergency	Non Emergency	Total	Percent Emergency
<=5	1,238	6,801	8,039	15.4%	1,069	7,210	8,279	12.9%
>5 <=30	200	1,337	1,537	13.0%	237	1,468	1,705	13.9%
>30	89	404	493	18.1%	63	501	564	11.2%
Total	1,527	8,542	10,069	15.2%	1,369	9,179	10,548	13.0%

A late outage request may be denied or cancelled by PJM if it is expected to cause congestion based on PJM's analysis. Table 12-28 is a summary of outage requests by congestion status. Of all outage requests submitted in the first six months of 2015, 9.6 percent were expected to cause congestion and the percentage of outage requests flagged for congestion is similar across the categories of planned duration.

Table 12-28 Transmission facility outage request summary by congestion: June of 2014 and 2015

Planned Duration (Days)	2014 (Jan - Jun)				2015 (Jan - Jun)			
	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
<=5	679	7,360	8,039	8.4%	766	7,513	8,279	9.3%
>5 <=30	148	1,389	1,537	9.6%	188	1,517	1,705	11.0%
>30	44	449	493	8.9%	57	507	564	10.1%
Total	871	9,198	10,069	8.7%	1,011	9,537	10,548	9.6%

Table 12-29 shows the outage requests summary by received status, congestion status and emergency status. In the first six months of 2015, 72.6 percent of late requests were non-emergency outages while 4.8 percent of late non-emergency outage requests were expected to cause congestion in the first six months of 2015.

Table 12-29 Transmission facility outage requests that by received status, congestion and emergency: January through June of 2014 and 2015

Submission Status		2014 (Jan - Jun)				2015 (Jan - Jun)			
		Congestion Expected	No Congestion Expected	Total	Percent Congestion	Congestion Expected	No Congestion Expected	Total	Percent Congestion
Late	Emergency	44	1,475	1,519	2.9%	55	1,308	1,363	4.0%
	Non Emergency	167	3,226	3,393	4.9%	172	3,439	3,611	4.8%
On Time	Emergency	0	8	8	0.0%	0	6	6	0.0%
	Non Emergency	660	4,489	5,149	12.8%	784	4,784	5,568	14.1%
	Total	871	9,198	10,069	8.7%	1,011	9,537	10,548	9.6%

Once PJM processes an outage request, the outage request is labelled as submitted, received, denied, approved, cancelled by company, revised, active or complete according to the processed stage of a request.⁴⁴ Table 12-30 shows the detailed process status for outage requests only for the outage requests that are expected to cause congestion. All process status categories except cancelled, complete or denied are in the In Process category in Table 12-30. Table 12-30 shows that 62.8 percent of late, non-emergency, outage requests which were expected to cause congestion were approved and completed and 6.6 (67 out of 1,011) percent of the outage requests which were expected to cause congestion were denied in the first six months of 2015.

Table 12-30 Transmission facility outage requests that might cause congestion status summary: January through June of 2014 and 2015

Submission Status		2014 (Jan - Jun)						2015 (Jan - Jun)					
		Cancelled	Complete	In Process	Denied	Congestion Expected	Percent Complete	Cancelled	Complete	In Process	Denied	Congestion Expected	Percent Complete
Late	Emergency	2	41	1	0	44	93.2%	7	47	0	1	55	85.5%
	Non Emergency	29	117	1	20	167	70.1%	38	108	2	24	172	62.8%
On Time	Non Emergency	133	485	1	41	660	73.5%	223	516	3	42	784	65.8%
	Total	164	643	3	61	871	73.8%	268	671	5	67	1,011	66.4%

Rescheduling Transmission Facility Outage Requests

A TO can reschedule or cancel an outage after initial submission. Table 12-31 is a summary of all the outage requests planned for the first six months of 2014 and 2015 which were approved and then cancelled or revised by TOs at least once. In the first six months of 2015, 2.7 percent of transmission outage requests were approved by PJM and then revised by the TOs, and 12.9 percent of the transmission outages were approved by PJM and subsequently cancelled by the TOs.

Table 12-31 Rescheduled transmission outage request summary: January through June of 2014 and 2015

Days	Outage Requests	2014 (Jan - Jun)				2015 (Jan - Jun)				
		Approved and Revised	Percent Approved and Revised	Approved and Cancelled	Percent Approved and Cancelled	Outage Requests	Approved and Revised	Percent Approved and Revised	Approved and Cancelled	Percent Approved and Cancelled
<=5	8,039	270	3.4%	1,173	14.6%	8,279	207	2.5%	1,186	14.3%
>5 <=30	1,537	68	4.4%	116	7.5%	1,705	54	3.2%	129	7.6%
>30	493	14	2.8%	30	6.1%	564	25	4.4%	50	8.9%
Total	10,069	352	3.5%	1,319	13.1%	10,548	286	2.7%	1,365	12.9%

All late rescheduled outages are reevaluated by PJM. An on-time transmission outage ticket with duration of five days or less with an on-time status can retain its on-time status if the outage is rescheduled within the original scheduled month.⁴⁵ This rule allows a TO to move an outage to an earlier date than originally requested within the same month with very little notice.

An on-time transmission outage ticket with duration exceeding five days can retain its on-time status if the outage is moved to a future month, and the revision is submitted by the first of the month prior to the month in which new proposed outage will occur.⁴⁶ This rescheduling rule is much less strict than the rule that

⁴⁴ PJM. Markets and Operations. "Outage Information," <<http://www.pjm.com/markets-and-operations/etools/oasis/system-information/outage-info.aspx>>

⁴⁵ PJM. "Manual 3: Transmission Outages," Revision 46 (December 1, 2014), p. 63.

⁴⁶ PJM. "Manual 3: Transmission Outages," Revision: 46 (December 1, 2014), p. 64.

applies to the first submission of outage requests with similar duration. When first submitted, the outage request planned to last longer than five days needs to be submitted the first of the month six months prior to the month in which the outage was expected to occur.

These rules mean that an outage, once approved, acts as a reservation that does not require further review and allows rescheduling without review.

The MMU recommends that PJM reevaluate all transmission outage tickets as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages.

Transmission Facility Outage Analysis for the FTR Market

Transmission facility outages affect the price and quantity outcomes of FTR auctions. It is critical that outages are known with enough lead time prior to FTR auctions both so that market participants can understand market conditions and so that PJM can accurately model market conditions. Outage requests must be submitted according to rules based on planned outage duration (Table 12-25). The rules defining when an outage is late are based on the timing of FTR auctions. When an outage request is submitted late, the outage will be marked as late and may be denied if it is expected to cause congestion.

There are Long Term, Annual and Monthly Balance of Planning Period auctions in the FTR market. When modeling transmission outages in the annual ARR allocation and FTR auction, PJM does not consider outages with planned duration shorter than two weeks, does consider some outages with planned duration longer than two weeks but shorter than two months, and does consider all outages with planned duration longer than or equal to two months. PJM posts an FTR outage list to the FTR web page usually at least one week before the auction bidding opening day.⁴⁷

⁴⁷ PJM. 2015-2016 Annual ARR Allocation and FTR Auction Transmission Outage Modeling <<http://www.pjm.com/~media/markets-ops/ftr/annual-ftr-auction/2015-2016/2015-2016-annual-outage-modeling.ashx>>

Table 12-32 shows that 89.9 percent of the outage requests for outages expected to occur during the planning period 2014 to 2015 were planned for less than two weeks and that 47.7 percent of all outage requests for the planning period were submitted late according to outage submission rules.

Table 12-32 Transmission facility outage requests by received status: Planning period 2014 to 2015

Planned Duration	On Time	Late	Total	Percent Late
<2 weeks	9,300	8,346	17,646	47.3%
>=2 weeks & <2 months	805	821	1,626	50.5%
>=2 months	155	192	347	55.3%
Total	10,260	9,359	19,619	47.7%

Once received, PJM processes outage requests in the following priority order: emergency transmission outage request, transmission outage requests submitted On Time, and transmission submitted Late. If two outage requests submitted by different transmission owners are expected to occur during the same period, the outage submitted first is processed first by PJM. If a request has an emergency flag, it has the highest priority and will be approved even if submitted past its deadline after PJM determines that the outage does not result in Emergency Procedures.⁴⁸ Table 12-33 shows outage requests summary by emergency status. Of all outage requests submitted late in the 2014 to 2015 planning year, 72.7 percent were for non-emergency outages.

Table 12-33 Transmission facility outage requests by received status and emergency: Planning period 2014 to 2015

Planned Duration	On Time			Late		
	Emergency	Non Emergency	Percent Non Emergency	Emergency	Non Emergency	Percent Non Emergency
<2 weeks	13	9,287	99.9%	2,363	5,983	71.7%
>=2 weeks & <2 months	0	805	100.0%	155	666	81.1%
>=2 months	0	155	100.0%	35	157	81.8%
Total	13	10,247	99.9%	2,553	6,806	72.7%

⁴⁸ PJM. "Manual 3: Transmission Outages," Revision: 46 (December 1, 2014), p. 67 and p.68.

PJM analyzes expected congestion for both on time and late outage requests. A late outage request may be denied or cancelled if it is expected to cause congestion. Table 12-34 shows a summary of requests by congestion flag and received status. Overall, 5.3 percent of all tickets submitted late in the 2014 to 2015 planning year were requests that might cause congestion.

Table 12-34 Transmission facility outage requests by received status and congestion: Planning period 2014 to 2015

Planned Duration	On Time				Late			
	Congestion Expected	No Congestion Expected	Percent	Congestion Expected	Congestion Expected	No Congestion Expected	Percent	Congestion Expected
<2 weeks	1,334	7,966		14.3%	445	7,901		5.3%
>=2 weeks & <2 months	160	645		19.9%	43	778		5.2%
>=2 months	32	123		20.6%	6	186		3.1%
Total	1,526	8,734		14.9%	494	8,865		5.3%

Table 12-35 shows that 86.5 percent of late outage requests with a duration of two weeks or longer but shorter than two months were completed and that 86.5 percent of late outage requests with a duration of two months or longer were completed.

Table 12-35 Transmission facility outage requests by received status and processed status: Planning period 2014 to 2015

Planned Duration	Processed Status	On Time	Percent	Late	Percent
<2 weeks	In Process	23	0.2%	166	2.0%
	Denied	106	1.1%	91	1.1%
	Cancelled by Company	2,766	29.7%	1,193	14.3%
	Completed	6,405	68.9%	6,895	82.6%
Total		9,300	100.0%	8,345	100.0%
>=2 weeks & <2 months	In Process	1	0.1%	9	1.1%
	Denied	0	0.0%	2	0.2%
	Cancelled by Company	194	24.1%	100	12.2%
	Completed	610	75.8%	710	86.5%
Total		805	100.0%	821	100.0%
>=2 months	In Process	0	0.0%	7	3.6%
	Denied	0	0.0%	0	0.0%
	Cancelled by Company	38	24.5%	19	9.9%
	Completed	117	75.5%	166	86.5%
Total		155	100.0%	192	100.0%

Table 12-36 shows outage requests in more detail. It shows that there were 821 outage requests with a duration of two weeks or longer but shorter than two months were submitted late, of which 40 were non-emergency and expected to cause congestion in the 2014 to 2015 planning year. Of the 40 such requests, 33 were approved and completed. For the outages planned for two months or longer, there are 347 total outages, of which 192 requests were late. The six outages that were non-emergency and expected to cause congestion were all approved and completed.

Table 12-36 Transmission facility outage requests by received status, processed status, emergency and congestion: Planning period 2014 to 2015

Planned Duration	Processed Status	On time					Late				
		Emergency		Non Emergency		Total	Emergency		Non Emergency		Total
		Congestion Expected		Congestion Expected			Congestion Expected		Congestion Expected		
Yes	No	Yes	No		Yes	No	Yes	No			
<2 weeks	In Progress	0	0	2	21	23	0	77	3	86	166
	Denied	0	0	72	34	106	1	8	39	43	91
	Cancelled by Company	1	1	362	2,402	2,766	9	133	75	977	1,194
	Completed	0	11	897	5,497	6,405	96	2,039	222	4,538	6,895
Total Submission	1	12	1,333	7,954	9,300	106	2,257	339	5,644	8,346	
>=2 weeks & <2 months	In Progress	0	0	1	0	1	0	4	0	5	9
	Denied	0	0	0	0	0	0	0	2	0	2
	Cancelled by Company	0	0	30	164	194	0	5	5	90	100
	Completed	0	0	129	481	610	3	143	33	531	710
Total Submission	0	0	160	645	805	3	152	40	626	821	
>=2 months	In Progress	0	0	0	0	0	0	1	0	6	7
	Denied	0	0	0	0	0	0	0	0	0	0
	Cancelled by Company	0	0	3	35	38	0	1	0	18	19
	Completed	0	0	29	88	117	0	33	6	127	166
Total Submission	0	0	32	123	155	0	35	6	151	192	

If an outage request were submitted after the Annual FTR Auction bidding opening date, the outage would not be considered in the FTR model. If an outage were submitted on-time according to the transmission outage rules, it may not be modeled in the FTR model if it is submitted after the Annual FTR Auction bidding opening date. Table 12-38 shows that 84.0 percent of outage requests labelled on time according to rules were submitted after the annual FTR bidding opening date.

Table 12-37 Transmission facility outage requests by submission status and bidding opening date: Planning period 2014 to 2015

Planned Duration	On Time			Late		
	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After
<2 weeks	1,040	8,260	88.8%	78	8,267	99.1%
>=2 weeks & <2 months	475	330	41.0%	77	744	90.6%
>=2 months	127	28	18.1%	18	174	90.6%
Total	1,642	8,618	84.0%	173	9,185	98.2%

Table 12-38 shows that 83.1 percent of late outage requests which were submitted after the Annual FTR Auction bidding opening date were approved and complete.

Thus, although the definition of late outages was developed in order to prevent outages for the planning period being submitted after the Annual FTR Auction bidding opening date, the rules have not worked to prevent this.

Table 12-38 Late transmission facility outage requests that are submitted after annual bidding opening date: Planning period 2014 to 2015

Planned Duration	Completed Outages	Total	Percent
<2 weeks	6,837	8,267	82.7%
>=2 weeks & <2 months	650	744	87.4%
>=2 months	150	174	86.2%
Total	7,637	9,185	83.1%

Transmission Facility Outage Analysis in the Day-Ahead Market

Transmission facility outages also affect the energy market. Just as with the FTR market, it is critical that outages that affect the operating day are known prior to the submission of offers in the Day-Ahead Energy Market both so that market participants can understand market conditions and so that PJM can accurately model market conditions.

There may be more than one instance for each outage request due to the change of the processed status. PJM maintains all the history of outage requests including all the processed status changes and all the starting or ending date changes. For example, if an outage requested were submitted, received, approved and completed, the four occurrences, termed instances, of the outage request will be stored in the database. In the day-ahead market transmission outage analysis, all instances of the outages planned in the 2014/2015 planning year are included. Table 12-39 shows that 14.6 percent of non-emergency outage request instances were submitted late for the day-ahead market and were expected to cause congestion.

Table 12-39 Transmission facility outage request instance summary by congestion and emergency: Planning period 2014 to 2015

For Day-ahead Market	Submission Status	Congestion		Total	Percent Congestion
		Expected	No Congestion Expected		
Late	Emergency	310	3,916	4,226	7.3%
	Non Emergency	2,677	15,682	18,359	14.6%
On Time	Emergency	816	11,101	11,917	6.8%
	Non Emergency	15,197	88,362	103,559	14.7%
	Total	19,000	119,061	138,061	13.8%

Table 12-40 shows that there were 22,585 instances related to outage requests which were expected to occur in the planning period 2014 to 2015, of which 3,043 (13.5 percent) had the status submitted, cancelled by company or revised and 205 (0.9 percent) had the status submitted, cancelled by company or revised and were expected to cause congestion.

Table 12-40 Transmission facility outage request instance status summary by congestion and emergency: Planning period 2014 to 2015

Processed Status	Late For Day-ahead Market					On Time For Day-ahead Market				
	Emergency Congestion Expected		Non Emergency Congestion Expected		Total	Emergency Congestion Expected		Non Emergency Congestion Expected		Total
	Yes	No	Yes	No		Yes	No	Yes	No	
Submitted	24	984	71	668	1,747	113	1,515	2,292	15,835	19,755
Cancelled by Company	8	41	86	703	838	8	132	593	4,273	5,006
Revised	14	131	48	265	458	215	3,649	2,678	13,927	20,469
Total	46	1,156	205	1,636	3,043	336	5,296	5,563	34,035	45,230
Other	264	2,760	2,472	14,046	19,542	480	5,805	9,634	54,327	70,246
Total	310	3,916	2,677	15,682	22,585	816	11,101	15,197	88,362	115,476

