

Generation and Transmission Planning

Overview

Planned Generation and Retirements

- **Planned Generation.** As of December 31, 2016, 101,473.5 MW of capacity were in generation request queues for construction through 2024, compared to an average installed capacity of 193,407.0 MW as of December 31, 2016. Of the capacity in queues, 13,110.5 MW, or 12.9 percent, are uprates and the rest are new generation. Wind projects account for 14,656.8 MW of nameplate capacity or 14.4 percent of the capacity in the queues. Combined cycle projects account for 69,264.4 MW of capacity or 68.3 percent of the capacity in the queues.
- **Generation Retirements.** As shown in Table 12-5, 29,057.5 MW have been, or are planned to be, retired between 2011 and 2020. Of that, 4,965.3 MW are planned to retire after 2016. In 2016, 395.5 MW were retired. Of the 4,965.3 MW pending retirement, 3,649.0 MW are coal units. The coal unit retirements were a result of low gas prices, low capacity prices and the investments required for compliance with the EPA's Mercury and Air Toxics Standards (MATS) for some units.
- **Generation Mix.** A significant shift in the distribution of unit types within the PJM footprint continues as natural gas fired units enter the queue and steam units retire. There are 277.0 MW of coal fired steam capacity and 69,264.4 MW of gas fired capacity in the queue. The replacement of coal steam units by units burning natural gas will significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

Generation and Transmission Interconnection Planning Process

- Any entity that requests interconnection of a new generating facility, including increases to the capacity of an existing generating unit, or that requests interconnection of a merchant transmission facility, must follow the process defined in the PJM tariff to obtain interconnection service.¹ The process

is complex and time consuming at least in part as a result of the required analyses. The cost, time and uncertainty associated with interconnecting to the grid may create barriers to entry for potential entrants.

- The queue contains a substantial number of projects that are not likely to be built. Excluding currently active projects and projects currently under construction, 3,293 projects, representing 453,810.1 MW, have entered the queue process since its inception. Of those, 687 projects, 46,436.0 MW, went into service. Of the projects that entered the queue process, 67.4 percent of the MW withdrew prior to completion. Such projects may create barriers to entry for projects that would otherwise be completed by taking up queue positions, increasing interconnection costs and creating uncertainty.
- Feasibility, impact and facilities studies may be delayed for reasons including disputes with developers, circuit and network issues and retooling as a result of projects being withdrawn. The Earlier Queue Submittal Task Force (EQSTF) was established in August 2015 to address delays.² On May 12, 2016, The EQSTF presented proposed rule changes to the interconnection process. These changes were filed with FERC, and FERC approved the changes, and the PJM Open Access Transmission Tariff was modified effective October 31, 2016.
- A transmission owner (TO) is an "entity that owns, leases or otherwise has a possessory interest in facilities used for the transmission of electric energy in interstate commerce under the tariff."³ Where the transmission owner is a vertically integrated company that also owns generation, there is a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is a competitor to the generation of the parent company and when the transmission owner evaluates the interconnection requirements of new generation which is part of the same company as the transmission owner. There is also a potential conflict of interest when the transmission owner evaluates the interconnection requirements of a merchant transmission developer which is a competitor of the transmission owner.

¹ See PJM, OATT Parts IV & VI.

² See Earlier Queue Submittal Task Force at <<http://www.pjm.com/committees-and-groups/task-forces/eqstf.aspx>>.

³ See PJM, OATT, Part I, § 1 "Definitions."

Regional Transmission Expansion Plan (RTEP)

- Artificial Island is an area in southern New Jersey that includes nuclear units at Salem and at Hope Creek in the PSEG Zone. On April 29, 2013, PJM issued a request for proposal (RFP), seeking technical solutions to improve stability issues and operational performance under a range of anticipated system conditions, and the elimination of potential planning criteria violations in this area. On July 30, 2015, the PJM Board of Managers accepted PJM's recommendation to assign the project to LS Power, a merchant developer, PSEG, and PHI with a total cost estimate between \$263M and \$283M.^{4,5} On August 5, 2016, PJM announced that the Artificial Island project was to be suspended immediately due to unanticipated project complexities and significant cost overruns. The PJM Board of Managers called for a new review of the project to be completed by PJM by February 2017 in order to assess how to proceed with the project.⁶
- On October 25, 2012, Schedule 12 of the tariff and Schedule 6 of the OA were changed to address FERC Order No. 1000 reforms to the cost allocation requirements for local and regional transmission planning projects that were formerly defined in Order No. 890. The new approach was applied for the first time to the 2013 RTEP. The allocation process has been upheld by the FERC despite repeated challenges.⁷

Backbone Facilities

- PJM baseline transmission projects are implemented to resolve reliability criteria violations. PJM backbone transmission projects are a subset of

significant baseline projects, which are intended to resolve multiple reliability criteria violations and congestion issues and which may have substantial impacts on energy and capacity markets. There are currently three backbone projects under development, Surry Skiffes Creek 500kV, the Northern New Jersey 345 kV Upgrades, and Byron Wayne 345 kV.⁸

Transmission Facility Outages

- PJM maintains a list of reportable transmission facilities. When the reportable transmission facilities need to be taken out of service, PJM transmission owners are required to report planned transmission facility outages as early as possible. PJM processes the transmission facility outage requests according to rules in PJM's Manual 3 to decide if the outage is on time or late and whether or not they will allow the outage.⁹
- There were 20,214 transmission outage requests submitted in 2016. Of the requested outages, 77.5 percent were planned for five days or shorter and 6.6 percent were planned for longer than 30 days. Of the requested outages, 51.7 percent were late according to the rules in PJM's Manual 3.

Recommendations

The MMU recommends improvements to the planning process.

- The MMU recommends that PJM continue to incorporate the principle that the goal of transmission planning should be the incorporation of transmission investment decisions into market driven processes as much as possible. (Priority: Low. First reported 2001. Status: Not adopted.)
- The MMU recommends the creation of a mechanism to permit a direct comparison, or competition, between transmission and generation alternatives, including which alternative is less costly and who bears the risks associated with each alternative. (Priority: Low. First reported 2013. Status: Not adopted.)

4 See "Artificial Island Recommendations," presented at the TEAC meeting on April 28, 2015 at <<http://www.pjm.com/~media/committees-groups/committees/teac/20150428-ai/20150428-artificial-island-recommendations.ashx>>.

5 See letter from Terry Boston concerning the Artificial Island Project at <<http://www.pjm.com/~media/documents/reports/board-statement-on-artificial-island-project.ashx>>.

6 See "PJM Board Statement on Artificial Island Project Suspension." <<http://www.pjm.com/~media/documents/reports/20160805-artificial-island-update.ashx>> Accessed November 7, 2016.

7 See *Delaware PSC v. PJM Interconnection, LLC*, 155 FERC ¶ 61,090 (2016); *PJM Interconnection, LLC*, 155 FERC ¶ 61,089 (2016); *Consolidated Edison Company of New York, Inc. v. PJM Interconnection*, 155 FERC ¶ 61,088 (2016); see also *Transmission Planning and Cost Allocation by Transmission Owning and Operating Public Utilities*, Order No. 1000, FERC Stats. & Regs. ¶ 31,323 (2011), *order on reh'g*, Order No. 1000-A, 139 FERC ¶ 61,132, *order on reh'g and clarification*, Order No. 1000-B, 141 FERC ¶ 61,044 (2012), *aff'd sub nom. S.C. Pub. Serv. Auth. v. FERC*, 762 F.3d 41, 412 (D.C. Cir. 2014); *PJM Interconnection, LLC*, 142 FERC ¶ 61,074 (2013) (accepting the proposed PJM cost allocation method, effective February 1, 2013, subject to the outcome of PJM's Order No. 1000 regional compliance filing proceeding); *PJM Interconnection, LLC*, 142 FERC ¶ 61,214 (2013), *order on reh'g and compliance*, 147 FERC ¶ 61,128 (2014), *order on reh'g and compliance*, 150 FERC ¶ 61,038 (2015), *order on reh'g and compliance*, 151 FERC ¶ 61,250 (2015).

8 See "2016 RTEP Process Scope and Input Assumptions White Paper," P 23. <<http://www.pjm.com/~media/documents/reports/2016-rtep-process-scope-and-input-assumptions.ashx>> Accessed November 7, 2016.

9 PJM. "Manual 03: Transmission Operations," Revision 50 (Dec. 1, 2016), Section 4.

- The MMU recommends that rules be implemented to permit competition to provide financing for transmission projects. This competition could reduce the cost of capital for transmission projects and significantly reduce total costs to customers. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that rules be implemented to require that project cost caps on new transmission projects be part of the evaluation of competing projects. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that barriers to entry be addressed in a timely manner in order to help ensure that the capacity market will result in the entry of new capacity to meet the needs of PJM market participants and reflect the uncertainty and resultant risks in the cost of new entry used to establish the capacity market demand curve in RPM. (Priority: Low. First reported 2012. Status: Not adopted.)
- The MMU recommends that the question of whether Capacity Injection Rights (CIRs) should persist after the retirement of a unit be addressed. Even if the treatment of CIRs remains unchanged, the rules need to ensure that incumbents cannot exploit control of CIRs to block or postpone entry of competitors.¹⁰ (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends outsourcing interconnection studies to an independent party to avoid potential conflicts of interest. Currently, these studies are performed by incumbent transmission owners under PJM's direction. This creates potential conflicts of interest, particularly when transmission owners are vertically integrated and the owner of transmission also owns generation. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that PJM establish fair terms of access to rights of way and property, such as at substations, in order to remove any barriers to entry and permit competition between incumbent transmission providers and merchant transmission providers in the RTEP. (Priority: Medium. First reported 2014. Status: Not adopted.)
- The MMU recommends that PJM enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. (Priority: Medium. First reported 2015. Status: Not adopted.)
- The MMU recommends consideration of changing the minimum distribution factor in the allocation from 0.01 to 0.00 and adding a threshold minimum usage impact on the line. (Priority: Medium. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM reevaluate all transmission outage tickets as on time or late as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages. (Priority: Low. First reported 2014. Status: Not adopted.)
- The MMU recommends that PJM draft a clear definition of the congestion analysis required for transmission outage requests to include in Manual 3 after appropriate review. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM modify the rules to reduce or eliminate the approval of late outage requests submitted or rescheduled after the FTR auction bidding opening date. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM not permit transmission owners to divide long duration outages into smaller segments to avoid complying with the requirements for long duration outages. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends improvements in queue management including that PJM establish a review process to ensure that projects are removed from the queue if they are not viable, as well as a process to allow commercially viable projects to advance in the queue ahead of projects which have failed to make progress, subject to rules to prevent gaming. (Priority: Medium. First reported 2013. Status: Partially adopted.)

¹⁰ See "Comments of the Independent Market Monitor for PJM," Docket No. ER12-1177-000 <http://www.monitoringanalytics.com/reports/Reports/2012/IMM_Comments_ER12-1177-000_20120312.pdf>.

- The MMU recommends an analysis of the study phase of PJM's transmission planning to reduce the need for postponements of study results, to decrease study completion times, and to improve the likelihood that a project at a given phase in the study process will successfully go into service. (Priority: Medium. First reported 2014. Status: Partially adopted.)

Conclusion

The goal of PJM market design should be to enhance competition and to ensure that competition is the driver for all the key elements of PJM markets. But transmission investments have not been fully incorporated into competitive markets. The construction of new transmission facilities has significant impacts on the energy and capacity markets. But when generating units retire or load increases, there is no market mechanism in place that would require direct competition between transmission and generation to meet loads in the affected area. In addition, despite FERC Order No. 1000, there is not yet a transparent, robust and clearly defined mechanism to permit competition to build transmission projects, to ensure that competitors provide a total project cost cap, or to obtain least cost financing through the capital markets.

The addition of a planned transmission project changes the parameters of the capacity auction for the area, changes the amount of capacity needed in the area, changes the capacity market supply and demand fundamentals in the area and may effectively forestall the ability of generation to compete. But there is no mechanism to permit a direct comparison, let alone competition, between transmission and generation alternatives. There is no mechanism to evaluate whether the generation or transmission alternative is less costly, whether there is more risk associated with the generation or transmission alternatives, or who bears the risks associated with each alternative. Creating such a mechanism should be an explicit goal of PJM market design.

The PJM queue evaluation process should be improved to ensure that barriers to competition for new generation investments are not created. Issues that need to be addressed include the ownership rights to CIRs, whether transmission owners should perform interconnection studies, and improvements in queue management.

The PJM rules for competitive transmission development through the RTEP should build upon FERC Order No. 1000 to create real competition between incumbent transmission providers and merchant transmission providers. PJM should enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. Another element of opening competition would be to consider transmission owners' ownership of property and rights of way at or around transmission substations. In many cases, the land acquired included property intended to support future expansion of the grid. Incumbents have included the costs of the property in their rate base. Because PJM now has the responsibility for planning the development of the grid under its RTEP process, property bought to facilitate future expansion should be a part of the RTEP process and be made available to all providers on equal terms.

There are currently no market incentives for transmission owners to submit and complete transmission outages in a timely and efficient manner. Requiring transmission owners to pay does not create an effective incentive when those payments are passed through to transmission customers. The process for the submission of planned transmission outages needs to be carefully reviewed and redesigned to limit the ability of transmission owners to submit transmission outages that are late for FTR auction bid submission dates and are late for the Day-Ahead Energy Market. The submission of late transmission outages can inappropriately affect market outcomes when market participants do not have the ability to modify market bids and offers.

Planned Generation and Retirements Planned Generation Additions

Expected net revenues provide incentives to build new generation to serve PJM markets. The amount of planned new generation in PJM reflects investors' perception of the incentives provided by the combination of revenues from the PJM energy, capacity and ancillary service markets. On December 31, 2016, 101,402.4 MW of capacity were in generation request queues for construction through 2024, compared to an average installed capacity of 193,407.9 MW as of December 31,

2016. Although it is clear that not all generation in the queues will be built, PJM has added capacity.¹¹ In 2016, 5,414.1 MW of nameplate capacity went into service in PJM.

PJM Generation Queues

Generation request queues are groups of proposed projects, including new units, reratings of existing units, capacity resources and energy only resources. Each queue is open for a fixed amount of time. Studies commence on all projects in a given queue when that queue closes. The duration of the queue period has varied. Queues A and B were open for a year. Queues C-T were open for six months. Starting in February 2008, Queues U-Y1 were open for three months. Starting in May 2012, the duration of the queue period was reset to six months, starting with Queue Y2. Queue AC2 is currently open.

All projects that have been entered in a queue have a status assigned. Projects listed as active are undergoing one of the studies (feasibility, system impact, facility) required to proceed. Other status options are under construction, suspended, and in service. Withdrawn projects are removed from the queue and listed separately. A project cannot be suspended until it has reached the status of under construction. Any project that entered the queue before February 1, 2011, can be suspended for up to three years. Projects that entered the queue after February 1, 2011, face an additional restriction in that the suspension period is reduced to one year if they affect any project later in the queue.¹² When a project is suspended, PJM extends the scheduled milestones by the duration of the suspension. If, at any time, a milestone is not met, PJM will initiate the termination of the Interconnection Service Agreement (ISA) and the corresponding cancellation costs must be paid by the customer.¹³

Table 12-1 shows MW in queues by expected completion date and MW changes in the queues between December 31, 2015 and December 31, 2016, for ongoing projects, i.e. projects with the status active, under construction

or suspended.¹⁴ Projects that are already in service are not included here. The total MW in queues increased by 16,079.3 MW, or 18.8 percent, from 85,323.1 MW at the end of 2015.

Table 12-1 Queue comparison by expected completion year (MW): December 31, 2015 to December 31, 2016¹⁵

Year	Twelve Month Change			
	As of 12/31/2015	As of 12/31/2016	MW	Percent
2015	9,641.9	0.0	NA	NA
2016	15,085.7	7,973.5	(7,112.2)	(89.2%)
2017	12,442.3	14,533.3	2,091.0	14.4%
2018	13,403.6	24,468.5	11,064.9	45.2%
2019	21,461.3	25,844.9	4,383.6	17.0%
2020	11,444.3	17,355.1	5,910.8	34.1%
2021	0.0	9,133.1	9,133.1	NA
2022	250.0	1,480.0	1,230.0	83.1%
2023	0.0	614.0	614.0	100.0%
2024	1,594.0	0.0	(1,594.0)	0.0%
Total	85,323.1	101,402.4	16,079.3	18.8%

Table 12-2 shows the yearly project status changes in more detail and how scheduled queue capacity has changed between December 31, 2015, and December 31, 2016. For example, 22,800.7 MW entered the queue in 2016 and 568.6 of these MW have been withdrawn in 2016. Of the total 52,350.1 MW marked as active at the beginning of 2016, 1,129.9 MW were withdrawn, 69.1 MW were suspended, 1,050.9 MW started construction, and 10.0 MW went into service by the end of the quarter. The Under Construction column shows that 16.9 MW came out of suspension and 1,050.9 MW began construction 2016, in addition to the 22,957.7 MW of capacity that maintained the status under construction from the previous year.

¹¹ See Monitoring Analytics, "New Generation in the PJM Capacity Market: MW and Funding Sources for Delivery Years 2007/2008 through 2018/2019," <http://www.monitoringanalytics.com/reports/Reports/2016/New_Generation_in_the_PJM_Capacity_Market_20160504.pdf>.

¹² See PJM. Manual 14C "Generation and Transmission Interconnection Process," Revision 10 (October 1, 2016) Section 3.7 <<http://www.pjm.com/~media/documents/manuals/m14c.ashx>>.

¹³ PJM does not track the duration of suspensions or PJM termination of projects.

¹⁴ Expected completion dates are entered when the project enters the queue. Actual completion dates are generally different than expected completion dates.

¹⁵ Wind and solar capacity in Table 12-2 through Table 12-5 have not been adjusted to reflect derating.

Table 12-2 Change in project status (MW): December 31, 2015 to December 31, 2016

Status at 12/31/2015	Total at 12/31/2015	Status at 12/31/2016				
		Active	Suspended	Under Construction	In Service	Withdrawn
(Entered in 2016)		22,800.7	0.0	0.0	0.0	568.6
Active	52,350.1	48,766.3	69.1	1,050.9	10.0	1,129.9
Suspended	4,698.9	0.0	5,040.9	16.9	0.0	261.8
Under Construction	28,274.1	0.0	680.0	22,957.7	399.7	1,988.6
In Service	41,021.9	0.0	0.0	0.0	46,026.3	0.0
Withdrawn	286,258.0	0.0	0.0	19.9	0.0	301,951.7
Total at 12/31/2016		71,567.0	5,790.0	24,045.3	46,436.0	305,900.6

Table 12-3 shows the amount of capacity active, in service, under construction, suspended, or withdrawn for each queue since the beginning of the RTEP process and the total amount of capacity that had been included in each queue. All items in queues A-M are either in service or have been withdrawn. As of December 31, 2016, there are 101,402.4 MW of capacity in queues that are not yet in service, of which 5.7 percent are suspended, 23.7 percent are under construction and 70.6 percent have not begun construction.

Table 12-3 Capacity in PJM queues (MW): At December 31, 2016¹⁶

Queue	Active	In Service	Under			Total
			Construction	Suspended	Withdrawn	
A Expired 31-Jan-98	0.0	8,103.0	0.0	0.0	17,252.0	25,355.0
B Expired 31-Jan-99	0.0	4,645.5	0.0	0.0	15,656.7	20,302.2
C Expired 31-Jul-99	0.0	531.0	0.0	0.0	3,474.8	4,005.8
D Expired 31-Jan-00	0.0	850.6	0.0	0.0	7,369.0	8,219.6
E Expired 31-Jul-00	0.0	795.2	0.0	0.0	8,033.8	8,829.0
F Expired 31-Jan-01	0.0	52.0	0.0	0.0	3,092.5	3,144.5
G Expired 31-Jul-01	0.0	1,189.6	0.0	0.0	17,980.8	19,170.4
H Expired 31-Jan-02	0.0	702.5	0.0	0.0	8,421.9	9,124.4
I Expired 31-Jul-02	0.0	103.0	0.0	0.0	3,738.3	3,841.3
J Expired 31-Jan-03	0.0	40.0	0.0	0.0	846.0	886.0
K Expired 31-Jul-03	0.0	98.9	0.0	0.0	485.3	584.2
L Expired 31-Jan-04	0.0	256.5	0.0	0.0	4,033.7	4,290.2
M Expired 31-Jul-04	0.0	504.8	0.0	0.0	3,705.6	4,210.4
N Expired 31-Jan-05	0.0	2,398.8	38.0	0.0	8,090.3	10,527.0
O Expired 31-Jul-05	0.0	1,668.2	437.0	0.0	5,466.8	7,572.0
P Expired 31-Jan-06	0.0	3,064.7	253.0	0.0	5,320.5	8,638.2
Q Expired 31-Jul-06	0.0	3,147.9	0.0	0.0	11,385.7	14,533.6
R Expired 31-Jan-07	0.0	1,886.4	600.0	848.3	19,420.6	22,755.3
S Expired 31-Jul-07	0.0	3,549.5	120.0	70.0	12,396.5	16,136.0
T Expired 31-Jan-08	0.0	2,814.0	1,408.0	300.0	23,013.3	27,535.3
U Expired 31-Jan-09	200.0	837.3	849.9	620.0	30,829.6	33,336.8
V Expired 31-Jan-10	590.0	2,020.6	770.1	555.0	12,877.6	16,813.3
W Expired 31-Jan-11	944.0	2,102.5	1,121.8	814.8	19,097.2	24,080.3
X Expired 31-Jan-12	1,689.0	3,738.2	5,622.4	878.0	18,416.8	30,344.5
Y Expired 30-Apr-13	833.5	719.1	4,381.3	1,336.5	18,469.3	25,739.5
Z Expired 30-Apr-14	1,114.0	430.3	5,823.4	82.2	6,860.8	14,310.7
AA1 Expired 31-Oct-14	5,226.3	115.7	1,416.1	141.4	5,102.4	12,001.9
AA2 Expired 30-Apr-15	8,393.4	36.1	358.4	94.0	7,184.4	16,066.3
AB1 Expired 31-Oct-15	12,839.1	24.2	701.0	49.9	6,684.3	20,298.5
AB2 Expired 31-Mar-16	12,422.6	10.0	145.0	0.0	625.6	13,203.2
AC1 Through 30-Sep-16	26,936.0	0.0	0.0	0.0	11.0	26,946.9
AC2 Through 30-Apr-17	379.2	0.0	0.0	0.0	557.6	936.8
Total	71,567.0	46,436.0	24,045.3	5,790.0	305,900.6	453,739.0

¹⁶ Projects listed as partially in service are counted as in service for the purposes of this analysis.

Distribution of Units in the Queues

Table 12-4 shows the projects under construction, suspended, or active, by unit type, and control zone.¹⁷ As of December 31, 2016, 101,402.4 MW of capacity were in generation request queues for construction through 2024, compared to 85,323.1 MW at December 31, 2015.¹⁸ Table 12-4 also shows the planned retirements for each zone.

Table 12-4 Queue capacity by LDA, control zone and fuel (MW): At December 31, 2016¹⁹

LDA	Zone	BioMass	CC	CT	Diesel	Fuel							Total Queue Capacity	Planned Retirements
						Cell	Hydro	Nuclear	Solar	Steam	Storage	Wind		
EMAAC	AECO	0.0	1,667.0	469.0	0.0	1.7	0.0	0.0	85.0	0.0	20.0	175.0	2,417.7	303.0
	DPL	25.8	742.0	0.0	2.0	0.0	0.0	1,412.5	0.0	26.0	599.6	2,807.9	34.0	
	JCPL	0.0	2,047.2	0.0	0.0	0.4	0.0	0.0	304.8	0.0	103.0	0.0	2,455.4	614.5
	PECO	0.0	1,256.0	0.0	6.6	0.0	0.0	94.0	20.0	0.0	0.0	0.0	1,376.6	50.8
	PSEG	0.0	2,659.5	788.0	10.6	0.0	0.0	0.0	92.0	24.0	3.8	0.0	3,577.9	1,863.0
RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
	EMAAC Total	25.8	8,371.7	1,257.0	19.2	2.2	0.0	94.0	1,914.3	24.0	152.8	774.6	12,635.5	2,865.3
SWMAAC	BGE	0.0	0.0	0.0	1.3	0.0	0.4	19.2	44.1	0.0	0.1	0.0	65.1	135.0
	Pepco	0.0	2,498.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,498.5	0.0
	SWMAAC Total	0.0	2,498.5	0.0	1.3	0.0	0.4	19.2	44.1	0.0	0.1	0.0	2,563.6	135.0
WMAAC	Met-Ed	0.0	497.0	34.1	0.0	0.0	0.0	0.0	138.0	30.0	0.0	0.0	699.1	6.0
	PENELEC	0.0	1,333.0	560.9	139.0	0.0	17.0	0.0	13.5	590.0	0.0	575.8	3,229.2	0.0
	PPL	16.0	5,940.0	19.9	0.0	0.0	0.0	0.0	36.0	0.0	30.0	266.2	6,308.1	0.0
	WMAAC Total	16.0	7,770.0	614.9	139.0	0.0	17.0	0.0	187.5	620.0	30.0	842.0	10,236.4	6.0
Non-MAAC	AEP	0.0	15,077.0	394.0	9.4	0.0	146.5	102.0	2,400.1	504.0	120.0	6,953.5	25,706.5	0.0
	AP	0.0	5,730.4	30.0	122.8	0.0	0.0	0.0	666.1	10.0	162.5	1,001.7	7,723.4	0.0
	ATSI	0.0	5,153.0	0.0	4.0	0.0	0.0	0.0	326.0	0.0	12.5	518.0	6,013.5	776.0
	ComEd	0.0	8,733.3	1,114.0	32.1	0.0	22.7	0.0	27.0	64.0	89.1	3,446.5	13,528.7	510.0
	DAY	0.0	1,150.0	0.0	0.0	0.0	0.0	0.0	223.0	12.0	39.9	300.0	1,724.9	0.0
	DEOK	0.0	0.0	0.0	4.8	0.0	0.0	0.0	125.0	20.0	19.8	0.0	169.6	0.0
	DLCO	0.0	205.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	20.0	0.0	225.0	0.0
	Dominion	62.5	9,166.9	114.0	12.0	0.0	0.0	0.0	9,855.5	0.0	134.0	820.5	20,165.4	621.0
	EKPC	0.0	614.0	0.0	0.0	0.0	0.0	0.0	80.0	0.0	0.0	0.0	694.0	0.0
	Non-MAAC Total	62.5	45,829.6	1,652.0	185.0	0.0	169.2	102.0	13,702.6	610.0	597.8	13,040.2	75,950.9	1,907.0
Total in PJM	104.3	64,469.8	3,523.9	344.5	2.2	186.6	215.2	15,848.5	1,254.0	780.7	14,656.8	101,386.4	4,913.3	

A significant shift in the distribution of unit types within the PJM footprint continues to develop as natural gas fired units enter the queue and steam units retire. As of December 31, 2016, there were 18,070.3 MW of gas fired capacity under construction in PJM. As of December 31, 2016, there were only 200.0 MW of coal fired steam capacity under construction in PJM. There is only one coal project classified as new under construction in PJM. With respect to retirements, 3,649.0 MW of coal fired steam capacity and 208.8 MW of natural gas capacity are slated for deactivation between now and 2020. The replacement of coal steam units by natural gas units could significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

Planned Retirements

As shown in Table 12-5, 29,057.5 MW have been, or are planned to be, retired between 2011 and 2020.²⁰ Of that, 4,965.3 MW are planned to retire after 2016. In 2016, 395.5 MW were retired. Of the 4,965.3 MW pending retirement, 3,649.0 MW are coal units. The coal unit retirements were a result of low gas prices, low capacity prices and the investments required for compliance with the EPA's Mercury and Air Toxics Standards (MATS) for some units.

¹⁷ Unit types designated as reciprocating engines are classified as diesel.

¹⁸ Since wind resources cannot be dispatched on demand, PJM rules previously required that the unforced capacity of wind resources be derated to 20 percent of nameplate capacity until actual generation data are available. Beginning with Queue U, PJM derates wind resources to 13 percent of nameplate capacity until there is operational data to support a different conclusion. PJM derates solar resources to 38 percent of nameplate capacity. Based on the derating of 14,505.3 MW of wind resources and 7,733.5 MW of solar resources, the 82,741.7 MW currently active in the queue would be reduced to 65,327.3 MW.

¹⁹ This data includes only projects with a status of active, under-construction, or suspended.


²⁰ See PJM "Generator Deactivation Summary Sheets," at <<http://www.pjm.com/planning/generation-deactivation/gd-summaries.aspx>> (June 2, 2016).

Table 12-5 Summary of PJM unit retirements by fuel (MW): 2011 through 2020

	Coal	Diesel	Heavy Oil	Hydro	Kerosene	Landfill Gas	Light Oil	Natural Gas	Nuclear	Wind	Wood Waste	Total
Retirements 2011	543.0	0.0	0.0	0.0	0.0	0.0	63.7	522.5	0.0	0.0	0.0	1,129.2
Retirements 2012	5,907.9	0.0	0.0	0.0	0.0	0.0	788.0	250.0	0.0	0.0	16.0	6,961.9
Retirements 2013	2,589.9	2.9	166.0	0.0	0.0	3.8	85.0	0.0	0.0	0.0	8.0	2,855.6
Retirements 2014	2,427.0	50.0	0.0	0.0	184.0	15.3	0.0	294.0	0.0	0.0	0.0	2,970.3
Retirements 2015	7,661.8	10.3	0.0	0.0	644.2	2.0	212.0	1,239.0	0.0	10.4	0.0	9,779.7
Retirements 2016	243.0	59.0	74.0	0.5	0.0	5.0	14.0	0.0	0.0	0.0	0.0	395.5
Planned Retirements Post-2016	3,501.0	0.0	182.0	0.0	0.0	6.0	0.0	661.8	614.5	0.0	0.0	4,965.3
Total	22,873.6	122.2	422.0	0.5	828.2	32.1	1,162.7	2,967.3	614.5	10.4	24.0	29,057.5

A map of the retirements between 2011 and 2020 is shown in Figure 12-1.

Figure 12-1 Map of PJM unit retirements: 2011 through 2020



The list of pending retirements is shown in Table 12-6.

Table 12-6 Planned retirement of PJM units: as of December 31, 2016

Unit	Zone	ICAP (MW)	Fuel	Unit Type	Projected Deactivation Date
Rolling Hills Landfill Generator	Met-Ed	6.0	LFG	Diesel	07-Dec-16
Roanoke Valley 1-2	Dominion	209.0	Coal	Steam	01-Mar-17
Yorktown 1-2	Dominion	323.0	Coal	Steam	15-Apr-17
BL England 2-3	AECO	303.0	Coal	Steam	30-Apr-17
McKee 1-2	DPL	34.0	Heavy Oil	Combustion Turbine	31-May-17
Hopewell James River Cogen	Dominion	89.0	Coal	Steam	31-May-17
Hudson 2	PSEG	620.0	Coal	Steam	01-Jun-17
Mercer 1-2	PSEG	632.0	Coal	Steam	01-Jun-17
Sewaren 1-4	PSEG	453.0	Kerosene	Combustion Turbine	01-Jun-18
Bayonne Cogen Plant (CC)	PSEG	158.0	Natural gas	Steam	01-Nov-18
MH50 Marcus Hook Co-gen	PECO	50.8	Natural gas	Steam	13-May-19
Elmer Smith U1	External	52.0	Coal	Steam	01-Jun-19
Oyster Creek	JCPL	614.5	Nuclear	Nuclear	31-Dec-19
Will County 4	ComEd	510.0	Coal	Steam	31-May-20
W H Sammis 1-4	ATSI	640.0	Coal	Steam	31-May-20
Wagner 2	BGE	135.0	Coal	Steam	01-Jun-20
Bay Shore 1	ATSI	136.0	Coal	Steam	01-Oct-20
Total		4,965.3			

Table 12-7 shows the capacity, average size, and average age of units retiring in PJM, from 2011 through 2020, while Table 12-8 shows these retirements by state. The majority, 78.7 percent, of all MW retiring during this period are coal steam units. These units have an average age of 55.4 years and an average size of 167.0 MW. Over half of them, 51.0 percent, are located in either Ohio or Pennsylvania. Retirements have generally consisted of smaller subcritical coal steam units and those without adequate environmental controls to remain viable beyond 2016.

Table 12-7 Retirements by fuel type: 2011 through 2020

	Number of Units	Avg. Size (MW)	Avg. Age at Retirement (Years)	Total MW	Percent
Coal	137	167.0	55.4	22,873.6	78.7%
Diesel	7	17.5	42.7	122.2	0.4%
Heavy Oil	5	84.4	54.6	422.0	1.5%
Hydro	1	0.5	100.0	0.5	0.0%
Kerosene	20	41.4	45.5	828.2	2.9%
Landfill Gas	9	3.6	14.0	32.1	0.1%
Light Oil	16	72.7	44.1	1,162.7	4.0%
Natural Gas	47	63.1	46.6	2,967.3	10.2%
Nuclear	1	614.5	51.0	614.5	2.1%
Wind	1	10.4	15.0	10.4	0.0%
Wood Waste	2	12.0	23.5	24.0	0.1%
Total	246	118.1	50.0	29,057.5	100.0%

Table 12-8 Retirements (MW) by fuel type and state: 2011 through 2020

State	Coal	Diesel	Hydro	Heavy Oil	Kerosene	Landfill		Natural Gas			Wind	Wood Waste	Total
						Gas	Light Oil	Gas	Nuclear	Gas			
DC	0.0	0.0	0.0	0.0	0.0	0.0	788.0	0.0	0.0	0.0	0.0	0.0	788.0
DE	254.0	0.0	34.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	288.0
IL	2,134.0	0.0	0.0	0.0	0.0	6.4	0.0	0.0	0.0	0.0	0.0	0.0	2,140.4
IN	982.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	982.0
KY	1,047.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,047.0
MD	250.0	51.0	74.0	0.0	0.0	0.0	0.0	115.0	0.0	0.0	0.0	0.0	490.0
NC	209.0	0.0	0.0	0.0	0.0	0.0	31.0	0.0	0.0	0.0	0.0	0.0	240.0
NJ	1,543.0	8.0	148.0	0.5	828.2	7.7	212.0	2,600.5	614.5	0.0	0.0	0.0	5,962.4
OH	6,528.6	60.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6,588.9
PA	5,145.0	0.0	166.0	0.0	0.0	16.0	131.7	251.8	0.0	10.4	24.0	0.0	5,744.9
VA	2,140.0	2.9	0.0	0.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0	0.0	2,144.9
WV	2,641.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,641.0
Total	22,873.6	122.2	422.0	0.5	828.2	32.1	1,162.7	2,967.3	614.5	10.4	24.0	0.0	29,057.5

Actual Generation Deactivations in 2016

Table 12-9 shows the units that were deactivated in 2016.

Table 12-9 Unit deactivations in 2016

Company	Unit Name	ICAP (MW)	Primary Fuel	Zone Name	Average Age (Years)	Retirement Date
Exelon Corporation	Fauquier County Landfill	2.0	Diesel	Dominion	12	31-Jan-16
Exelon Corporation	Perryman 2	51.0	Diesel	BGE	44	01-Feb-16
NRG Energy Inc.	Avon Lake 7	94.0	Coal	ATSI	67	16-Apr-16
Eastern Kentucky Power Cooperative, Inc.	Dale 3	74.0	Coal	EKPC	59	16-Apr-16
Eastern Kentucky Power Cooperative, Inc.	Dale 4	75.0	Coal	EKPC	56	16-Apr-16
Rockland Capital Energy Investments, LLC	BL England Diesel Units 1-4	8.0	Diesel	AECO	55	31-May-16
Exelon Corporation	Riverside 4	74.0	Heavy Oil	BGE	65	01-Jun-16
South Jersey Industries, Inc.	Warren County Landfill Generator	3.0	LFG	JCPL	10	02-Jun-16
Great Bear Hydropower, Inc.	Columbia Dam Hydro	0.5	Hydro	JCPL	0	03-Oct-16
Talen Energy Corporation	Harrisburg 4 CT	14.0	Light Oil	PPL	49	17-Nov-16
Total		395.5				

Generation Mix

As of December 31, 2016, PJM had an installed capacity of 193,407.9 MW (Table 12-10). This measure differs from capacity market installed capacity because it includes energy-only units, excludes all external units, and uses nameplate values for solar and wind resources.

Table 12-10 Existing PJM capacity: At December 31, 2016 (By zone and unit type (MW))²¹


Zone	CC	CT	Diesel	Fuel Cell	Hydroelectric	Nuclear	Solar	Steam	Storage	Wind	Total
AECO	901.9	570.7	14.6	0.0	0.0	0.0	41.7	815.9	0.0	7.5	2,352.3
AEP	6,100.0	3,682.2	80.3	0.0	1,071.9	3,211.0	10.1	18,897.8	4.0	2,204.0	35,261.3
APS	1,129.0	1,226.9	47.9	0.0	129.2	0.0	36.1	5,409.0	47.4	1,088.5	9,114.0
ATSI	685.0	1,618.3	67.7	0.0	0.0	2,134.0	0.0	5,719.0	0.0	0.0	10,224.0
BGE	0.0	789.0	18.4	0.0	0.0	1,716.0	0.0	2,921.5	0.0	0.0	5,444.9
ComEd	3,146.1	7,244.0	109.1	0.0	0.0	10,473.5	9.0	5,166.1	107.5	2,781.9	29,037.2
DAY	0.0	1,368.5	47.5	0.0	0.0	0.0	1.1	2,908.0	40.0	0.0	4,365.1
DEOK	47.2	654.0	0.0	0.0	112.0	0.0	0.0	3,567.0	20.0	0.0	4,400.2
DLCO	244.0	15.0	0.0	0.0	6.3	1,777.0	0.0	660.0	0.0	0.0	2,702.3
Dominion	6,851.6	3,761.7	151.8	0.0	3,589.3	3,581.3	157.8	7,775.0	0.0	208.0	26,076.5
DPL	1,498.5	1,820.4	96.1	30.0	0.0	0.0	100.0	1,620.0	0.0	0.0	5,165.0
EKPC	0.0	774.0	0.0	0.0	70.0	0.0	0.0	1,687.0	0.0	0.0	2,531.0
JCPL	2,682.5	763.1	16.1	0.0	400.0	614.5	154.2	10.0	0.0	0.0	4,640.4
Met-Ed	2,111.0	406.5	41.4	0.0	19.0	805.0	0.0	200.0	0.0	0.0	3,582.9
PECO	3,209.0	834.0	2.9	0.0	1,642.0	4,546.8	3.0	979.1	1.0	0.0	11,217.8
PENELEC	850.0	407.5	110.2	0.0	512.8	0.0	0.0	6,793.5	10.4	969.2	9,653.6
Pepco	230.0	1,091.7	9.9	0.0	0.0	0.0	0.0	3,649.1	0.0	0.0	4,980.7
PPL	2,657.9	602.2	55.5	0.0	706.6	2,520.0	15.0	5,169.9	20.0	219.7	11,966.8
PSEG	3,846.3	1,132.0	11.1	0.0	5.0	3,493.0	152.4	2,050.1	2.0	0.0	10,691.9
RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total	36,190.0	28,761.7	880.5	30.0	8,264.1	34,872.1	680.4	75,998.0	252.3	7,478.8	193,407.9

Figure 12-2 and Table 12-11 show the age of PJM generators by unit type. Units older than 40 years comprise 71,090.4 MW, or 36.8 percent, of the total capacity of 193,407.9 MW.

Table 12-11 PJM capacity (MW) by age (years): At December 31, 2016

Age (years)	CC	CT	Diesel	Fuel Cell	Hydroelectric	Nuclear	Solar	Steam	Storage	Wind	Total
Less than 20	30,893.5	21,016.2	624.1	30.0	344.8	0.0	680.4	3,905.5	252.3	7,478.8	65,225.6
20 to 40	4,854.5	3,315.5	98.8	0.0	3,557.2	24,033.9	0.0	21,232.0	0.0	0.0	57,091.9
40 to 60	442.0	4,430.0	155.6	0.0	2,915.0	10,838.2	0.0	49,188.5	0.0	0.0	67,969.3
More than 60	0.0	0.0	2.0	0.0	1,447.1	0.0	0.0	1,672.0	0.0	0.0	3,121.1
Total	36,190.0	28,774.8	873.8	30.0	8,264.1	33,732.1	561.4	76,072.0	242.3	6,956.7	193,407.9

Figure 12-2 PJM capacity (MW) by age (years): At December 31, 2016



²¹ The capacity described in this section refers to all capacity in PJM at nameplate ratings, regardless of whether the capacity entered the RPM auction. This table previously included external units.

Generation and Transmission Interconnection Planning Process

PJM made changes to the queue process in May 2012.²² These changes included reducing the length of the queues, creating an alternate queue for some small projects, and adjustments to the rules regarding suspension rights and Capacity Interconnection Rights (CIR). PJM staff reported on June 11, 2015, that due to these and other process improvements, the study backlog has been significantly reduced.²³ The Earlier Queue Submittal Task Force (EQSTF) was established in August 2015, to further address the issue.²⁴

The Earlier Queue Submittal Task Force

In 2015 and 2016, participants of the Earlier Queue Submittal Task Force (EQSTF) drafted rule changes to the Interconnection Queue process meant to address high levels of deficient project applications being submitted to PJM for review.

To discourage incomplete interconnection project requests, the EQSTF proposed to only assign queue positions for project applications that had submitted all required project elements including site control. In addition, all project applications would be required to remedy any deficiencies by the end of the queue window in order to be considered in feasibility studies or be terminated and withdrawn. Queue positions had historically been assigned to project developers that paid the study deposit and submitted a project application by the appropriate submission deadline. Project applications with missing information were assigned queue numbers so long as these two criteria were met.

The EQSTF also proposed rule changes to interconnection study fee structures that would discourage the submission of speculative or incomplete queue projects. Under the old rules, deposits provided by developers for interconnection studies could not be charged until after a queue position was accepted. Under the new rules, these deposits would be available for charging before a queue position is assigned.

In addition, rather than socializing the study costs for deficient applications from project developers, the EQSTF proposed that these project costs be assigned directly to the developer that submitted the project. This would significantly increase the cost burden that developers would experience if a project is found to be deficient in the review process.

The EQSTF proposed to change the timing of queue windows and Feasibility Study dates to enable more generation projects to participate in the PJM Base Residual Auction. The EQSTF proposed shifting start dates for the queue windows back a month from May 1 to April 1 and Nov 1 to October 1. The EQSTF also proposed shifting feasibility study dates from Dec 1 to Nov 1 and June 1 to May 1.

The EQSTF presented these proposed tariff changes to the PJM Planning Committee on May 12, 2016, where they were endorsed. The Markets and Reliability Committee and PJM Members Committee endorsed the same changes. FERC approved these changes and they were added into the PJM Open Access Transmission Tariff effective October 31, 2016.

Interconnection Study Phase

In the study phase of the interconnection planning process, a series of studies are performed to determine the feasibility, impact, and cost of projects in the queue. Table 12-12 is an overview of PJM's study process. System impact and facilities studies are often redone when a project is withdrawn in order to determine the impact on the projects remaining in the queue.

²² See letter from PJM to Secretary Kimberly Bose, Docket No. ER12-1177-000 <<http://www.pjm.com/~media/documents/ferc/2012-filings/20120229-er12-1177-000.ashx>>.

²³ See presentation by Dave Egan to the PJM Planning Committee, at <<http://www.pjm.com/~media/committees-groups/committees/pc/20150611/20150611-item-09-queue-status-update.ashx>>.

²⁴ See Earlier Queue Submittal Task Force at <<http://www.pjm.com/committees-and-groups/task-forces/eqstf.aspx>>.

Table 12-12 PJM generation planning process

Process Step	Start on	Financial Obligation	Days for PJM to Complete	Days for Applicant to Decide Whether to Continue
Feasibility Study	Close of current queue	Cost of study (partially refundable deposit)	90	30
System Impact Study	Upon acceptance of the System Impact Study Agreement	Cost of study (partially refundable deposit)	120	30
Facilities Study	Upon acceptance of the Facilities Study Agreement	Cost of study (refundable deposit)	Varies	60
Schedule of Work	Upon acceptance of Interconnection Service Agreement (ISA)	Letter of credit for upgrade costs	Varies	37
Construction (only for new generation)	Upon acceptance of Interconnection Construction Service Agreement (ICSA)	None	Varies	NA

Manual 14B requires PJM to apply a commercial probability factor at the feasibility study stage to improve the accuracy of capacity and cost estimates. The commercial probability factor is based on the historical incidence of projects dropping out of the queue at the impact study stage.²⁵ The impact and facilities studies are performed using the full amount of planned generation in the queues. The actual withdrawal rates are shown in Table 12-13 and Table 12-14.

Table 12-13 shows the milestone status when projects were withdrawn, for all withdrawn projects. Of the projects withdrawn, 49.6 percent were withdrawn before the system impact study was completed. Once an Interconnection Service Agreement (ISA) or a Wholesale Market Participation Agreement (WMPA) is executed, the financial obligation for any necessary transmission upgrades cannot be retracted.²⁶ ²⁷ Withdrawing at or beyond this point is uncommon; only 235 projects, or 12.8 percent, of all projects withdrawn were withdrawn after reaching this milestone.

Table 12-13 Last milestone at time of withdrawal: January 1, 1997 through December 31, 2016

Milestone Completed	Projects Withdrawn	Percent	Average Days	Maximum Days
Never Started	101	5.5%	171	1,235
Feasibility Study	810	44.1%	320	3,238
System Impact Study	439	23.9%	593	3,174
Facilities Study	250	13.6%	1,281	4,210
Construction Service Agreement (CSA) or beyond	235	12.8%	1,341	4,249
Total	1,835	100.0%		

²⁵ See PJM Manual 14B, "PJM Region Transmission Planning Process," Revision 33 (May 5, 2016), p.70.

²⁶ "Generators planning to connect to the local distribution systems at locations that are not under FERC jurisdiction and wish to participate in PJM's market need to execute a PJM Wholesale Market Participation Agreement (WMPA)..." instead of an ISA. See PJM Manual 14C, "Generation and Transmission Interconnection Facility Construction," Revision 10 (October 1, 2016), p.8.

²⁷ See PJM, "Manual 14C: Generation and Transmission Interconnection Facility Construction," Revision 10 (October 1, 2016), p.22.

Table 12-14 and Table 12-15 show the time spent at various stages in the queue process and the completion time for the studies performed. For completed projects, there is an average time of 983 days, or 2.7 years, between entering a queue and going into service. For withdrawn projects, there is an average time of 639 days, or 1.8 years, between entering a queue and withdrawing.

Table 12-14 Average project queue times (days): At December 31, 2016

Status	Average (Days)	Standard Deviation	Minimum	Maximum
Active	907	570	65	3,745
In-Service	983	709	1	4,024
Suspended	2,031	1,091	610	5,108
Under Construction	1,678	1,010	426	4,652
Withdrawn	639	668	1	4,249

Table 12-15 presents information on the time in the stages of the queue for those projects not yet in service. Of the 765 projects in the queue as of December 31, 2016, 88 had a completed feasibility study and 183 were under construction.

Table 12-15 PJM generation planning summary: At December 31, 2016

Milestone Reached	Number of Projects	Percent of Total Projects	Average Days	Maximum Days
Under Review	314	41.0%	745	2,540
Feasibility Study	88	11.5%	866	1,828
System Impact Study	89	11.6%	1,104	3,651
Facilities Study	91	11.9%	1,809	4,260
Construction Service Agreement (CSA) or beyond	183	23.9%	1,979	5,108
Total	765	100.0%		

The time it takes to complete a study depends on the backlog and the number of projects in the queue, but not on the size of the project. Table 12-16 shows the number of projects that entered the queue by year. The number of queue entries has increased during the past three years, primarily by renewable projects (solar, hydro, storage, biomass, wind). Of the 844 projects entered in 2014, 2015, and 2016, 594, 70.3 percent, were renewable. Of the 349 projects entered 2016, 281, 80.5 percent, were renewable.

Table 12-16 Number of projects entered in the queue as of December 31, 2016

Year Entered	Fuel Group			Grand Total
	Nuclear	Renewable	Traditional	
1997	2	0	11	13
1998	0	0	18	18
1999	1	5	85	91
2000	2	3	79	84
2001	4	6	83	93
2002	3	14	33	50
2003	1	35	17	53
2004	4	17	32	53
2005	3	78	51	132
2006	9	78	70	157
2007	9	68	142	219
2008	3	114	99	216
2009	10	113	50	173
2010	5	381	55	441
2011	6	265	78	349
2012	2	73	80	155
2013	1	78	73	152
2014	0	122	68	190
2015	0	191	114	305
2016	3	281	65	349
Total	68	1,922	1,303	3,293

Even though renewable projects comprise the majority of projects entered in the queue, as well as what is currently active in the queue, renewable projects only account for 31.2 percent of the nameplate MW currently active in the queue (Table 12-17).

Table 12-17 Queue details by fuel group: At December 31, 2016

Fuel Group	Number of Projects	Percent of Projects	MW	Percent MW
Nuclear	8	1.0%	226.3	0.2%
Renewable	518	67.4%	31,636.8	31.2%
Traditional	243	31.6%	69,610.4	68.6%
Total	769	100.0%	101,473.5	100.0%

Table 12-18 shows the current status of all generation queue projects by fuel type and project classification from January 1, 1997, through December 31, 2016. For example, between January 1, 1997 and December 31, 2016, 138 nameplate capacity upgrades at natural gas fired facilities have completed the queue process and are in service.

Since 1997, there have been a total of 3,293 projects in PJM generation queues. A total of 2,681 projects have been classified as new generation and 612 projects have been classified as upgrades. Wind, solar and natural gas projects have accounted for 2,540 projects, or 77.1 percent, of all 3,293 generation queue projects. A total of 361 new projects from either project classification entered the generation queue in 2016.

**Table 12-18 Status of all generation queue projects:
January 1, 1997 through December 31, 2016**

Project Status	Project Classification	Number of Projects												
		Natural Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	Diesel	TOTAL
In Service	New Generation	87	61	9	102	1	9	4	7	15	3	71	6	375
	Upgrade	138	15	45	15	41	16	14	5	3	4	14	2	312
Under Construction	New Generation	34	25	1	65	0	4	0	0	30	0	9	0	168
	Upgrade	34	1	5	3	1	1	0	2	3	0	1	0	51
Suspended	New Generation	15	15	0	22	0	0	0	1	4	0	1	0	58
	Upgrade	3	2	0	0	0	0	0	0	2	0	0	0	7
Withdrawn	New Generation	403	368	54	621	9	40	9	32	63	10	74	12	1695
	Upgrade	65	14	12	8	9	2	13	1	7	2	7	2	142
Active	New Generation	68	43	0	236	0	1	0	4	31	0	2	0	385
	Upgrade	60	7	4	10	7	1	0	1	4	3	0	3	100
Total Projects	New Generation	607	512	64	1046	10	54	13	44	143	13	157	18	2681
	Upgrade	300	39	66	36	58	20	27	9	19	9	22	7	612

Table 12-19 shows the MW in Table 12-18 by share by classification as new generation or upgrade. Within a fuel type the shares of upgrades add to 100 percent and the shares of new generation add to 100 percent. For example, 80.0 percent of all hydro projects classified as upgrades are currently in service in PJM, 10.0 percent of hydro upgrades were withdrawn, 5.0 percent of hydro upgrades are under construction, and 5.0 percent of hydro upgrades are active in the queue. From January 1, 1997, through December 31, 2016, solar projects have had the lowest completion rate across all technology types for projects classified as new generation and storage projects have had the lowest completion rate across all technology types for projects classified as upgrades. Landfill gas projects have had the highest completion rate across all technology types for projects classified as new generation and hydro projects have had the highest completion rate across all technology types for projects classified as upgrades.

Table 12-20 shows the nameplate generating capacity of projects in the PJM generation queue by technology type and project classification. For example, the 368 new generation wind projects that have been withdrawn from the queue as of December 31, 2016 listed in Table 12-18 constitute 57,889.6 MW of nameplate capacity. The 468 new generation and upgrade natural gas projects that have been withdrawn in the same time period constitute 188,595.9 MW of nameplate capacity.

Table 12-19 Status of all generation queue projects as percent of total projects by classification: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Percent of Total Projects by Classification												
		Natural Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	Diesel	
In Service	New Generation	14.3%	11.9%	14.1%	9.8%	10.0%	16.7%	30.8%	15.9%	10.5%	23.1%	45.2%	33.3%	
	Upgrade	46.0%	38.5%	68.2%	41.7%	70.7%	80.0%	51.9%	55.6%	15.8%	44.4%	63.6%	28.6%	
Under Construction	New Generation	5.6%	4.9%	1.6%	6.2%	0.0%	7.4%	0.0%	0.0%	21.0%	0.0%	5.7%	0.0%	
	Upgrade	11.3%	2.6%	7.6%	8.3%	1.7%	5.0%	0.0%	22.2%	15.8%	0.0%	4.5%	0.0%	
Suspended	New Generation	2.5%	2.9%	0.0%	2.1%	0.0%	0.0%	0.0%	2.3%	2.8%	0.0%	0.6%	0.0%	
	Upgrade	1.0%	5.1%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	10.5%	0.0%	0.0%	0.0%	
Withdrawn	New Generation	66.4%	71.9%	84.4%	59.4%	90.0%	74.1%	69.2%	72.7%	44.1%	76.9%	47.1%	66.7%	
	Upgrade	21.7%	35.9%	18.2%	22.2%	15.5%	10.0%	48.1%	11.1%	36.8%	22.2%	31.8%	28.6%	
Active	New Generation	11.2%	8.4%	0.0%	22.6%	0.0%	1.9%	0.0%	9.1%	21.7%	0.0%	1.3%	0.0%	
	Upgrade	20.0%	17.9%	6.1%	27.8%	12.1%	5.0%	0.0%	11.1%	21.1%	33.3%	0.0%	42.9%	

Table 12-20 Status of all generation capacity (MW) in the PJM generation queue: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Project MW												TOTAL
		Natural Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	Diesel	
In Service	New Generation	22,626.3	6,698.6	1,378.0	792.2	9.0	465.6	607.0	225.7	149.0	50.0	382.7	69.5	33,453.5
	Upgrade	6,914.4	33.7	755.5	19.4	3,810.8	605.6	125.8	58.8	36.4	547.5	49.3	25.3	12,982.4
Under Construction	New Generation	16,196.1	4,191.1	80.0	965.2	0.0	123.1	0.0	0.0	83.9	0.0	49.8	0.0	21,689.1
	Upgrade	1,874.2	100.0	120.0	4.5	102.0	17.0	0.0	62.5	72.0	0.0	4.0	0.0	2,356.2
Suspended	New Generation	2,616.2	2,547.4	0.0	249.0	0.0	0.0	0.0	16.0	54.0	0.0	0.9	0.0	5,483.4
	Upgrade	221.6	75.0	0.0	0.0	0.0	0.0	0.0	0.0	10.0	0.0	0.0	0.0	306.6
Withdrawn	New Generation	180,004.5	57,889.5	33,431.6	8,085.8	8,161.0	1,988.0	1,721.0	1,027.7	688.8	843.8	416.2	63.9	294,321.8
	Upgrade	8,591.4	367.0	815.0	47.8	916.0	56.0	589.0	12.1	92.1	24.0	39.4	29.0	11,578.8
Active	New Generation	39,177.9	7,482.5	0.0	14,099.3	0.0	12.5	0.0	21.8	388.3	0.0	8.2	0.0	61,190.5
	Upgrade	9,178.4	260.8	77.0	590.6	124.3	34.0	0.0	4.0	172.5	0.0	0.0	6.1	10,447.7
Total Projects	New Generation	260,621.0	78,809.2	34,889.6	24,191.4	8,170.0	2,589.2	2,328.0	1,291.2	1,363.9	893.8	857.7	133.4	416,138.4
	Upgrade	26,780.0	836.4	1,767.5	662.3	4,953.1	712.6	714.8	137.4	383.0	571.5	92.7	60.4	37,671.7

Figure 12-3 shows the project MW that have entered the PJM generation queue by fuel type and year of entry. In 2015 and 2016, natural gas, wind, and solar projects accounted for the majority of all new projects entering the generation queue. The increase in solar projects entering the queue in 2016 from 2015 was primarily a result of new projects in Dominion.

Figure 12-3 Queue Project MW by Fuel Type and queue entry year: January 1, 1997 through December 31, 2016




Table 12-21 shows the MW in Table 12-20 by share by classification as new generation or upgrade. Within a fuel type the shares of upgrades add to 100 percent and the shares of new generation add to 100 percent. For example, 73.5 percent of wind projects classified as new generation have been withdrawn from the queue between January 1, 1997, and December 31, 2016.

Table 12-21 Status of all generation queue projects as percent of total MW in project classification: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Percent of Total Project MW by Classification											
		Natural											
		Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	Diesel
In Service	New Generation	8.7%	8.5%	3.9%	3.3%	0.1%	18.0%	26.1%	17.5%	10.9%	5.6%	44.6%	52.1%
	Upgrade	25.8%	4.0%	42.7%	2.9%	76.9%	85.0%	17.6%	42.8%	9.5%	95.8%	53.2%	41.9%
Under Construction	New Generation	6.2%	5.3%	0.2%	4.0%	0.0%	4.8%	0.0%	0.0%	6.2%	0.0%	5.8%	0.0%
	Upgrade	7.0%	12.0%	6.8%	0.7%	2.1%	2.4%	0.0%	45.5%	18.8%	0.0%	4.3%	0.0%
Suspended	New Generation	1.0%	3.2%	0.0%	1.0%	0.0%	0.0%	0.0%	1.2%	4.0%	0.0%	0.1%	0.0%
	Upgrade	0.8%	9.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	2.6%	0.0%	0.0%	0.0%
Withdrawn	New Generation	69.1%	73.5%	95.8%	33.4%	99.9%	76.8%	73.9%	79.6%	50.5%	94.4%	48.5%	47.9%
	Upgrade	32.1%	43.9%	46.1%	7.2%	18.5%	7.9%	82.4%	8.8%	24.0%	4.2%	42.5%	48.0%
Active	New Generation	15.0%	9.5%	0.0%	58.3%	0.0%	0.5%	0.0%	1.7%	28.5%	0.0%	1.0%	0.0%
	Upgrade	34.3%	31.2%	4.4%	89.2%	2.5%	4.8%	0.0%	2.9%	45.0%	0.0%	0.0%	10.1%

Table 12-22 shows the status of all natural gas projects by number of projects that entered PJM generation queues from January 1, 1997 through December 31, 2016, by zone. Of the 128 natural gas projects classified either as new generation or upgrade currently active in the PJM generation queue, 63 projects, 49.2 percent, are located within AEP, ComEd and PENELEC.

Table 12-22 Status of all natural gas generation queue projects: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Number of Projects																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	7	2	7	1	6	2	0	1	4	7	0	0	8	3	7	6	6	9	11	0	87
	Upgrade	7	9	7	1	3	9	6	0	29	13	0	0	5	2	8	6	3	6	24	0	138
Under Construction	New Generation	2	4	1	1	1	0	0	0	4	0	1	0	2	0	2	4	4	5	3	0	34
	Upgrade	2	3	3	1	0	6	0	0	5	0	0	0	1	0	3	0	2	4	4	0	34
Suspended	New Generation	3	2	5	0	0	0	0	0	0	1	0	0	0	0	0	4	0	0	0	0	15
	Upgrade	0	1	0	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0	0	0	3
Withdrawn	New Generation	23	11	37	13	11	9	0	1	17	18	2	2	23	25	41	47	32	34	55	2	403
	Upgrade	5	1	4	3	0	1	0	1	7	4	0	0	5	7	2	4	3	4	14	0	65
Active	New Generation	4	11	8	4	0	11	1	0	4	1	0	1	2	1	1	9	0	5	5	0	68
	Upgrade	1	16	6	2	0	14	0	0	4	0	0	0	1	4	3	2	0	3	4	0	60
Total Projects	New Generation	39	30	58	19	18	22	1	2	29	27	3	3	35	29	51	70	42	53	74	2	607
	Upgrade	15	30	20	7	3	30	6	1	45	17	0	0	13	13	16	13	8	17	46	0	300

Table 12-23 shows the status of all gas projects by MW that entered PJM generation queues from January 1, 1997 through December 31, 2016, by zone. Of the 48,356.3 MW of natural gas projects classified either as new generation or upgrade currently active in the PJM generation queue, 26,968.0 MW, 55.8 percent, are located within AEP, ComEd and Dominion.

Table 12-23 Status of all natural gas generation capacity (MW) in the PJM generation queue: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Project MW											
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC
In Service	New Generation	1,016.2	1,615.0	1,701.0	16.5	390.0	629.0	0.0	20.0	3,211.0	1,122.2	0.0	0.0
	Upgrade	265.7	244.0	796.7	40.0	6.5	849.5	60.0	0.0	1,418.7	189.0	0.0	0.0
Under Construction	New Generation	1.5	2,729.0	930.0	800.0	1.3	0.0	0.0	0.0	3,655.1	0.0	205.0	0.0
	Upgrade	41.0	21.0	61.0	161.0	0.0	112.6	0.0	0.0	369.1	0.0	0.0	0.0
Suspended	New Generation	1,058.0	1,110.0	70.1	0.0	0.0	0.0	0.0	0.0	0.0	291.0	0.0	0.0
	Upgrade	0.0	20.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Withdrawn	New Generation	6,932.0	5,535.0	15,915.1	5,420.7	4,792.1	3,958.0	0.0	134.5	11,066.0	5,651.4	665.0	377.8
	Upgrade	122.8	610.0	567.0	86.0	0.0	10.0	0.0	36.0	305.3	668.0	0.0	0.0
Active	New Generation	963.2	8,224.0	4,495.9	4,047.0	0.0	7,343.3	1,150.0	0.0	3,598.5	451.0	0.0	614.0
	Upgrade	74.0	3,660.0	315.0	145.0	0.0	2,484.0	0.0	0.0	1,658.2	0.0	0.0	0.0
Total Projects	New Generation	9,970.9	19,213.0	23,112.1	10,284.2	5,183.4	11,930.3	1,150.0	154.5	21,530.6	7,515.6	870.0	991.8
	Upgrade	503.5	4,555.0	1,739.7	432.0	6.5	3,456.1	60.0	36.0	3,751.3	857.0	0.0	0.0

Project Status	Project Classification	Project MW										TOTAL
		JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO			
In Service	New Generation	2,070.3	1,397.0	2,464.3	1,227.3	115.0	3,576.6	2,054.9	0.0	22,626.3		
	Upgrade	224.0	665.0	715.0	103.0	45.1	327.3	964.9	0.0	6,914.4		
Under Construction	New Generation	440.4	0.0	760.5	649.7	2,374.0	3,074.0	575.6	0.0	16,196.1		
	Upgrade	0.0	0.0	206.0	0.0	124.5	524.0	254.0	0.0	1,874.2		
Suspended	New Generation	0.0	0.0	0.0	87.1	0.0	0.0	0.0	0.0	2,616.2		
	Upgrade	200.0	0.0	0.0	1.6	0.0	0.0	0.0	0.0	221.6		
Withdrawn	New Generation	11,286.0	12,486.5	23,270.0	16,557.0	19,769.2	13,576.7	22,604.7	6.9	180,004.5		
	Upgrade	253.0	1,730.0	205.0	1,040.6	85.0	480.0	2,392.7	0.0	8,591.4		
Active	New Generation	1,267.2	450.0	220.0	1,793.5	0.0	2,058.9	2,501.4	0.0	39,177.9		
	Upgrade	140.0	111.1	70.0	91.0	0.0	303.0	127.1	0.0	9,178.4		
Total Projects	New Generation	15,063.9	14,333.5	26,714.8	20,314.6	22,258.2	22,286.2	27,736.6	6.9	260,621.0		
	Upgrade	817.0	2,506.1	1,196.0	1,236.2	254.6	1,634.3	3,738.7	0.0	26,780.0		

Table 12-24 shows the status of all wind generation projects that entered PJM generation queues from January 1, 1997 through December 31, 2016, by zone. Of the 76 wind projects to achieve in service status, 65 projects, 87.8 percent are located within ComEd, AEP, AP and PENELEC. Of the 50 wind projects currently active in the PJM generation queue, 37 projects, 74.0 percent are located within AEP, ComEd and AP.

Table 12-24 Status of all wind generation queue projects: January 1, 1997 December 31, 2016

Project Status	Project Classification	Number of Projects																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	1	8	11	0	0	17	0	0	0	0	0	0	1	1	0	18	0	4	0	0	61
	Upgrade	0	0	3	0	0	2	0	0	0	0	0	0	0	0	0	6	0	4	0	0	15
Under Construction	New Generation	1	9	6	1	0	4	0	0	3	1	0	0	0	0	0	0	0	0	0	0	25
	Upgrade	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Suspended	New Generation	1	7	2	0	0	1	2	0	0	0	0	0	0	0	0	1	0	1	0	0	15
	Upgrade	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
Withdrawn	New Generation	15	80	40	6	0	92	13	0	13	8	0	1	1	0	0	59	0	39	1	0	368
	Upgrade	1	0	7	0	0	1	0	0	1	0	0	0	0	0	0	2	0	2	0	0	14
Active	New Generation	0	19	1	1	0	12	0	0	2	2	0	0	0	0	0	4	0	2	0	0	43
	Upgrade	0	0	3	0	0	2	0	0	0	0	0	0	0	0	0	2	0	0	0	0	7
Total Projects	New Generation	18	123	60	8	0	126	15	0	18	11	0	1	2	1	0	82	0	46	1	0	512
	Upgrade	2	1	14	0	0	5	0	0	1	0	0	0	0	0	0	10	0	6	0	0	39

Table 12-25 shows the wind project capacity in MW of all wind generation projects that have entered the PJM generation queue from January 1, 1997 through December 31, 2016, by zone.. Of the 6,732.3 MW of wind generation capacity to achieve in service status, 6,397.7 MW, or 95.0 percent of nameplate capacity is located within ComEd, AEP, AP and PENELEC. Of the 7,743.3 MW of wind generation capacity currently active in the PJM generation queue, 6,375.5 MW of generation capacity or 82.3 percent is located within AEP, ComEd and AP.

Table 12-25 Status of all wind generation capacity (MW) in the PJM generation queue: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Project MW											
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC
In Service	New Generation	7.5	2,052.0	1,031.4	0.0	0.0	2,413.5	0.0	0.0	0.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Under Construction	New Generation	150.0	1,118.3	732.0	500.0	0.0	978.5	0.0	0.0	612.3	100.0	0.0	0.0
	Upgrade	0.0	100.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Suspended	New Generation	20.0	1,398.3	129.1	0.0	0.0	500.0	300.0	0.0	0.0	0.0	0.0	0.0
	Upgrade	5.0	0.0	70.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Withdrawn	New Generation	3,626.4	15,123.0	2,950.1	645.6	0.0	21,515.8	1,828.0	0.0	2,156.5	2,210.0	0.0	150.3
	Upgrade	0.0	0.0	199.0	0.0	0.0	4.0	0.0	0.0	78.0	0.0	0.0	0.0
Active	New Generation	0.0	4,336.9	50.6	18.0	0.0	1,798.0	0.0	0.0	208.2	499.6	0.0	0.0
	Upgrade	0.0	0.0	20.0	0.0	0.0	170.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Projects	New Generation	3,803.9	24,028.5	4,893.2	1,163.6	0.0	27,205.8	2,128.0	0.0	2,977.0	2,809.6	0.0	150.3
	Upgrade	5.0	100.0	289.0	0.0	0.0	174.0	0.0	0.0	78.0	0.0	0.0	0.0

Project Status	Project Classification	Project MW									
		JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL	
In Service	New Generation	30.6	70.0	0.0	894.4	0.0	199.2	0.0	0.0	6,698.6	
	Upgrade	0.0	0.0	0.0	6.4	0.0	27.3	0.0	0.0	33.7	
Under Construction	New Generation	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	4,191.1	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	100.0	
Suspended	New Generation	0.0	0.0	0.0	100.0	0.0	100.0	0.0	0.0	2,547.4	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	75.0	
Withdrawn	New Generation	60.0	0.0	0.0	4,897.6	0.0	2,706.3	20.0	0.0	57,889.6	
	Upgrade	0.0	0.0	0.0	80.0	0.0	6.0	0.0	0.0	367.0	
Active	New Generation	0.0	0.0	0.0	405.0	0.0	166.2	0.0	0.0	7,482.5	
	Upgrade	0.0	0.0	0.0	70.8	0.0	0.0	0.0	0.0	260.8	
Total Projects	New Generation	90.6	70.0	0.0	6,297.0	0.0	3,171.7	20.0	0.0	78,809.2	
	Upgrade	0.0	0.0	0.0	157.1	0.0	33.3	0.0	0.0	836.4	

Table 12-26 shows the status of all solar generation projects that have entered the PJM generation queue from January 1, 1997 through December 31, 2016, by zone. Out of a total of 1,082 solar projects in the PJM generation queue, 500 projects or 46.2 percent have been located in JCPL, AECO and PSEG, all zones in New Jersey. Of these three zones, AECO has the lowest completion rates for new generation and upgrade solar projects. Excluding currently active projects, only 5.1 percent of solar projects classified as new generation or upgrades in AECO are either in service or under construction. Of these three zones, PSEG has the highest completion rates. Excluding currently active projects, 43.6 percent of solar projects classified as either new generation or upgrades in PSEG are either in service or under construction.

The number of currently active new generation solar projects is also highly concentrated in several zones. Out of 200 active new generation projects, 108 projects, or 43.9 percent of all currently active new generation solar projects are located in Dominion.

Table 12-26 Status of all solar generation queue projects: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Number of Projects																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	5	4	2	0	1	1	1	0	6	9	0	0	34	0	1	0	0	2	36	0	102
	Upgrade	0	0	0	0	0	0	0	0	2	8	0	0	5	0	0	0	0	0	0	0	15
Under Construction	New Generation	3	4	9	0	2	0	2	0	12	9	0	0	14	0	0	0	0	2	8	0	65
	Upgrade	0	0	0	0	0	0	0	0	1	1	0	0	1	0	0	0	0	0	0	0	3
Suspended	New Generation	0	3	9	0	0	0	0	0	1	0	0	0	5	1	0	1	0	0	2	0	22
	Upgrade	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Withdrawn	New Generation	147	17	44	6	4	7	4	4	47	78	0	0	151	11	5	10	6	25	55	0	621
	Upgrade	1	1	0	0	0	0	0	0	1	0	0	0	5	0	0	0	0	0	0	0	8
Active	New Generation	10	28	10	2	6	3	4	1	100	48	0	1	8	2	1	0	2	2	8	0	236
	Upgrade	0	0	0	0	0	0	0	0	8	0	0	0	0	0	0	0	0	0	2	0	10
Total Projects	New Generation	165	56	74	8	13	11	11	5	166	144	0	1	212	14	7	11	8	31	109	0	1,046
	Upgrade	1	1	0	0	0	0	0	0	12	9	0	0	11	0	0	0	0	0	2	0	36

Table 12-27 shows the status of all solar generation project MW that have entered the PJM generation queue from January 1, 1997 through December 31, 2016, by zone. Out of a total of 42,191.4 MW of solar nameplate capacity in the PJM generation queue, 4,232.0 MW or 17.0 percent have been located in JCPL, AECO and PSEG, all of which are zones in New Jersey. Solar projects in Dominion have accounted for 11,559.9 MW or 46.5 percent of all solar project nameplate capacity in the PJM queue from January 1, 1997 through December 31, 2016. Solar projects in DPL have accounted for 2,679.4 MW or 10.8 percent of all solar project nameplate capacity in the PJM queue from January 1, 1997 through December 31, 2016.

Table 12-27 Current status of all solar generation capacity (MW) in the PJM generation queue: January 1, 1997 through December 31, 2016

Project Status	Project Classification	Project MW											
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC
In Service	New Generation	38.5	14.7	34.0	0.0	1.1	9.0	2.5	0.0	157.0	118.4	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3.1	0.0	0.0	0.0
Under Construction	New Generation	20.8	40.0	105.8	0.0	22.0	0.0	23.4	0.0	438.0	80.5	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	4.5	0.0	0.0	0.0
Suspended	New Generation	0.0	49.9	108.9	0.0	0.0	0.0	0.0	0.0	5.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Withdrawn	New Generation	1,628.8	332.3	750.1	60.1	9.2	84.8	51.5	63.0	1,536.2	1,148.5	0.0	0.0
	Upgrade	10.0	6.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0
Active	New Generation	64.2	2,310.2	451.4	326.0	22.1	27.0	199.6	125.0	8,819.1	1,332.0	0.0	80.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	588.9	0.0	0.0	0.0
Total Projects	New Generation	1,752.3	2,747.1	1,450.2	386.1	54.4	120.8	277.0	188.0	10,955.3	2,679.4	0.0	80.0
	Upgrade	10.0	6.0	0.0	0.0	0.0	0.0	0.0	0.0	604.5	0.0	0.0	0.0

Project Status	Project Classification	Project MW									TOTAL
		JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO		
In Service	New Generation	217.3	0.0	3.3	0.0	0.0	15.0	181.4	0.0	792.2	
	Upgrade	16.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	19.4	
Under Construction	New Generation	187.5	0.0	0.0	0.0	0.0	6.0	41.2	0.0	965.2	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	4.5	
Suspended	New Generation	59.0	3.0	0.0	13.5	0.0	0.0	9.7	0.0	249.0	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Withdrawn	New Generation	1,243.4	367.0	50.1	34.3	58.1	277.7	390.6	0.0	8,085.8	
	Upgrade	23.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	47.8	
Active	New Generation	58.3	135.0	20.0	0.0	60.0	30.0	39.4	0.0	14,099.3	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	1.7	0.0	590.6	
Total Projects	New Generation	1,765.5	505.0	73.4	47.8	118.1	328.7	662.4	0.0	24,191.4	
	Upgrade	40.1	0.0	0.0	0.0	0.0	0.0	1.7	0.0	662.3	

Table 12-28 shows the relationship between the project developer and Transmission Owner for every project that has entered the PJM generation queue from January 1, 1997 through December 31, 2016 by zone and technology type. A project where the developer is affiliated with the Transmission Owner is classified as related. A project where the developer is not affiliated with the Transmission Owner is classified as unrelated. For example, 36.0 MW of natural gas fired generation projects that have entered the PJM generation queue in DEOK were projects submitted by Duke Energy or subsidiaries of Duke Energy, the Transmission Owner for DEOK. There have been 154.5 MW of natural gas fired projects that have entered the PJM generation queue in DEOK by developers unrelated to Duke Energy.

Table 12-28 Relationship between project developer and Transmission Owner for all interconnection queue projects MW by fuel type: January 1, 1997 through December 31, 2016

Parent Company	Transmission Owner	Related To Developer	Number of Projects	MW by Fuel Type											Total MW
				Biomass	Coal	Diesel	Hydro	Landfill Gas	Natural Gas	Nuclear	Other	Solar	Wind		
AEP	AEP	Related	47	0.0	3,965.0	0.0	34.0	3.0	3,010.0	186.0	0.0	74.7	0.0	7,272.7	
		Unrelated	316	501.1	10,292.0	7.5	448.4	83.8	22,338.0	0.0	66.0	2,588.0	23,749.9	60,074.6	
AES	DAY	Related	15	0.0	1,347.5	0.0	0.0	0.0	51.0	0.0	0.0	4.0	0.0	1,402.5	
		Unrelated	28	1.9	0.0	0.0	0.0	10.0	9.0	0.0	0.0	223.1	2,128.0	2,372.0	
DLCO	DLCO	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	20	0.0	2,810.0	0.0	106.0	19.2	870.0	1,879.0	0.0	0.0	0.0	5,684.2	
Dominion	Dominion	Related	73	64.0	287.0	0.0	340.0	0.0	13,075.0	1,944.0	0.0	101.4	142.0	15,953.4	
		Unrelated	259	343.7	20.0	10.0	29.5	184.0	12,033.8	0.0	156.3	11,283.5	3,063.0	27,123.8	
Duke	DEOK	Related	4	0.0	0.0	0.0	0.0	0.0	36.0	0.0	0.0	0.0	0.0	36.0	
		Unrelated	14	0.0	70.0	0.0	112.0	4.8	154.5	0.0	0.0	188.0	0.0	529.3	
EKPC	EKPC	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	6	0.0	0.0	0.0	0.0	0.0	2,141.8	0.0	0.0	80.0	150.3	2,372.1	
Exelon	AECO	Related	3	0.0	0.0	0.0	0.0	0.0	730.0	0.0	0.0	0.0	0.0	730.0	
		Unrelated	265	29.8	15.0	13.0	0.0	31.0	9,782.8	0.0	0.0	1,772.1	3,808.9	15,452.6	
	BGE	Related	13	0.0	10.0	0.0	0.0	0.0	1,037.0	3,362.2	0.0	20.0	0.0	4,429.2	
		Unrelated	58	0.0	0.0	29.0	140.4	9.5	4,152.9	0.0	132.0	34.4	0.0	4,498.2	
	ComEd	Related	18	0.0	0.0	0.0	0.0	0.0	0.0	1,185.0	0.0	9.0	396.0	1,590.0	
		Unrelated	239	90.0	1,926.0	42.0	22.7	112.9	15,386.4	0.0	20.0	91.8	27,359.8	45,051.6	
	DPL	Related	10	0.0	0.0	0.0	0.0	0.0	1,716.0	0.0	0.0	31.4	0.0	1,747.4	
		Unrelated	232	66.0	653.0	0.0	0.0	27.6	6,656.6	0.0	30.0	2,644.2	2,809.6	12,887.0	
	PECO	Related	29	0.0	7.0	0.0	45.0	0.0	6,420.0	437.8	0.0	0.0	0.0	6,909.8	
		Unrelated	78	0.0	0.0	12.1	220.0	18.7	21,490.8	0.0	0.0	73.4	0.0	21,815.0	
	Pepco	Related	1	0.0	0.0	0.0	0.0	0.0	0.0	1,640.0	0.0	0.0	0.0	1,640.0	
		Unrelated	63	0.0	0.0	0.0	0.0	12.5	22,623.9	0.0	0.0	58.1	0.0	22,694.5	
First Energy	AP	Related	14	0.0	1,745.0	0.0	252.0	0.0	4,790.0	0.0	0.0	0.0	0.0	6,787.0	
		Unrelated	295	177.2	4,057.0	53.8	356.3	125.8	18,938.3	0.0	96.0	1,463.9	5,182.7	30,450.9	
	ATSI	Related	8	0.0	0.0	0.0	0.0	0.0	1,678.0	16.0	0.0	0.6	0.0	1,694.6	
		Unrelated	47	0.0	0.0	0.0	0.0	35.3	9,021.7	0.0	135.0	385.5	1,163.6	10,741.1	
	JCPL	Related	2	0.0	0.0	0.0	20.0	0.0	100.0	0.0	0.0	0.0	0.0	120.0	
		Unrelated	303	30.0	0.0	0.0	1.6	24.4	15,780.9	0.0	0.0	1,815.0	90.6	17,742.4	
	Met-Ed	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	88	90.4	0.0	8.0	0.0	57.9	16,839.6	93.0	11.0	505.0	70.0	17,674.9	
	PENELEC	Related	8	0.0	1,860.0	0.0	32.0	0.0	1,174.0	0.0	0.0	0.0	0.0	3,066.0	
		Unrelated	211	0.0	561.0	8.0	53.3	50.9	19,387.8	0.0	621.0	47.8	6,454.1	27,183.8	
PPL	PPL	Related	36	0.0	139.0	0.0	0.0	7.7	2,294.0	1,988.0	0.0	0.0	0.0	4,428.7	
		Unrelated	186	28.5	6,868.6	10.4	2.6	95.4	21,626.5	0.0	152.5	328.7	3,205.0	32,318.1	
PSEG	PSEG	Related	100	0.0	24.0	0.0	0.0	11.7	12,802.1	381.0	0.0	124.0	0.0	13,342.8	
		Unrelated	163	0.0	0.0	0.0	1,000.0	24.4	18,516.8	0.0	45.5	544.8	20.0	20,151.5	
Consolidated Edison, Inc.	RECO	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	1	0.0	0.0	0.0	0.0	0.0	6.0	0.0	0.0	0.0	0.0	6.0	
Total		Related	381	64.0	9,384.5	0.0	723.0	22.4	48,913.1	11,140.0	0.0	365.1	538.0	71,150.1	
		Unrelated	2,872	1,358.6	27,272.6	193.8	2,492.8	928.0	237,758.0	1,972.0	1,465.3	24,127.1	79,255.5	376,823.7	

Table 12-29 shows the relationship between the project developer and Transmission Owner for every solar project that has entered the PJM generation queue from January 1, 1997 through December 31, 2016 by zone and project status. A project where the developer is affiliated with the Transmission Owner is classified as related. A project where the developer is not affiliated with the Transmission Owner is classified as unrelated. PSEG is the zone that has had the most solar MW built by the incumbent Transmission Owner.

Table 12-29 Relationship between project developer and Transmission Owner for all solar project MW in PJM interconnection queue: January 1, 1997 through December 31, 2016

Parent Company	Transmission Owner	Related To Developer	MW by Project Status				
			IS	UC	Suspended	W	Active
AEP	AEP	Related	2.5	12.2	0.0	0.0	60.0
		Unrelated	0.0	20.0	51.7	336.5	2,310.2
AES	DAY	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	2.5	23.4	0.0	51.5	199.6
DLCO	DLCO	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0
Dominion	Dominion	Related	20.0	0.0	0.0	7.0	74.4
		Unrelated	140.1	122.9	205.0	1,511.2	9,762.3
Duke	DEOK	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	63.0	125.0
EKPC	EKPC	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	80.0
Exelon	AECO	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	38.5	20.8	0.0	1,638.8	74.0
	BGE	Related	0.0	20.0	0.0	0.0	0.0
		Unrelated	1.1	2.0	0.0	9.2	22.1
	ComEd	Related	9.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	84.8	27.0
	DPL	Related	7.4	0.0	0.0	24.0	0.0
		Unrelated	21.0	159.5	0.0	1,094.5	1,541.2
	PECO	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	3.3	0.0	0.0	50.1	20.0
	Pepco	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	58.1	60.0
First Energy	AP	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	34.0	32.5	38.9	692.2	666.3
	ATSI	Related	0.0	0.0	0.0	0.6	0.0
		Unrelated	0.0	0.0	0.0	59.5	326.0
	JCPL	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	204.1	175.5	92.9	1,235.2	111.7
	Met-Ed	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	3.0	367.0	135.0
	PENELEC	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	13.5	34.3	0.0
PPL	PPL	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	15.0	16.0	0.0	267.7	30.0
PSEG	PSEG	Related	105.8	10.0	0.0	8.2	0.0
		Unrelated	53.8	46.2	9.7	382.5	53.0
Consolidated Edison, Inc.	RECO	Related	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0
Total		Related	144.7	42.2	0.0	39.8	134.4
		Unrelated	513.4	618.8	414.7	7,935.9	15,543.4

Transmission Facility Outages

Scheduling Transmission Facility Outage Requests

A transmission facility is designated as reportable by PJM if a change in its status can affect a transmission constraint on any Monitored Transmission Facility or could impede free flowing ties within the PJM RTO and/or adjacent areas.²⁸ When one of the reportable transmission facilities needs to be taken out of service, the TO is required to submit an outage request as early as possible. The specific timeline is shown in Table 12-31.²⁹

Transmission outages have significant impacts on PJM markets. There are impacts on FTR auctions, on congestion, and on expected market outcomes in the day-ahead and real-time markets. It is important for the efficient functioning of the markets that there be clear, enforceable rules governing transmission outages.

Transmission outages are categorized by duration: greater than 30 calendar days; less than or equal to 30 calendar days and greater than five calendar days; or less than or equal to five calendar days.³⁰ Table 12-30 shows that 77.5 percent of the requested outages were planned for less than or equal to five days and 6.6 percent of requested outages were planned for greater than 30 days in 2016. All of the outage data in this section except in the analysis for the FTR market are for outages scheduled to occur in 2015 and 2016, regardless of when they were initially submitted.³¹ The outage data in the analysis for the FTR market are for outages scheduled to occur in the planning periods 2015 to 2016 and 2016 to 2017.

²⁸ If a transmission facility is not modeled in the PJM EMS or the facility is not expected to significantly impact PJM system security or congestion management, it is not reportable. See PJM. "Manual 3A: Energy Management System (EMS) Model Updates and Quality Assurance (QA), Revision 12 (September 30, 2016).

²⁹ See PJM. "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p.68.

³⁰ See PJM. "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p.70.

³¹ The hotline tickets, EMS tripping tickets or test outage tickets were excluded. We only included all the transmission outage tickets submitted by PJM internal companies which are currently active.

Table 12-30 Transmission facility outage request summary by planned duration: 2015 and 2016

Planned Duration (Days)	2015		2016	
	Outage Requests	Percent	Outage Requests	Percent
<=5	15,527	77.3%	15,670	77.5%
>5 & <=30	3,177	15.8%	3,212	15.9%
>30	1,388	6.9%	1,332	6.6%
Total	20,092	100.0%	20,214	100.0%

After receiving a transmission facility outage request from a TO, PJM assigns a received status to the request based on its submission date and outage planned duration. The received status can be On Time or Late, as defined in Table 12-31.³²

The purpose of the rules defined in Table 12-31 is to require the TOs to submit transmission facility outages prior to the Financial Transmission Right (FTR) auctions so that market participants have complete information about market conditions on which to base their FTR bids and so that PJM can accurately model market conditions.³³

Table 12-31 PJM transmission facility outage request received status definition

Planned Duration (Calendar Days)	Request Submitted	Received Status
<=5	Before the 1st of the month one month prior to the starting month of the outage	On Time
	After or on the 1st of the month one month prior to the starting month of the outage	Late
> 5 & <=30	Before the 1st of the month six months prior to the starting month of the outage	On Time
	After or on the 1st of the month six months prior to the starting month of the outage	Late
>30	The earlier of 1) February 1st, 2) the 1st of the month six months prior to the starting month of the outage	On Time
	After or on the earlier of 1) February 1st, 2) the 1st of the month six months prior to the starting month of the outage	Late

Table 12-32 shows a summary of requests by received status. In 2016, 51.7 percent of outage requests received were late.

Table 12-32 Transmission facility outage request summary by received status: 2015 and 2016

Planned Duration (Days)	2015				2016			
	On Time	Late	Total	Percent Late	On Time	Late	Total	Percent Late
<=5	8,077	7,450	15,527	48.0%	7,798	7,872	15,670	50.2%
>5 & <=30	1,551	1,626	3,177	51.2%	1,521	1,691	3,212	52.6%
>30	518	870	1,388	62.7%	451	881	1,332	66.1%
Total	10,146	9,946	20,092	49.5%	9,770	10,444	20,214	51.7%

Once received, PJM processes outage requests in priority order: emergency transmission outage request; transmission outage requests submitted on time; and transmission outage request submitted late. PJM retains the right to deny all transmission outage requests that are submitted late unless the request is an emergency.

Outages with emergency status will be approved even if submitted late after PJM determines that the outage does not result in Emergency Procedures. PJM cancels or withholds approval of any outage that results in Emergency Procedures.³⁴ Table 12-33 is a summary of outage requests by emergency status. Of all outage requests scheduled to occur in 2016, 13.7 percent were for emergency outages. Of all outage requests scheduled to occur in 2015, 13.4 percent were for emergency outages.

³² See PJM, "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p.69 and p.70.

³³ See "Report of PJM Interconnection, L.L.C. on Transmission Oversight Procedures," Docket No. EL01-122-000 (November 2, 2001).

³⁴ PJM, "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p. 80.

Table 12-33 Transmission facility outage request summary by emergency: 2015 and 2016

Planned Duration (Days)	2015				2016			
	Emergency	Non Emergency	Total	Percent Emergency	Emergency	Non Emergency	Total	Percent Emergency
<=5	2,104	13,423	15,527	13.6%	2,183	13,487	15,670	13.9%
>5 <=30	418	2,759	3,177	13.2%	415	2,797	3,212	12.9%
>30	177	1,211	1,388	12.8%	172	1,160	1,332	12.9%
Total	2,699	17,393	20,092	13.4%	2,770	17,444	20,214	13.7%

PJM will approve all transmission outage requests that are submitted on time and do not jeopardize the reliability of the PJM system. PJM will approve all transmission outage requests that are submitted late and are not expected to cause congestion on the PJM system and do not jeopardize the reliability of the PJM system. Each outage is studied and if it is expected to cause a constraint to exceed a limit, PJM will flag the outage ticket as “congestion expected.”³⁵

After PJM determines that a late request may cause congestion, PJM informs the Transmission Owner of solutions available to eliminate the congestion. For example, if a generator planned or maintenance outage request is contributing to the congestion, PJM can request that the Generation Owner defer the outage. If no solutions are available, PJM may require the Transmission Owner to reschedule or cancel the outage. Table 12-34 is a summary of outage requests by congestion status. Of all outage requests submitted to occur in 2016, 8.7 percent were expected to cause congestion. Of all the outage requests that were expected to cause congestion, 4.2 percent (73 out of 1,757) were denied by PJM in 2016 and 20.5 percent (361 out of 1,757) were cancelled (Table 12-36).

Table 12-34 Transmission facility outage request summary by congestion: 2015 and 2016

Planned Duration (Days)	2015				2016			
	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
<=5	1,426	14,101	15,527	9.2%	1,301	14,369	15,670	8.3%
>5 <=30	363	2,814	3,177	11.4%	344	2,868	3,212	10.7%
>30	132	1,256	1,388	9.5%	112	1,220	1,332	8.4%
Total	1,921	18,171	20,092	9.6%	1,757	18,457	20,214	8.7%

35 PJM added this definition to Manual 38 in February 2017. PJM. "Manual 38: Operations Planning," Revision 10 (February 1, 2017), p. 17.

Table 12-35 shows the outage requests summary by received status, congestion status and emergency status. In 2016, 38.0 percent of requests were submitted late and were nonemergency while 1.8 (367 out of 20,214) percent of requests were late, nonemergency, and expected to cause congestion.

Table 12-35 Transmission facility outage requests that by received status, congestion and emergency: 2015 and 2016

Submission Status		2015				2016			
		Congestion Expected	No Congestion Expected	Total	Percent	Congestion Expected	No Congestion Expected	Total	Percent
Late	Emergency	113	2,569	2,682	13.3%	100	2,654	2,754	13.6%
	Non Emergency	346	6,918	7,264	36.2%	367	7,323	7,690	38.0%
On Time	Emergency	3	14	17	0.1%	1	15	16	0.1%
	Non Emergency	1,459	8,670	10,129	50.4%	1,289	8,465	9,754	48.3%
Total		1,921	18,171	20,092	100.0%	1,757	18,457	20,214	100.0%

Once PJM processes an outage request, the outage request is labelled as Submitted, Received, Denied, Approved, Cancelled by Company, PJM Admin Closure, Revised, Active or Complete according to the processed stage of a request.³⁶ Table 12-36 shows the detailed process status for outage requests only for the outage requests that are expected to cause congestion. Status Submitted and status Received are in the In Process category and status Cancelled by Company and status PJM Admin Closure are in the Cancelled category in Table 12-36. Table 12-36 shows that of all the outage requests that were expected to cause congestion, 4.2 percent (73 out of 1,757) were denied by PJM in 2016, 75.0 percent were complete and 20.5 percent (361 out of 1,757) were cancelled.

36 See PJM. "Outage Information," <<http://www.pjm.com/markets-and-operations/etools/oasis/system-information/outage-info.aspx>> (November 1, 2015).

Table 12-36 Transmission facility outage requests that might cause congestion status summary: 2015 and 2016

Submission Status		2015						2016					
		Cancelled	Complete	In Process	Denied	Congestion Expected	Percent Complete	Cancelled	Complete	In Process	Denied	Congestion Expected	Percent Complete
Late	Emergency	12	100	0	1	113	88.5%	4	94	1	1	100	94.0%
	Non Emergency	66	252	2	26	346	72.8%	67	253	4	43	367	68.9%
On Time	Emergency	0	3	0	0	3	100.0%	0	1	0	0	1	100.0%
	Non Emergency	387	1,020	2	50	1,459	69.9%	290	969	1	29	1,289	75.2%
Total		465	1,375	4	77	1,921	71.6%	361	1,317	6	73	1,757	75.0%

There are clear rules defined for assigning On Time or Late status for submitted outage requests in both the PJM Tariff and PJM Manuals.³⁷ However, the On Time or Late status only affects the priority that PJM assigns for processing the outage request. Many (68.9 percent or 253 out of 367) outages that were nonemergency, expected to cause congestion, and late transmission outages were approved and completed. The expected impact on congestion is the basis for PJM's treatment of late outage requests. But there is no rule or clear definition of this congestion analysis in the PJM Manuals. The MMU recommends that PJM draft a clear definition of the congestion analysis required for transmission outage requests to include in Manual 3 after appropriate review.

Rescheduling Transmission Facility Outage Requests

A TO can reschedule or cancel an outage after initial submission. Table 12-37 is a summary of all the outage requests planned for 2015 and 2016 which were approved and then cancelled or rescheduled by TOs at least once. If an outage request was submitted, approved and subsequently rescheduled at least once, the outage request will be counted as Approved and Rescheduled. If an outage request was submitted, approved and subsequently cancelled at least once, the outage request will be counted as Approved and Cancelled. In 2016, 1.7 percent of transmission outage requests were approved by PJM and then rescheduled by the TOs, and 1.9 percent of the transmission outages were approved by PJM and subsequently cancelled by the TOs.

Table 12-37 Rescheduled and cancelled transmission outage request summary: 2015 and 2016

Days	Outage Requests	2015				2016				
		Approved and Rescheduled	Percent Approved and Rescheduled	Approved and Cancelled	Percent Approved and Cancelled	Outage Requests	Approved and Rescheduled	Percent Approved and Rescheduled	Approved and Cancelled	Percent Approved and Cancelled
<=5	102,667	2,003	2.0%	2,465	2.4%	95,754	1,695	1.8%	2,000	2.1%
>5 <=30	18,170	278	1.5%	211	1.2%	16,499	204	1.2%	180	1.1%
>30	8,052	126	1.6%	74	0.9%	6,345	76	1.2%	51	0.8%
Total	128,889	2,407	1.9%	2,750	2.1%	118,598	1,975	1.7%	2,231	1.9%

If a requested outage is determined to be late and TO reschedules the outage, the outage will be reevaluated by PJM again as On Time or Late.

A transmission outage ticket with a duration of five days or less with an On Time status can retain its On Time status if the outage is rescheduled within the original scheduled month.³⁸ This rule allows a TO to reschedule within the same month with very little notice.

A transmission outage ticket with a duration exceeding five days with an On Time status can retain its On Time status if the outage is rescheduled to a future month, and the revision is submitted by the first of the month prior to the revised month in which the outage will occur.³⁹ This rescheduling rule is much less strict than the rule that applies to the first submission of outage requests with similar duration. When first submitted, the outage request with

37 OATT Attachment K Appendix § 1.9.2 (Planned Outages).

38 PJM. "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p. 70.

39 PJM. "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p. 70.

a duration exceeding five days needs to be submitted before the first of the month nine months prior to the month in which the outage was expected to occur.

The MMU recommends that PJM reevaluate all transmission outage tickets as On Time or Late as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages.

Long Duration Transmission Facility Outage Requests

PJM rules (Table 12-31) define a transmission outage request as On Time or Late based on the planned outage duration and the time of submission. The rule has stricter submission requirements for transmission outage requests planned for longer than 30 days. In order to avoid the stricter submission requirement, some transmission owners divided the duration of outage requests longer than 30 days into shorter segments for the same equipment and submitted one request for each segment. The MMU recommends that PJM not permit transmission owners to divide long duration outages into smaller segments to avoid complying with the requirements for long duration outages. Table 12-38 shows that there were 12,141 transmission equipment planned outages in 2016, of which 1,375 were planned outages longer than 30 days, and of which 205 or 1.7 percent were scheduled longer than 30 days if the duration of the outages were combined for the same equipment. The duration of those outages could potentially be longer than 30 days, however were divided into shorter periods by transmission owners.

Table 12-38 Transmission outage summary: 2015 and 2016

Duration	Divided into Shorter Periods	2015		2016	
		Number of Outages	Percent	Number of Outages	Percent
> 30 Days	No	1,207	10.5%	1,170	9.6%
	Yes	181	1.6%	205	1.7%
<= 30 Days		10,108	87.9%	10,766	88.7%
Total		11,496	100.0%	12,141	100.0%

Table 12-39 shows the details of potentially long duration (> 30 days) outages when combining the duration of the outages for the same equipment. The actual duration of scheduled outages would be longer than 30 days if the duration of the outages were combined for the same equipment within a period of days. In 2016, there would

have been two outages with a combined duration longer than 30 days that were instead scheduled to occur as shorter outages within a period of less than or equal to 31 days. In 2016, there would have been 32 outages with a combined duration longer than 30 days that were instead scheduled to occur as shorter outages within a period of more than 31 days and less than 62 days.

Table 12-39 Summary of potentially long duration (> 30 days) outages: 2015 and 2016

Days	2015		2016	
	Number of Outages	Percent	Number of Outages	Percent
<=31	4	2.2%	2	1.0%
>31 & <=62	12	6.6%	32	15.6%
>62 and <=93	18	9.9%	19	9.3%
>93	147	81.2%	152	74.1%
Total	181	100.0%	205	100.0%

Transmission Facility Outage Analysis for the FTR Market

Transmission facility outages affect the price and quantity outcomes of FTR auctions. The purpose of the rules is to ensure that outages are known with enough lead time prior to FTR auctions so that market participants can understand market conditions and so that PJM can accurately model market conditions. Outage requests must be submitted according to rules based on planned outage duration (Table 12-31). The rules defining when an outage is late are based on the timing of FTR auctions. When an outage request is submitted late, the outage will be marked as Late and may be denied if it is expected to cause congestion. Table 12-43 shows that 792 outage requests with a duration of two weeks or longer but shorter than two months were late, and only one of them were denied by PJM and 9.0 percent were cancelled. Table 12-43 also shows that 399 outage requests with a duration of two months or longer were late and only one of them were denied by PJM and 9.5 percent were cancelled in the 2016 to 2017 planning year.

There are Long Term, Annual and Monthly Balance of Planning Period auctions in the FTR market. When determining transmission outages to be modeled in the annual ARR allocation and FTR auction, PJM does not consider outages with planned durations shorter than two weeks, does consider some outages with planned duration longer than two weeks but shorter than two months, and does consider all

outages with planned duration longer than or equal to two months. PJM may exercise significant discretion in selecting outages to be modeled. PJM posts an FTR outage list to the FTR web page usually at least one week before the auction bidding opening day.⁴⁰

Table 12-40 shows that 85.5 percent of the outage requests for outages expected to occur during the planning period 2016 to 2017 had a planned duration of less than two weeks and that 46.0 (7,031 out of 15,274) percent of all outage requests for the planning period were submitted late according to outage submission rules.

Table 12-40 Transmission facility outage requests by received status: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	2015/2016				2016/2017			
	On Time	Late	Total	Percent	On Time	Late	Total	Percent
<2 weeks	8,797	8,814	17,611	87.0%	7,216	5,840	13,056	85.5%
>=2 weeks & <2 months	853	1,022	1,875	9.3%	827	792	1,619	10.6%
>=2 months	225	523	748	3.7%	200	399	599	3.9%
Total	9,875	10,359	20,234	100.0%	8,243	7,031	15,274	100.0%

Table 12-41 shows outage requests summary by emergency status. Of all outage requests for outages expected to occur in the 2016 to 2017 planning year and submitted late, 73.8 percent were for nonemergency outages.

Table 12-41 Transmission facility outage requests by received status and emergency: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	2015/2016				2016/2017			
	Emergency	Non		Total	Emergency	Non		Total
		Emergency	Non			Emergency	Non	
On Time								
<2 weeks	16	8,781	8,797	99.8%	10	7,206	7,216	99.9%
>=2 weeks & <2 months	4	849	853	99.5%	2	825	827	99.8%
>=2 months	0	225	225	100.0%	0	200	200	100.0%
Total	20	9,855	9,875	99.8%	12	8,231	8,243	99.9%
Late								
<2 weeks	2,399	6,415	8,814	72.8%	1,630	4,210	5,840	72.1%
>=2 weeks & <2 months	174	848	1,022	83.0%	138	654	792	82.6%
>=2 months	102	421	523	80.5%	75	324	399	81.2%
Total	2,675	7,684	10,359	74.2%	1,843	5,188	7,031	73.8%

PJM analyzes expected congestion for both On time and Late outage requests. A Late outage request may be denied or cancelled if it is expected to cause congestion. Table 12-42 shows a summary of requests by expected congestion and received status. Overall, 5.1 percent of all outage requests for outages expected to occur in the 2016 to 2017 planning year and submitted late were requests that were expected to cause congestion.

Table 12-42 Transmission facility outage requests by submission status and congestion: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	2015/2016				2016/2017			
	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
On Time								
<2 weeks	1,151	7,646	8,797	13.1%	885	6,331	7,216	12.3%
>=2 weeks & <2 months	172	681	853	20.2%	132	695	827	16.0%
>=2 months	46	179	225	20.4%	34	166	200	17.0%
Total	1,369	8,506	9,875	13.9%	1,051	7,192	8,243	12.8%
Late								
<2 weeks	371	8,443	8,814	4.2%	296	5,544	5,840	5.1%
>=2 weeks & <2 months	49	973	1,022	4.8%	47	745	792	5.9%
>=2 months	18	505	523	3.4%	14	385	399	3.5%
Total	438	9,921	10,359	4.2%	357	6,674	7,031	5.1%

⁴⁰ PJM Financial Transmission Rights, "Annual ARR Allocation and FTR Auction Transmission outage Modeling," <<http://www.pjm.com/~media/markets-ops/ftr/annual-ftr-auction/2015-2016/2015-2016-annual-outage-modeling.ashx>> (April 1, 2015).

Table 12-43 shows that 69.2 percent of late outage requests with a duration of two weeks or longer but shorter than two months were active or completed, one was denied by PJM and 9.0 percent were cancelled in the 2016 to 2017 planning year. Table 12-43 also shows that 56.6 percent of late outage requests with duration of two months or longer were active or completed, one of them was denied, and 9.5 percent were cancelled in the 2016 to 2017 planning year.

Table 12-43 Transmission facility outage requests by received status and processed status: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	Processed Status	2015/2016				2016/2017			
		On Time	Percent	Late	Percent	On Time	Percent	Late	Percent
<2 weeks	In Progress	16	0.2%	144	1.6%	2,025	28.1%	299	5.1%
	Denied	39	0.4%	36	0.4%	26	0.4%	44	0.8%
	Approved	0	0.0%	0	0.0%	36	0.5%	44	0.8%
	Cancelled	2,416	27.5%	1,062	12.0%	1,477	20.5%	658	11.3%
	Revised	0	0.0%	0	0.0%	14	0.2%	3	0.1%
	Active	0	0.0%	1	0.0%	12	0.2%	17	0.3%
	Completed	6,326	71.9%	7,571	85.9%	3,626	50.2%	4,775	81.8%
Total Submission		8,797	100.0%	8,814	100.0%	7,216	100.0%	5,840	100.0%
>=2 weeks & <2 months	In Progress	0	0.0%	13	1.3%	301	36.4%	115	14.5%
	Denied	0	0.0%	0	0.0%	1	0.1%	1	0.1%
	Approved	0	0.0%	0	0.0%	1	0.1%	2	0.3%
	Cancelled	236	27.7%	92	9.0%	164	19.8%	71	9.0%
	Revised	0	0.0%	0	0.0%	0	0.0%	0	0.0%
	Active	0	0.0%	0	0.0%	10	1.2%	55	6.9%
	Completed	617	72.3%	917	89.7%	350	42.3%	548	69.2%
Total Submission		853	100.0%	1,022	100.0%	827	100.0%	792	100.0%
>=2 months	In Progress	0	0.0%	9	1.7%	30	15.0%	39	9.8%
	Denied	0	0.0%	0	0.0%	0	0.0%	1	0.3%
	Approved	0	0.0%	0	0.0%	0	0.0%	2	0.5%
	Cancelled	45	20.0%	46	8.8%	50	25.0%	38	9.5%
	Revised	0	0.0%	0	0.0%	0	0.0%	0	0.0%
	Active	4	1.8%	30	5.7%	35	17.5%	93	23.3%
	Completed	176	78.2%	438	83.7%	85	42.5%	226	56.6%
Total Submission		225	100.0%	523	100.0%	200	100.0%	399	100.0%

Table 12-44 shows that there were 792 outage requests with a duration of two weeks or longer but shorter than two months submitted late, of which 45 were nonemergency and expected to cause congestion in the 2016 to 2017 planning year. Of the 45 such requests, 9 were in process, one was denied, four were cancelled, and 30 were active or complete. For the outages planned for two months or longer, there were 399 total outages submitted late, of which 13 requests were nonemergency. Of those requests, three were in process, three were cancelled and six were active or complete.

Table 12-44 Transmission facility outage requests by received status, processed status, emergency and congestion: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	Processed Status	2015/2016						2016/2017					
		On Time			Late			On Time			Late		
		Non Emergency and Congestion Expected	Total	Percent									
<2 weeks	In Progress	0	16	0.0%	1	144	0.7%	184	2,025	9.1%	12	299	4.0%
	Denied	32	39	82.1%	18	36	50.0%	20	26	76.9%	31	44	70.5%
	Approved	0	0	0.0%	0	0	0.0%	6	36	16.7%	3	44	6.8%
	Cancelled	305	2,416	12.6%	61	1,062	5.7%	167	1,477	11.3%	37	658	5.6%
	Revised	0	0	0.0%	0	0	0.0%	2	14	14.3%	0	3	0.0%
	Active	0	0	0.0%	0	1	0.0%	2	12	16.7%	0	17	0.0%
	Completed	811	6,326	12.8%	205	7,571	2.7%	503	3,626	13.9%	136	4,775	2.8%
Total Submission		1,148	8,797	13.0%	285	8,814	3.2%	884	7,216	12.3%	219	5,840	3.8%
>=2 weeks & <2 months	In Progress	0	0	0.0%	1	13	7.7%	49	301	16.3%	9	115	7.8%
	Denied	0	0	0.0%	0	0	0.0%	1	1	100.0%	1	1	100.0%
	Approved	0	0	0.0%	0	0	0.0%	0	1	0.0%	1	2	50.0%
	Cancelled	31	236	13.1%	5	92	5.4%	13	164	7.9%	4	71	5.6%
	Revised	0	0	0.0%	0	0	0.0%	0	0	0.0%	0	0	0.0%
	Active	0	0	0.0%	0	0	0.0%	1	10	10.0%	5	55	9.1%
	Completed	141	617	22.9%	39	917	4.3%	68	350	19.4%	25	548	4.6%
Total Submission		172	853	20.2%	45	1,022	4.4%	132	827	16.0%	45	792	5.7%
>=2 months	In Progress	0	0	0.0%	0	9	0.0%	5	30	16.7%	3	39	7.7%
	Denied	0	0	0.0%	0	0	0.0%	0	0	0.0%	1	1	100.0%
	Approved	0	0	0.0%	0	0	0.0%	0	0	0.0%	0	2	0.0%
	Cancelled	3	45	6.7%	2	46	4.3%	6	50	12.0%	3	38	7.9%
	Revised	0	0	0.0%	0	0	0.0%	0	0	0.0%	0	0	0.0%
	Active	0	4	0.0%	0	30	0.0%	3	35	8.6%	1	93	1.1%
	Completed	43	176	24.4%	15	438	3.4%	20	85	23.5%	5	226	2.2%
Total Submission		46	225	20.4%	17	523	3.3%	34	200	17.0%	13	399	3.3%

Even if an outage were submitted on time according to the transmission outage rules, it would not be modeled in the FTR model if it were submitted after the Annual FTR Auction bidding opening date. Table 12-45 shows that 62.5 percent of outage requests with duration longer than two weeks and shorter than two months labelled on time according to rules were submitted or rescheduled after the Annual FTR Auction bidding opening date in the 2016 to 2017 planning year. It also shows that 34.0 percent of outage requests with duration longer than or equal to two months labelled on time according to rules were submitted or rescheduled after the Annual FTR Auction bidding opening date in the 2016 to 2017 planning year.

Table 12-45 Transmission facility outage requests by received status and bidding opening date: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	2015/2016						2016/2017					
	On Time			Late			On Time			Late		
	Before Bidding Opening Date	After Bidding Opening Date	Percent After									
<2 weeks	766	8,031	91.3%	181	8,633	97.9%	830	6,386	88.5%	134	5,706	97.7%
>=2 weeks & <2 months	316	537	63.0%	126	896	87.7%	310	517	62.5%	68	724	91.4%
>=2 months	131	94	41.8%	189	334	63.9%	132	68	34.0%	166	233	58.4%
Total	1,213	8,662	87.7%	496	9,863	95.2%	1,272	6,971	84.6%	368	6,663	94.8%

Table 12-46 shows that 78.9 percent of late outage requests which were submitted or rescheduled after the Annual FTR Auction bidding opening date were approved and complete in the 2016 to 2017 planning.

Table 12-46 Late transmission facility outage requests that are submitted after annual bidding opening date: Planning periods 2015 to 2016 and 2016 to 2017

Planned Duration	2015/2016			2016/2017		
	Completed Outages	Total	Percent	Completed Outages	Total	Percent
<2 weeks	7,407	8,633	85.8%	4,653	5,706	81.5%
>=2 weeks & <2 months	799	896	89.2%	497	724	68.6%
>=2 months	282	334	84.4%	110	233	47.2%
Total	8,488	9,863	86.1%	5,260	6,663	78.9%

Thus, although the definition of late outages was developed in order to prevent outages for the planning period being submitted after the Annual FTR Auction bidding opening date, the rules have not worked to prevent this since the rule has no direct connection to the Annual FTR Auction opening date. By requiring all long-duration transmission outages to be submitted before February 1, PJM outage submission rules only prevent long-duration transmission outages from being submitted late. The rule does not address the situation in which long-duration transmission outages are submitted on-time, but are rescheduled so that they are late. The Annual FTR Auction model may consider transmission outages planned for longer than two weeks but less than two months. Those outages not only include long-duration but also include outages shorter than 30 days. In those cases, PJM outage submission rules failed to prevent long-duration transmission outages submitted late. The MMU recommends that PJM modify the rules to reduce or eliminate the approval of late outage requests submitted or rescheduled after the Annual FTR Auction bidding opening date.

Transmission Facility Outage Analysis in the Day-Ahead Energy Market

Transmission facility outages also affect the energy market. Just as with the FTR market, it is critical that outages that affect the operating day are known prior to the submission of offers in the Day-Ahead Energy Market so that market participants can understand market conditions and so that PJM can accurately model market conditions in the day-ahead market. PJM requires transmission owners to submit changes to outages scheduled for the next two days no later than 09:30 am.⁴¹

In order to analyze the market impact, the outage requests that affect the operating day are compared: before the day-ahead market is closed; when the day-ahead market save cases are created; and during the operating day. The list of approved or active outage requests before the day-ahead market is closed is the view of outages available to market participants.

The day-ahead market model uses a list of outages as an input. The list of outages that actually occurred during the operating day are the outages that affect the real-time market. If the three sets of outages are the same, there is no potential impact on markets. If the three sets of outages differ, there is a potential impact on markets.

For example for the operating day of November 23, 2016, Figure 12-4 shows that: there were 421 approved or active outages seen by market participants before the day-ahead market was closed; there were 282 outage requests included in the day-ahead market model; there were 273 outage request included in both sets of outage; there were 148 outage requests approved or active before the day-ahead market was closed but not included as inputs in day-ahead market model; and there were 9 outage requests included in day-ahead market model but not available to market participants prior to the day-ahead market.

⁴¹ PJM. "Manual 3: Transmission Operations," Revision 50 (December 1, 2016), p. 74

Figure 12-4 Illustration of day-ahead market analysis on November 22, 2016




Figure 12-5 compares the weekly average number of active or approved outages available to market participants prior to the close of the day-ahead market with the outages included as inputs to the day-ahead market by PJM.

Figure 12-5 Weekly average number of approved or active outage requests comparing day-ahead market model outages: 2015 and 2016




Figure 12-6 compares the weekly average number of outages included as inputs to the day-ahead market by PJM with the outages that actually occurred during the operating day.

Figure 12-6 Weekly average number of day-ahead market model outages comparing outages occurred on operating day: 2015 and 2016




Figure 12-7 compares the weekly average number of active or approved outages available to market participants prior to the close of the day-ahead market with the outages that actually occurred during the operating day.

Figure 12-7 Weekly average number of approved or active outage requests comparing outages occurred on operating day: 2015 and 2016




Figure 12-5, Figure 12-6, and Figure 12-7 show that on a weekly average basis, the active or approved outages available to day-ahead market participants, the outages included as inputs in the day-ahead market model and the outages that actually occurred in real time are not consistent. The active or approved outages available to day-ahead market participants are more consistent with the outages that actually occurred in real time than with the outages included in the day-ahead market model.