

## Generation and Transmission Planning

### Overview

#### Planned Generation and Retirements

- **Planned Generation.** As of March 31, 2016, 81,936.3 MW of capacity were in generation request queues for construction through 2024, compared to an average installed capacity of 187,281.3 MW as of March 31, 2016. Of the capacity in queues, 5,999.7 MW, or 7.3 percent, are uprates and the rest are new generation. Wind projects account for 15,686.2 MW of nameplate capacity or 19.1 percent of the capacity in the queues. Combined cycle projects account for 53,202.8 MW of capacity or 64.9 percent of the capacity in the queues.
- **Generation Retirements.** As shown in Table 12-6, 26,486.5 MW have been, or are planned to be, retired between 2011 and 2020. Of that, 2,997.3 MW are planned to retire after 2016. In the first three months of 2016, 53 MW were retired. Of the 2,656.8 MW pending retirement, 1,263 MW are coal units. The coal unit retirements were a result of low gas prices, and the EPA's Mercury and Air Toxics Standards (MATS) for some units.
- **Generation Mix.** A significant shift in the distribution of unit types within the PJM footprint continues as natural gas fired units enter the queue and steam units retire. There are 1,957.0 MW of coal fired steam capacity and 56,645.1 MW of gas fired capacity in the queue. The replacement of coal steam units by units burning natural gas could significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

#### Generation and Transmission Interconnection Planning Process

- Any entity that requests interconnection of a new generating facility, including increases to the capacity of an existing generating unit, or that requests interconnection of a merchant transmission facility, must follow the process defined in the PJM tariff to obtain interconnection

service.<sup>1</sup> The process is complex and time consuming at least in part as a result of the required analyses. The cost, time and uncertainty associated with interconnecting to the grid may create barriers to entry for potential entrants.

- The queue contains a substantial number of projects that are not likely to be built. Excluding currently active projects and projects currently under construction, 2,329 projects, representing 334,777.6 MW, have completed the queue process since its inception. Of those, 621 projects, 43,797.8 MW, went into service. Of the projects that entered the queue process, 86.9 percent of the MW withdrew prior to completion. Such projects may create barriers to entry for projects that would otherwise be completed by taking up queue positions, increasing interconnection costs and creating uncertainty.
- Feasibility, impact and facilities studies may be delayed for reasons including disputes with developers, circuit and network issues and retooling as a result of projects being withdrawn. The Earlier Queue Submittal Task Force (EQSTF) was established in August 2015 to address delays.<sup>2</sup>
- As defined in the tariff, a transmission owner (TO) is an “entity that owns, leases or otherwise has a possessory interest in facilities used for the transmission of electric energy in interstate commerce under the tariff.”<sup>3</sup> Where the transmission owner is a vertically integrated company that also owns generation, there is a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is a competitor to the generation of the parent company and when the transmission owner evaluates the interconnection requirements of new generation which is part of the same company as the transmission owner. There is also a potential conflict of interest when the transmission owner evaluates the interconnection requirements of a merchant transmission developer which is a competitor of the transmission owner.

<sup>1</sup> See PJM, OATT Parts IV & VI.

<sup>2</sup> See Earlier Queue Submittal Task Force at <<http://www.pjm.com/committees-and-groups/task-forces/eqstf.aspx>>

<sup>3</sup> See PJM, OATT, Part I, S 1 “Definitions.”

## Regional Transmission Expansion Plan (RTEP)

- Artificial Island is an area in southern New Jersey that includes nuclear units at Salem and at Hope Creek in the PSEG Zone. On April 29, 2013, PJM issued a request for proposal (RFP), seeking technical solutions to improve stability issues and operational performance under a range of anticipated system conditions, and the elimination of potential planning criteria violations in this area. On July 30, 2015, the PJM Board of Managers accepted PJM's recommendation to assign the project to LS Power, a merchant developer, PSEG, and PHI with a total cost estimate between \$263M and \$283M.<sup>4 5</sup>
- On October 25, 2012, Schedule 12 of the tariff and Schedule 6 of the OA were changed to address FERC Order No. 1000 reforms to the cost allocation requirements for local and regional transmission planning projects that were formerly defined in Order No. 890. The new approach was applied for the first time to the 2013 RTEP.

## Backbone Facilities

- PJM baseline transmission projects are implemented to resolve reliability criteria violations. PJM backbone transmission projects are a subset of significant baseline projects, which are intended to resolve multiple reliability criteria violations and congestion issues and which may have substantial impacts on energy and capacity markets. There is currently only one backbone project under development, Surry Skiffes Creek 500kV.

## Transmission Facility Outages

- PJM maintains a list of reportable transmission facilities. When the reportable transmission facilities need to be taken out of service, PJM transmission owners are required to report planned transmission facility outages as early as possible. PJM processes the transmission facility outage requests according to rules in PJM's Manual 3 to decide if the

outage is on time, late, or past its deadline and whether or not they will allow the outage.<sup>6</sup>

- There were 4,052 transmission outage requests submitted for the first three months of 2016. Of the requested outages, 85.6 percent were planned for five days or shorter and 1.6 percent were planned for longer than 30 days. Of the requested outages, 53.6 percent were late according to the rules in PJM's Manual 3.

## Recommendations

The MMU recommends improvements to the planning process.

- The MMU recommends that PJM continue to incorporate the principle that the goal of transmission planning should be the incorporation of transmission investment decisions into market driven processes as much as possible. (Priority: Low. First reported 2001. Status: Not adopted.)
- The MMU recommends the creation of a mechanism to permit a direct comparison, or competition, between transmission and generation alternatives, including which alternative is less costly and who bears the risks associated with each alternative. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that rules be implemented to permit competition to provide financing for transmission projects. This competition could reduce the cost of capital for transmission projects and significantly reduce total costs to customers. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that rules be implemented to require that project cost caps on new transmission projects be part of the evaluation of competing projects. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that barriers to entry be addressed in a timely manner in order to help ensure that the capacity market will result in the entry of new capacity to meet the needs of PJM market participants and reflect the uncertainty and resultant risks in the cost of new entry used to

<sup>4</sup> See "Artificial Island Recommendations," presented at the TEAC meeting on April 28, 2015 at <<http://www.pjm.com/~media/committees-groups/committees/teac/20150428-ai/20150428-artificial-island-recommendations.ashx>>.

<sup>5</sup> See letter from Terry Boston concerning the Artificial Island Project at <<http://www.pjm.com/~media/documents/reports/board-statement-on-artificial-island-project.ashx>>.

<sup>6</sup> PJM. "Manual 03: Transmission Operations," Revision 46 (December 1, 2014), Section 4.

establish the capacity market demand curve in RPM. (Priority: Low. First reported 2012. Status: Not adopted.)

- The MMU recommends that the question of whether Capacity Injection Rights (CIRs) should persist after the retirement of a unit be addressed. Even if the treatment of CIRs remains unchanged, the rules need to ensure that incumbents cannot exploit control of CIRs to block or postpone entry of competitors.<sup>7</sup> (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends outsourcing interconnection studies to an independent party to avoid potential conflicts of interest. Currently, these studies are performed by incumbent transmission owners under PJM's direction. This creates potential conflicts of interest, particularly when transmission owners are vertically integrated and the owner of transmission also owns generation. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends improvements in queue management including that PJM establish a review process to ensure that projects are removed from the queue if they are not viable, as well as a process to allow commercially viable projects to advance in the queue ahead of projects which have failed to make progress, subject to rules to prevent gaming. (Priority: Medium. First reported 2013. Status: Partially adopted.)
- The MMU recommends an analysis of the study phase of PJM's transmission planning to reduce the need for postponements of study results, to decrease study completion times, and to improve the likelihood that a project at a given phase in the study process will successfully go into service. (Priority: Medium. First reported 2014. Status: Partially adopted.)
- The MMU recommends that PJM establish fair terms of access to rights of way and property, such as at substations, in order to remove any barriers to entry and permit competition between incumbent transmission providers and merchant transmission providers in the RTEP. (Priority: Medium. First reported 2014. Status: Not adopted.)

- The MMU recommends that PJM enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. (Priority: Medium. First reported 2015. Status: Not adopted.)
- The MMU recommends consideration of changing the minimum distribution factor in the method of allocating costs for baseline projects from .01 to .00 and adding a threshold minimum usage impact on the line. (Priority: Medium. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM reevaluate all transmission outage tickets as on time or late as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages. (Priority: Low. First reported 2014. Status: Not adopted.)
- The MMU recommends that PJM draft a clear definition of the congestion analysis required for transmission outage requests to include in Manual 3 after appropriate review. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM modify the rules to reduce or eliminate the approval of late outage requests submitted or rescheduled after the FTR auction bidding opening date. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM not permit transmission owners to divide long duration outages into smaller segments to avoid complying with the requirements for long duration outages. (Priority: Low. First reported 2015. Status: Not adopted.)

## Conclusion

The goal of PJM market design should be to enhance competition and to ensure that competition is the driver for all the key elements of PJM markets. But transmission investments have not been fully incorporated into competitive markets. The construction of new transmission facilities has significant impacts on the energy and capacity markets. But when generating units retire

<sup>7</sup> See "Comments of the Independent Market Monitor for PJM," Docket No. ER12-1177-000, <[http://www.monitoringanalytics.com/reports/Reports/2012/IMM\\_Comments\\_ER12-1177-000\\_20120312.pdf](http://www.monitoringanalytics.com/reports/Reports/2012/IMM_Comments_ER12-1177-000_20120312.pdf)>.

or load increases, there is no market mechanism in place that would require direct competition between transmission and generation to meet loads in the affected area. In addition, despite FERC Order No. 1000, there is not yet a transparent, robust and clearly defined mechanism to permit competition to build transmission projects, to ensure that competitors provide a total project cost cap, or to obtain least cost financing through the capital markets.

The addition of a planned transmission project changes the parameters of the capacity auction for the area, changes the amount of capacity needed in the area, changes the capacity market supply and demand fundamentals in the area and may effectively forestall the ability of generation to compete. But there is no mechanism to permit a direct comparison, let alone competition, between transmission and generation alternatives. There is no mechanism to evaluate whether the generation or transmission alternative is less costly, whether there is more risk associated with the generation or transmission alternatives, or who bears the risks associated with each alternative. Creating such a mechanism should be an explicit goal of PJM market design.

The PJM queue evaluation process should be improved to ensure that barriers to competition for new generation investments are not created. Issues that need to be addressed include the ownership rights to CIRs, whether transmission owners should perform interconnection studies, and improvements in queue management.

The PJM rules for competitive transmission development through the RTEP should build upon FERC Order No. 1000 to create real competition between incumbent transmission providers and merchant transmission providers. PJM should enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. Another element of opening competition would be to consider transmission owners' ownership of property and rights of way at or around transmission substations. In many cases, the land acquired included property intended to support future expansion of the grid. Incumbents have included the costs of the property

in their rate base. Because PJM now has the responsibility for planning the development of the grid under its RTEP process, property bought to facilitate future expansion should be a part of the RTEP process and be made available to all providers on equal terms.

There are currently no market incentives for transmission owners to submit and complete transmission outages in a timely and efficient manner. Requiring transmission owners to pay does not create an effective incentive when those payments are passed through to transmission customers. The process for the submission of planned transmission outages needs to be carefully reviewed and redesigned to limit the ability of transmission owners to submit transmission outages that are late for FTR Auction bid submission dates and are late for the Day-Ahead Energy Market. The submission of late transmission outages can inappropriately affect market outcomes when market participants do not have the ability to modify market bids and offers.

## Planned Generation and Retirements

### Planned Generation Additions

Expected net revenues provide incentives to build new generation to serve PJM markets. The amount of planned new generation in PJM reflects investors' perception of the incentives provided by the combination of revenues from the PJM energy, capacity and ancillary service markets. On March 31, 2016, 81,936.3 MW of capacity were in generation request queues for construction through 2024, compared to an average installed capacity of 187,281.3 MW as of March 31, 2016. Although it is clear that not all generation in the queues will be built, PJM has added capacity annually since 2000 (Table 12-1). In the first three months of 2016, 2,763.0 MW of nameplate capacity went into service in PJM.

**Table 12-1 Year-to-year capacity additions from PJM generation queue: Calendar years 2000 through March 31, 2016**

Year	MW
2000	505.0
2001	872.0
2002	3,841.0
2003	3,524.0
2004	1,935.0
2005	819.0
2006	471.0
2007	1,265.0
2008	2,776.7
2009	2,515.9
2010	2,097.4
2011	5,007.8
2012	2,669.4
2013	1,126.8
2014	2,659.0
2015	3,808.4
2016	2,763.0

## PJM Generation Queues

Generation request queues are groups of proposed projects, including new units, reratings of existing units, capacity resources and energy only resources. Each queue is open for a fixed amount of time. Studies commence on all projects in a given queue when that queue closes. The duration of the queue period has varied. Queues A and B were open for a year. Queues C-T were open for six months. Starting in February 2008, Queues U-Y1 were open for three months. Starting in May 2012, the duration of the queue period was reset to six months, starting with Queue Y2. Queue AB2 is currently open.

All projects that have been entered in a queue have a status assigned. Projects listed as active are undergoing one of the studies (feasibility, system impact, facility) required to proceed. Other status options are under construction, suspended, and in service. Withdrawn projects are removed from the queue and listed separately. A project cannot be suspended until it has reached the status of under construction. Any project that entered the queue before February 1, 2011, can be suspended for up to three years. Projects that entered

the queue after February 1, 2011, face an additional restriction in that the suspension period is reduced to one year if they affect any project later in the queue.<sup>8</sup> When a project is suspended, PJM extends the scheduled milestones by the duration of the suspension. If, at any time, a milestone is not met, PJM will initiate the termination of the Interconnection Service Agreement (ISA) and the corresponding cancellation costs must be paid by the customer.<sup>9</sup>

Table 12-2 shows MW in queues by expected completion date and MW changes in the queues between December 31, 2015 and March 31, 2016, for ongoing projects, i.e. projects with the status active, under construction or suspended.<sup>10</sup> Projects that are already in service are not included here. The total MW in queues decreased by 3,386.8 MW, or 4.0 percent, from 85,323.1 MW at the end of 2015. The change was the result of 3,575.8 MW in new projects entering the queue, 4,076.7 MW in projects withdrawing, and 2,775.9 MW going into service. The remaining difference is the result of projects adjusting their expected MW.

**Table 12-2 Queue comparison by expected completion year (MW): December 31, 2015 vs. March 31, 2016<sup>11</sup>**

Year	As of 12/31/2015	As of 3/31/2016	Quarterly Change	
			MW	Percent
2015	9,641.9	0.0	NA	NA
2016	15,085.7	21,064.0	5,978.3	28.4%
2017	12,442.3	12,957.0	514.7	4.0%
2018	13,403.6	14,859.6	1,456.0	9.8%
2019	21,461.3	18,416.5	(3,044.8)	(16.5%)
2020	11,444.3	10,869.3	(575.0)	(5.3%)
2021	0.0	1,925.9	1,925.9	NA
2022	250.0	250.0	0.0	0.0%
2024	1,594.0	1,594.0	0.0	0.0%
Total	85,323.1	81,936.3	(3,386.8)	(4.0%)

Table 12-3 shows the yearly project status changes in more detail and how scheduled queue capacity has changed between December 31, 2015, and March

<sup>8</sup> See PJM. Manual 14C. "Generation and Transmission Interconnection Process," Revision 8 (December 20, 2012), Section 3.7, <<http://www.pjm.com/~media/documents/manuals/m14c.ashx>>.

<sup>9</sup> PJM does not track the duration of suspensions or PJM termination of projects.

<sup>10</sup> Expected completion dates are entered when the project enters the queue. Actual completion dates are generally different than expected completion dates.

<sup>11</sup> Wind and solar capacity in Table 12-2 through Table 12-5 have not been adjusted to reflect derating.

31, 2016. For example, 3,575.8 MW entered the queue in the first three months of 2016, 3,546.1 MW of which are currently active and 26.7 MW of which were withdrawn before the quarter ended. Of the total 52,350.1 MW marked as active at the beginning of the quarter, 3,788.0 MW were withdrawn, 19.9 MW were suspended, 2,540.5 MW started construction, and 298.0 MW went into service by the end of the quarter. The Under Construction column shows that 17.0 MW came out of suspension and 2,540.5 MW began construction in the first three months of 2016, in addition to the 24,625.2 MW of capacity that maintained the status under construction from the previous quarter.

**Table 12–3 Change in project status (MW): December 31, 2015 vs. March 31, 2016**

Status at 12/31/2015	Status at 3/31/2016					
	Total at 12/31/2015	Active	Suspended	Under Construction	In Service	Withdrawn
(Entered in Q1 2016)		3,546.1	0.0	0.0	3.0	26.7
Active	52,350.1	45,593.7	19.9	2,540.5	298.0	3,788.0
Suspended	4,698.9	0.0	4,681.9	17.0	0.0	0.0
Under Construction	28,274.1	70.0	842.0	24,625.2	2,474.9	262.0
In Service	41,021.9	0.0	0.0	0.0	41,021.9	0.0
Withdrawn	286,258.0	0.0	0.0	0.0	0.0	286,473.0
Total at 3/31/2016		49,209.8	5,543.8	27,182.6	43,797.8	290,549.8

Table 12–4 shows the amount of capacity active, in service, under construction, suspended, or withdrawn for each queue since the beginning of the RTEP process and the total amount of capacity that had been included in each queue. All items in queues A–M are either in service or have been withdrawn. As of March 31, 2016, there are 81,936.3 MW of capacity in queues that are not yet in service, of which 6.8 percent are suspended, 33.2 percent are under construction and 60.1 percent have not begun construction.

**Table 12–4 Capacity in PJM queues (MW): At March 31, 2016<sup>12</sup>**

Queue	Active	In-Service	Under Construction	Suspended	Withdrawn	Total
A Expired 31-Jan-98	0.0	8,103.0	0.0	0.0	17,252.0	25,355.0
B Expired 31-Jan-99	0.0	4,645.5	0.0	0.0	14,620.7	19,266.2
C Expired 31-Jul-99	0.0	531.0	0.0	0.0	3,470.3	4,001.3
D Expired 31-Jan-00	0.0	850.6	0.0	0.0	7,182.0	8,032.6
E Expired 31-Jul-00	0.0	795.2	0.0	0.0	8,021.8	8,817.0
F Expired 31-Jan-01	0.0	52.0	0.0	0.0	3,092.5	3,144.5
G Expired 31-Jul-01	0.0	1,189.6	0.0	0.0	17,961.8	19,151.4
H Expired 31-Jan-02	0.0	702.5	0.0	0.0	8,421.9	9,124.4
I Expired 31-Jul-02	0.0	103.0	0.0	0.0	3,728.4	3,831.4
J Expired 31-Jan-03	0.0	40.0	0.0	0.0	846.0	886.0
K Expired 31-Jul-03	0.0	98.9	0.0	0.0	485.2	584.1
L Expired 31-Jan-04	0.0	256.5	0.0	0.0	4,528.7	4,785.2
M Expired 31-Jul-04	0.0	504.8	0.0	0.0	3,705.6	4,210.4
N Expired 31-Jan-05	0.0	2,398.8	38.0	0.0	8,090.3	10,527.0
O Expired 31-Jul-05	0.0	1,668.2	437.0	0.0	5,466.8	7,572.0
P Expired 31-Jan-06	0.0	3,064.7	253.0	210.0	5,170.5	8,698.2
Q Expired 31-Jul-06	0.0	3,147.9	1,594.0	0.0	9,881.7	14,623.6
R Expired 31-Jan-07	0.0	1,886.4	648.3	800.0	19,420.6	22,755.3
S Expired 31-Jul-07	0.0	3,512.7	432.9	190.0	12,396.5	16,532.0
T Expired 31-Jan-08	200.0	1,779.0	2,443.0	300.0	22,813.3	27,535.3
U Expired 31-Jan-09	400.0	837.3	949.9	320.0	30,829.6	33,336.8
V Expired 31-Jan-10	1,369.2	1,936.1	916.6	555.0	12,036.4	16,813.3
W Expired 31-Jan-11	1,295.0	1,949.5	1,106.8	1,628.0	18,101.0	24,080.3
X Expired 31-Jan-12	2,944.0	2,847.9	6,551.7	366.8	17,634.0	30,344.5
Y Expired 30-Apr-13	1,312.5	548.8	4,340.2	1,117.5	18,446.7	25,765.5
Z Expired 30-Apr-14	2,899.4	294.7	5,236.5	42.3	5,860.8	14,333.7
AA1 Expired 31-Oct-14	7,400.3	53.4	2,201.1	14.3	2,333.3	12,002.4
AA2 Expired 30-Apr-15	9,420.6	0.0	27.5	0.0	6,629.8	16,077.9
AB1 Expired 31-Oct-15	17,952.0	0.0	6.3	0.0	2,522.6	20,480.9
AB2 Through 31-Mar-16	4,016.8	0.0	0.0	0.0	29.0	4,045.8
Total	49,209.8	43,797.8	27,182.6	5,543.8	290,979.8	416,713.9

<sup>12</sup> Projects listed as partially in service are counted as in service for the purposes of this analysis.

## Distribution of Units in the Queues

Table 12-5 shows the projects under construction, suspended, or active, by unit type, and control zone.<sup>13</sup> As of March 31, 2016, 81,936.3 MW of capacity were in generation request queues for construction through 2024, compared to 85,323.1 MW at December 31, 2015.<sup>14</sup> Table 12-5 also shows the planned retirements for each zone.

**Table 12-5 Queue capacity by LDA, control zone and fuel (MW): At March 31, 2016<sup>15</sup>**

LDA	Zone	BioMass	CC	CT	Diesel	Fuel Cell	Hydro	Nuclear	Solar	Steam	Storage	Wind	Total Queue Capacity	Planned Retirements
EMAAC	AECO	0.0	1,706.0	239.5	0.0	1.5	0.0	0.0	70.2	0.0	21.0	373.0	2,411.2	8.0
	DPL	0.0	742.0	7.0	2.0	0.0	0.0	0.0	796.8	0.0	24.0	749.6	2,321.4	34.0
	JCPL	0.0	3,376.2	0.0	0.6	0.0	0.0	0.0	436.7	0.0	181.0	0.0	3,994.5	616.0
	PECO	0.0	1,221.0	0.0	8.6	0.0	0.0	50.0	0.0	0.0	40.8	0.0	1,320.4	50.8
	PSEG	0.0	2,658.4	229.0	10.6	0.0	0.0	0.0	82.7	24.0	2.0	0.0	3,006.7	611.0
	RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	EMAAC Total	0.0	9,703.6	475.5	21.8	1.5	0.0	50.0	1,386.4	24.0	268.8	1,122.6	13,054.2	1,319.8
SWMAAC	BGE	0.0	0.0	256.0	30.3	0.0	0.4	0.0	23.1	132.0	20.1	0.0	461.9	209.0
	Pepco	0.0	2,642.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,642.6	0.0
	SWMAAC Total	0.0	2,642.6	256.0	30.3	0.0	0.4	0.0	23.1	132.0	20.1	0.0	3,104.5	209.0
WMAAC	Met-Ed	0.0	2,311.5	34.1	0.0	0.0	0.0	0.0	3.0	0.0	0.0	0.0	2,348.6	0.0
	PENELEC	0.0	2,814.5	1,420.8	180.7	0.0	40.0	0.0	13.5	0.0	40.0	418.3	4,927.8	0.0
	PPL	16.0	6,620.0	19.9	24.9	0.0	0.0	0.0	16.0	0.0	30.0	466.5	7,193.3	0.0
	WMAAC Total	16.0	11,746.0	1,474.8	205.6	0.0	40.0	0.0	32.5	0.0	70.0	884.8	14,469.7	0.0
Non-MAAC	AEP	0.0	7,234.0	97.0	13.0	0.0	134.0	102.0	119.2	251.0	114.0	6,926.2	14,990.4	0.0
	AP	0.0	4,335.4	0.0	133.3	0.0	0.0	0.0	343.8	1,726.5	73.0	940.0	7,552.0	0.0
	ATSI	0.0	5,947.0	0.0	65.3	0.0	0.0	0.0	0.0	0.0	12.5	518.0	6,542.8	94.0
	ComEd	0.0	4,949.3	590.0	58.7	0.0	22.7	80.0	0.0	27.0	111.1	3,522.5	9,361.3	510.0
	DAY	1.9	0.0	0.0	0.0	0.0	0.0	0.0	25.9	12.0	20.0	300.0	359.8	0.0
	DEOK	0.0	513.0	0.0	6.4	0.0	0.0	0.0	125.0	0.0	10.0	0.0	654.4	0.0
	DLCO	0.0	205.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	20.0	0.0	225.0	0.0
	Dominion	62.5	4,776.9	60.0	12.0	0.0	0.0	1,594.0	2,460.8	0.0	34.0	1,472.1	10,472.3	323.0
	EKPC	0.0	1,150.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,150.0	149.0
	Non-MAAC Total	64.4	29,110.6	747.0	288.7	0.0	156.7	1,776.0	3,074.7	2,016.5	394.6	13,678.8	51,308.0	1,076.0
<b>Total</b>		<b>80.4</b>	<b>53,202.8</b>	<b>2,953.3</b>	<b>546.4</b>	<b>1.5</b>	<b>197.1</b>	<b>1,826.0</b>	<b>4,516.7</b>	<b>2,172.5</b>	<b>753.5</b>	<b>15,686.2</b>	<b>81,936.3</b>	<b>2,604.8</b>

A significant shift in the distribution of unit types within the PJM footprint continues to develop as natural gas fired units enter the queue and steam units retire. While 56,560.08 MW of gas fired capacity are in the queue, there are only 1,957.0 MW of coal fired steam capacity in the queue. The only new coal project currently in the queue is the new Hatfield unit, with 1,710 MW of capacity. This project, which entered the queue in October 2014 and is already under

<sup>13</sup> Unit types designated as reciprocating engines are classified as diesel.

<sup>14</sup> Since wind resources cannot be dispatched on demand, PJM rules previously required that the unforced capacity of wind resources be derated to 20 percent of nameplate capacity until actual generation data are available. Beginning with Queue U, PJM derates wind resources to 13 percent of nameplate capacity until there is operational data to support a different conclusion. PJM derates solar resources to 38 percent of nameplate capacity. Based on the derating of 15,686.2 MW of wind resources and 4,516.7 MW of solar resources, the 81,936.3 MW currently active in the queue would be reduced to 65,489.0 MW.

<sup>15</sup> This data includes only projects with a status of active, under-construction, or suspended.

construction, is intended to replace three coal units retired in October 2013 at the same location. With respect to retirements, 1,263.0 MW of coal fired steam capacity and 282.8 MW of natural gas capacity are slated for deactivation between now and 2020. The replacement of coal steam units by units burning natural gas could significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

## Planned Retirements

As shown in Table 12-6, 26,486.5 MW have been, or are planned to be, retired between 2011 and 2020.<sup>16</sup> Of that, 2,007.3 MW are planned to retire after 2016. In the first three months of 2016, 53 MW were retired. Of the 2,656.8 MW pending retirement, 1,263 MW are coal units. The coal unit retirements were a result of low gas prices and the EPA's Mercury and Air Toxics Standards (MATS) for some units.

**Table 12-6 Summary of PJM unit retirements by fuel (MW): 2011 through 2020**


	Coal	Diesel	Heavy Oil	Kerosene	Landfill Gas	Light Oil	Natural Gas	Nuclear	Wind	Wood Waste	Total
Retirements 2011	543.0	0.0	0.0	0.0	0.0	63.7	522.5	0.0	0.0	0.0	1,129.2
Retirements 2012	5,907.9	0.0	0.0	0.0	0.0	788.0	250.0	0.0	0.0	16.0	6,961.9
Retirements 2013	2,589.9	2.9	166.0	0.0	3.8	85.0	0.0	0.0	0.0	8.0	2,855.6
Retirements 2014	2,427.0	50.0	0.0	184.0	15.3	0.0	294.0	0.0	0.0	0.0	2,970.3
Retirements 2015	7,661.8	10.3	0.0	644.2	2.0	212.0	1,319.0	0.0	10.4	0.0	9,859.7
Retirements 2016	0.0	51.0	0.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0	53.0
Planned Retirements 2016	566.0	8.0	74.0	0.0	1.5	0.0	0.0	0.0	0.0	0.0	649.5
Planned Retirements Post-2016	697.0	0.0	34.0	0.0	0.0	0.0	661.8	614.5	0.0	0.0	2,007.3
<b>Total</b>	<b>20,392.6</b>	<b>122.2</b>	<b>274.0</b>	<b>828.2</b>	<b>24.6</b>	<b>1,148.7</b>	<b>3,047.3</b>	<b>614.5</b>	<b>10.4</b>	<b>24.0</b>	<b>26,486.5</b>

<sup>16</sup> See PJM "Generator Deactivation Summary Sheets," at <<http://www.pjm.com/planning/generation-deactivation/gd-summaries.aspx>> (April 4, 2016).



A map of the retirements between 2011 and 2020 is shown in Figure 12-1.

Figure 12-1 Map of PJM unit retirements: 2011 through 2020



The list of pending retirements is shown in Table 12-7.

**Table 12-7 Planned retirement of PJM units: as of March 31, 2016**

Unit	Zone	ICAP (MW)	Fuel	Unit Type	Projected Deactivation Date
Yorktown 1-2	Dominion	323.0	Coal	Steam	31-Mar-16
Dale 3-4	EKPC	149.0	Coal	Steam	16-Apr-16
Avon Lake 7	ATSI	94.0	Coal	Steam	16-Apr-16
BL England Diesels	AECO	8.0	Diesel	Diesel	31-May-16
Riverside 4	BGE	74.0	Natural gas	Steam	01-Jun-16
Warren County Landfill	JCPL	1.5	Landfill Gas	Diesel	01-Jun-16
McKee 1-2	DPL	34.0	Heavy Oil	Combustion Turbine	31-May-17
Will County 4	ComEd	510.0	Coal	Steam	31-May-18
Sewaren 1-4	PSEG	453.0	Kerosene	Combustion Turbine	01-Jun-18
Bayonne Cogen Plant (CC)	PSEG	158.0	Natural gas	Steam	01-Nov-18
MH50 Marcus Hook Co-gen	PECO	50.8	Natural gas	Steam	13-May-19
Elmer Smith U1	External	52.0	Coal	Steam	01-Jun-19
Oyster Creek	JCPL	614.5	Nuclear	Nuclear	31-Dec-19
Wagner 2	BGE	135.0	Coal	Steam	01-Jun-20
<b>Total</b>		<b>2,656.8</b>			

Table 12-8 shows the capacity, average size, and average age of units retiring in PJM, from 2011 through 2020, while Table 12-9 shows these retirements by state. The majority, 77.0 percent, of all MW retiring during this period are coal steam units. These units have an average age of 56.0 years and an average size of 163.1 MW. Over half of them, 53.4 percent, are located in either Ohio or Pennsylvania. Retirements have generally consisted of smaller subcritical coal steam units and those without adequate environmental controls to remain viable beyond 2016.

**Table 12-8 Retirements by fuel type: 2011 through 2020**

	Number of Units	Avg. Size (MW)	Avg. Age at Retirement (Years)	Total MW	Percent
Coal	125	163.1	56.0	20,392.6	77.0%
Diesel	7	17.5	42.7	122.2	0.5%
Heavy Oil	4	68.5	57.5	274.0	1.0%
Kerosene	20	41.4	45.5	828.2	3.1%
Landfill Gas	7	3.5	15.0	24.6	0.1%
Light Oil	15	76.6	43.8	1,148.7	4.3%
Natural Gas	51	59.8	46.4	3,047.3	11.5%
Nuclear	1	614.5	50.0	614.5	2.3%
Wind	1	10.4	15.0	10.4	0.0%
Wood Waste	2	12.0	23.5	24.0	0.1%
<b>Total</b>	<b>233</b>	<b>113.7</b>	<b>50.1</b>	<b>26,486.5</b>	<b>100.0%</b>

**Table 12-9 Retirements (MW) by fuel type and state: 2011 through 2020**

State	Heavy		Landfill Gas	Light Oil	Natural Gas	Nuclear	Wind	Wood Waste	Total	
	Coal	Diesel								
DC	0.0	0.0	0.0	0.0	0.0	788.0	0.0	0.0	0.0	788.0
DE	254.0	0.0	34.0	0.0	0.0	0.0	0.0	0.0	0.0	288.0
IL	2,134.0	0.0	0.0	0.0	6.4	0.0	0.0	0.0	0.0	2,140.4
IN	982.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	982.0
KY	1,047.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,047.0
MD	250.0	51.0	74.0	0.0	0.0	0.0	115.0	0.0	0.0	490.0
NC	0.0	0.0	0.0	0.0	0.0	31.0	0.0	0.0	0.0	31.0
NJ	136.0	8.0	0.0	828.2	6.2	212.0	2,680.5	614.5	0.0	4,485.4
OH	5,752.6	60.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5,812.9
PA	5,145.0	0.0	166.0	0.0	10.0	117.7	251.8	0.0	10.4	5,724.9
VA	2,051.0	2.9	0.0	0.0	2.0	0.0	0.0	0.0	0.0	2,055.9
WV	2,641.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,641.0
<b>Total</b>	<b>20,392.6</b>	<b>122.2</b>	<b>274.0</b>	<b>828.2</b>	<b>24.6</b>	<b>1,148.7</b>	<b>3,047.3</b>	<b>614.5</b>	<b>10.4</b>	<b>26,486.5</b>

## Actual Generation Deactivations in 2016

Table 12-10 shows the units that were deactivated in 2016.

**Table 12-10 Unit deactivations in 2016**

Company	Unit Name	ICAP (MW)	Primary Fuel	Zone Name	Average Age (Years)	Retirement Date
Exelon Corporation	Fauquier County Landfill	2.0	Diesel	Dominion	12	31-Jan-16
Exelon Corporation	Perryman 2	51.0	Diesel	BGE	44	01-Feb-16
Total		53.0				

## Generation Mix

As of March 31, 2016, PJM had an installed capacity of 187,281.3 MW (Table 12-11). This measure differs from capacity market installed capacity because it includes energy-only units, excludes all external units, and uses nameplate values for solar and wind resources.

**Table 12-11 Existing PJM capacity: At March 31, 2016 (By zone and unit type (MW))<sup>17</sup>**

Zone	CC	CT	Diesel	Fuel Cell	Hydroelectric	Nuclear	Solar	Steam	Storage	Wind	Total
AECO	901.9	507.7	22.6	0.0	0.0	0.0	41.7	815.9	0.0	7.5	2,297.3
AEP	4,900.0	3,682.2	77.1	0.0	1,071.9	2,071.0	0.0	18,897.8	4.0	2,103.2	32,807.2
APS	1,129.0	1,214.9	47.9	0.0	129.2	0.0	36.1	5,409.0	27.4	1,088.5	9,082.0
ATSI	685.0	1,617.4	67.7	0.0	0.0	2,134.0	0.0	5,813.0	0.0	0.0	10,317.1
BGE	0.0	789.0	18.4	0.0	0.0	1,716.0	0.0	2,995.5	0.0	0.0	5,518.9
ComEd	3,146.1	7,244.0	93.8	0.0	0.0	10,473.5	9.0	5,166.1	76.0	2,431.9	28,640.4
DAY	0.0	1,368.5	47.5	0.0	0.0	0.0	1.1	2,908.0	40.0	0.0	4,365.1
DEOK	47.2	654.0	0.0	0.0	0.0	0.0	0.0	3,567.0	10.0	0.0	4,278.2
DLCO	244.0	15.0	0.0	0.0	6.3	1,777.0	0.0	660.0	0.0	0.0	2,702.3
Dominion	5,493.6	3,874.8	151.8	0.0	3,589.3	3,581.3	157.8	7,775.0	0.0	0.0	24,623.6
DPL	1,498.5	1,820.4	96.1	30.0	0.0	0.0	4.0	1,620.0	0.0	0.0	5,069.0
EKPC	0.0	774.0	0.0	0.0	70.0	0.0	0.0	1,836.0	0.0	0.0	2,680.0
JCPL	2,682.5	763.1	19.9	0.0	400.0	614.5	117.2	10.0	0.0	0.0	4,607.2
Met-Ed	2,111.0	406.5	41.4	0.0	19.0	805.0	0.0	200.0	0.0	0.0	3,582.9
PECO	3,209.0	834.0	2.9	0.0	1,642.0	4,546.8	3.0	979.1	1.0	0.0	11,217.8
PENELEC	0.0	407.5	52.2	0.0	512.8	0.0	0.0	6,793.5	10.4	930.9	8,707.3
Pepco	230.0	1,091.7	9.9	0.0	0.0	0.0	0.0	3,649.1	0.0	0.0	4,980.7
PPL	1,807.9	616.2	55.5	0.0	706.6	2,520.0	15.0	5,169.9	20.0	219.7	11,130.8
PSEG	3,846.3	1,132.0	11.1	0.0	5.0	3,493.0	134.0	2,050.1	2.0	0.0	10,673.5
RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total	31,932.0	28,812.9	815.8	30.0	8,152.1	33,732.1	518.9	76,315.0	190.8	6,781.7	187,281.3

<sup>17</sup> The capacity described in this section refers to all capacity in PJM at nameplate ratings, regardless of whether the capacity entered the RPM auction. This table previously included external units.

Figure 12-2 and Table 12-12 show the age of PJM generators by unit type. Units older than 40 years comprise 71,429.4 MW, or 38.1 percent, of the total capacity of 187,281.3 MW.

**Table 12-12 PJM capacity (MW) by age (years): At March 31, 2016**

Age (years)	CC	CT	Diesel	Fuel Cell	Hydroelectric	Nuclear	Solar	Steam	Storage	Wind	Total
Less than 20	26,635.5	21,053.4	551.4	30.0	232.8	0.0	518.9	3,905.5	190.8	6,781.7	59,900.0
20 to 40	4,854.5	3,315.5	98.8	0.0	3,557.2	22,893.9	0.0	21,232.0	0.0	0.0	55,951.9
40 to 60	442.0	4,444.0	163.6	0.0	2,915.0	10,838.2	0.0	49,337.5	0.0	0.0	68,140.3
More than 60	0.0	0.0	2.0	0.0	1,447.1	0.0	0.0	1,840.0	0.0	0.0	3,289.1
<b>Total</b>	<b>31,932.0</b>	<b>28,812.9</b>	<b>815.8</b>	<b>30.0</b>	<b>8,152.1</b>	<b>33,732.1</b>	<b>518.9</b>	<b>76,315.0</b>	<b>190.8</b>	<b>6,781.7</b>	<b>187,281.3</b>

**Figure 12-2 PJM capacity (MW) by age (years): At March 31, 2016**




Table 12-13 shows the effect that expected retirements and new generation in the queues would have on the existing generation mix five years from now. The planned additions reflect the historical rates of completion, as shown in Table 12-16. While there are currently 81,936.3 MW in the queue, historical patterns indicate that we can expect 33,512.9 MW to go into service, based on current status in the queue process. Even though 71,429.4 MW of the total capacity are more than 40 years old, only 2,656.8 MW of these are planned to retire within the next five years. The expected role of gas-fired generation depends on projects in the queues and retirement of coal-fired generation. Existing capacity in SWMAAC is currently 63.3 percent steam, which will be reduced to 52.4 percent by 2020 as a result of the addition of an expected 2,046.3 MW of planned CC capacity. CC capacity would increase from 2.2 percent to 18.2 percent of capacity in SWMAAC in 2020. CC and CT generators would comprise 33.3 percent of SWMAAC capacity in 2020. In PJM, as a whole, the share of capacity from renewables increases from 8.4 percent to 11.5 percent by 2020.

Table 12-13 Expected capacity (MW) in five years: as of March 31, 2016<sup>18</sup>

LDA	Unit Type	Current Generator Capacity	Percent of Area Total	Planned Additions	Planned Retirements	Estimated Capacity in 5 Years	Percent of Area Total	
EMAAC	Combined Cycle	12,138.2	35.8%	3,537.9	0.0	15,676.1	41.8%	
	Combustion Turbine	5,057.2	14.9%	105.6	0.0	5,162.8	13.8%	
	Diesel	152.6	0.5%	12.0	9.5	155.1	0.4%	
	Fuel Cell	30.0	0.1%	0.2	0.0	30.2	0.1%	
	Hydroelectric	2,047.0	6.0%	0.0	0.0	2,047.0	5.5%	
	Nuclear	8,654.3	25.6%	31.0	614.5	8,070.8	21.5%	
	Solar	299.9	0.9%	642.6	0.0	942.5	2.5%	
	Steam	5,475.1	16.2%	0.0	695.8	4,779.3	12.7%	
	Storage	3.0	0.0%	71.0	0.0	74.0	0.2%	
	Wind	7.5	0.0%	565.9	0.0	573.4	1.5%	
	Total	33,864.8	100.0%	4,966.2	1,319.8	37,511.2	100.0%	
	SWMAAC	Combined Cycle	230.0	2.2%	2,046.3	0.0	2,276.3	18.2%
		Combustion Turbine	1,880.7	17.9%	0.0	0.0	1,880.7	15.1%
Diesel		28.3	0.3%	24.3	0.0	52.7	0.4%	
Hydroelectric		0.0	0.0%	0.3	0.0	0.3	0.0%	
Nuclear		1,716.0	16.3%	0.0	0.0	1,716.0	13.7%	
Solar		0.0	0.0%	18.5	0.0	18.5	0.1%	
Steam		6,644.6	63.3%	106.1	209.0	6,541.7	52.4%	
Storage		0.0	0.0%	2.7	0.0	2.7	0.0%	
Total		10,499.6	100.0%	2,198.1	209.0	12,488.7	100.0%	
WMAAC	Biomass	0.0	0.0%	12.9	0.0	12.9	0.0%	
	Combined Cycle	3,918.9	16.7%	4,794.2	0.0	8,713.1	30.0%	
	Combustion Turbine	1,430.2	6.1%	272.9	0.0	1,703.1	5.9%	
	Diesel	149.1	0.6%	46.5	0.0	195.5	0.7%	
	Hydroelectric	1,238.4	5.3%	28.2	0.0	1,266.6	4.4%	
	Nuclear	3,325.0	14.2%	0.0	0.0	3,325.0	11.4%	
	Solar	15.0	0.1%	26.1	0.0	41.1	0.1%	
	Steam	12,163.4	51.9%	0.0	0.0	12,163.4	41.9%	
	Storage	30.4	0.1%	18.0	0.0	48.4	0.2%	
	Wind	1,150.6	4.9%	442.4	0.0	1,593.0	5.5%	
	Total	23,421.0	100.0%	5,641.1	0.0	29,062.0	100.0%	
RTO	Biomass	0.0	0.0%	51.7	0.0	51.7	0.0%	
	Combined Cycle	15,644.9	13.1%	11,144.2	0.0	26,789.1	19.3%	
	Combustion Turbine	20,444.8	17.1%	251.2	0.0	20,696.0	14.9%	
	Diesel	485.8	0.4%	111.5	0.0	597.3	0.4%	
	Hydroelectric	4,866.7	4.1%	23.1	0.0	4,889.9	3.5%	
	Nuclear	20,036.8	16.8%	138.4	0.0	20,175.2	14.5%	
	Solar	204.1	0.0	852.2	0.0	1,056.3	0.8%	
	Steam	52,031.9	43.5%	1,540.7	1,128.0	52,444.6	37.7%	
	Storage	157.4	0.1%	132.6	0.0	290.0	0.2%	
	Wind	5,623.6	4.7%	6,462.0	0.0	12,085.6	8.7%	
	Total	119,496.0	100.0%	20,707.5	1,128.0	139,075.5	100.0%	
	<b>Total</b>		<b>187,281.3</b>		<b>33,512.9</b>	<b>2,656.8</b>	<b>218,137.4</b>	

<sup>18</sup> Percent results shown in Table 12-13 are based on unrounded, underlying data and may differ from calculations based on the rounded values in the tables.

## Generation and Transmission Interconnection Planning Process

PJM made changes to the queue process in May 2012.<sup>19</sup> These changes included reducing the length of the queues, creating an alternate queue for some small projects, and adjustments to the rules regarding suspension rights and Capacity Interconnection Rights (CIR). PJM staff reported on June 11, 2015, that due to these and other process improvements, the study backlog has been significantly reduced.<sup>20</sup> The Earlier Queue Submittal Task Force (EQSTF) was established in August 2015, to further address the issue.<sup>21</sup>

### Interconnection Study Phase

In the study phase of the interconnection planning process, a series of studies are performed to determine the feasibility, impact, and cost of projects in the queue. Table 12-14 is an overview of PJM's study process. System impact and facilities studies are often redone when a project is withdrawn in order to determine the impact on the projects remaining in the queue.

**Table 12-14 PJM generation planning process**

Process Step	Start on	Financial Obligation	Days for PJM to Complete	Days for Applicant to Decide Whether to Continue
Feasibility Study	Close of current queue	Cost of study (partially refundable deposit)	90	30
System Impact Study	Upon acceptance of the System Impact Study Agreement	Cost of study (partially refundable deposit)	120	30
Facilities Study	Upon acceptance of the Facilities Study Agreement	Cost of study (refundable deposit)	Varies	60
Schedule of Work	Upon acceptance of Interconnection Service Agreement (ISA)	Letter of credit for upgrade costs	Varies	37
Construction (only for new generation)	Upon acceptance of Interconnection Construction Service Agreement (ICSA)	None	Varies	NA

Manual 14B requires PJM to apply a commercial probability factor at the feasibility study stage to improve the accuracy of capacity and cost estimates. The commercial probability factor is based on the historical incidence of projects dropping out of the queue at the impact study stage.<sup>22</sup> The impact and facilities studies are performed using the full amount of planned generation in

the queues. The actual withdrawal rates are shown in Table 12-15 and Table 12-16.

Table 12-15 shows the milestone status when projects were withdrawn, for all withdrawn projects. Of the projects withdrawn, 47.6 percent were withdrawn before the system impact study was completed. Once an Interconnection Service Agreement (ISA) or a Wholesale Market Participation Agreement (WMPA) is executed, the financial obligation for any necessary transmission upgrades cannot be retracted.<sup>23</sup> <sup>24</sup> Withdrawing at or beyond this point is uncommon; only 235 projects, or 13.8 percent, of all projects withdrawn were withdrawn after reaching this milestone.

<sup>19</sup> See letter from PJM to Secretary Kimberly Bose, Docket No. ER12-1177-000, <<http://www.pjm.com/~media/documents/ferc/2012-filings/20120229-er12-1177-000.ashx>>.

<sup>20</sup> See presentation by Dave Egan to the PJM Planning Committee, at <<http://www.pjm.com/~media/committees-groups/committees/pc/20150611/20150611-item-09-queue-status-update.ashx>>

<sup>21</sup> See Earlier Queue Submittal Task Force at <<http://www.pjm.com/committees-and-groups/task-forces/eqstf.aspx>>.

<sup>22</sup> See PJM Manual 14B. "PJM Region Transmission Planning Process," Revision 30 (February 26, 2015), p.70.

<sup>23</sup> "Generators planning to connect to the local distribution systems at locations that are not under FERC jurisdiction and wish to participate in PJM's market need to execute a PJM Wholesale Market Participation Agreement (WMPA)..." instead of an ISA. See PJM Manual 14C. "Generation and Transmission Interconnection Facility Construction," Revision 08 (December 20, 2012), p.8.

<sup>24</sup> See PJM. "Manual 14C: Generation and Transmission Interconnection Facility Construction," Revision 08 (December 20, 2012), p.22.

**Table 12-15 Last milestone completed at time of withdrawal: January 1, 1997 through March 31, 2016**

Milestone Completed	Projects Withdrawn	Percent
Never Started	188	11.0%
Feasibility Study	625	36.6%
System Impact Study	551	32.3%
Facilities Study	109	6.4%
Interconnection Service Agreement (ISA)	40	2.3%
Wholesale Market Participation Agreement (WMPA)	133	7.8%
Construction Service Agreement (CSA) or beyond	62	3.6%
Total	1,708	100.0%

Table 12-16 shows, by MW, the rate at which projects drop out of the queue as they move through the process, as well as the rate at which projects eventually go into service. Out of 334,777.6 nameplate MW that entered the queue, 43,797.8, 13.1 percent, went into service, while the remaining 290,979.8 MW withdrew at some point. Of the withdrawals, 39.3 percent happened after the feasibility study was completed.

**Table 12-16 Completed (withdrawn or in service) queue MW: January 1, 1997 through March 31, 2016**

Milestone Completed	MW in Queue	Percent of Total in Queue	MW Withdrawn	Percent of Total Withdrawn	Percent that Go In Service
Enter Queue	334,777.6	100.0%	28,939.2	9.9%	13.1%
Feasibility Study	305,838.4	91.4%	147,733.4	50.8%	14.3%
System Impact Study	158,105.0	47.2%	95,043.6	32.7%	27.7%
Facilities Study	63,061.5	18.8%	954.1	0.3%	69.5%
ISA/WMPA	62,107.4	18.6%	7,593.1	2.6%	70.5%
Construction	54,514.2	16.3%	10,716.4	3.7%	80.3%
In-Service	43,797.8	13.1%	0.0	0.0%	100.0%

Table 12-17 and Table 12-18 show the time spent at various stages in the queue process and the completion time for the studies performed. For completed projects, there is an average time of 945 days, or 2.6 years, between entering a queue and going into service. Nuclear and wind projects tend to take longer to go into service averaging 1,468 and 1,459 days. The average time to go into service for all other fuel types is 713 days. For withdrawn projects, there is an average time of 676 days between entering a queue and withdrawing.

**Table 12-17 Average project queue times (days): At March 31, 2016**

Status	Average (Days)	Standard Deviation	Minimum	Maximum
Active	933	646	34	3,745
In-Service	945	691	1	4,024
Suspended	2,200	881	634	4,260
Under Construction	1,703	998	205	6,380
Withdrawn	676	688	5	4,249

Table 12-18 presents information on the time in the stages of the queue for those projects not yet in service. Of the 651 projects in the queue as of March 31, 2016, 90 had a completed feasibility study and 223 were under construction.

**Table 12-18 PJM generation planning summary: At March 31, 2016**

Milestone Completed	Number of Projects	Percent of Total Projects	Average Days	Maximum Days
Not Started	157	24.1%	727	1,902
Feasibility Study	90	13.8%	756	2,555
Impact Study	81	12.4%	1,339	3,745
Facilities Study	8	1.2%	1,871	2,655
Interconnection Service Agreement (ISA)	19	2.9%	1,393	2,551
Wholesale Market Participation Agreement (WMPA)	2	0.3%	562	704
Construction Service Agreement (CSA)	1	0.2%	815	815
Under Construction	233	35.8%	1,703	6,380
Suspended	60	9.2%	2,200	4,260
Total	651	100.0%		

The time it takes to complete a study depends on the backlog and the number of projects in the queue, but not on the size of the project. Table 12-19 shows the number of projects that entered the queue by year. The last two full years show an increase in queue entries, primarily by renewable projects (solar, hydro, storage, biomass, wind). Of the 496 projects entered in 2014 and 2015, 314, 63.3 percent, were renewable.

Table 12-19 Number of projects entered in the queue as of March 31, 2016

Year Entered	Fuel Group			Grand Total
	Nuclear	Renewable	Traditional	
1997	2	1	10	13
1998	0	0	18	18
1999	1	5	83	89
2000	2	3	75	80
2001	4	6	81	91
2002	3	14	32	49
2003	1	36	18	55
2004	4	17	32	53
2005	3	79	53	135
2006	9	79	72	160
2007	9	68	142	219
2008	3	114	99	216
2009	10	113	50	173
2010	5	381	55	441
2011	6	265	78	349
2012	2	73	80	155
2013	1	78	73	152
2014	0	122	68	190
2015	0	192	114	306
2016	0	32	4	36
Total	65	1,678	1,237	2,980

Even though renewable projects comprise the majority of projects entered in the queue, as well as what is currently active in the queue, renewable projects only account for 25.9 percent of the nameplate MW currently active in the queue (Table 12-20).

Table 12-20 Queue details by fuel group: At March 31, 2016

Fuel Group	Number of Projects	Percent of Projects	MW	Percent MW
Nuclear	10	1.5%	1,826.0	2.2%
Renewable	410	63.0%	21,233.8	25.9%
Traditional	231	35.5%	58,876.5	71.9%
Total	651	100.0%	81,936.3	100.0%

Table 12-21 shows the current status of all generation queue projects by fuel type and project classification from January 1, 1997, through March 31, 2016. For example, 128 upgrades at natural gas fired facilities completed the queue process and are in service.

Since 1997, there have been a total of 2,969 projects in PJM generation queues. A total of 2,419 projects have been classified as new generation and 550 projects have been classified as upgrades. Wind, solar and natural gas projects have accounted for 2,256 projects, or 76.0 percent, of all 2,969 generation queue projects.



Table 12-21 Status of all generation queue projects: January 1, 1997 through March 31, 2016

Project Status	Project Classification	Number of Projects												TOTAL
		Natural	Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	
In Service	New Generation	82	59	9	76	1	9	4	7	13	3	69	6	338
	Upgrade	128	14	45	5	37	16	14	4	3	4	10	2	282
Under Construction	New Generation	34	25	2	74	1	4	0	2	28	1	7	0	178
	Upgrade	28	0	4	12	1	0	0	2	3	0	4	1	55
Suspended	New Generation	13	18	0	24	0	0	0	0	0	0	2	0	57
	Upgrade	1	2	0	0	0	0	0	0	0	0	0	0	3
Withdrawn	New Generation	372	348	53	571	8	40	9	35	40	9	69	12	1566
	Upgrade	62	13	12	7	9	2	13	1	3	2	7	1	132
Active	New Generation	74	44	0	113	0	0	0	0	41	0	8	0	280
	Upgrade	47	6	3	4	8	2	0	0	6	0	1	1	78
Total Projects	New Generation	575	494	64	858	10	53	13	44	122	13	155	18	2419
	Upgrade	266	35	64	28	55	20	27	7	15	6	22	5	550

Table 12-22 shows the MW in Table 12-21 by share by classification as new generation or upgrade. Within a fuel type the shares of upgrades add to 100 percent and the shares of new generation add to 100 percent. For example, 80.0 percent of all hydro projects classified as upgrades are currently in service in PJM, 10.0 percent of hydro upgrades were withdrawn and 10.0 percent are active. From January 1, 1997, through March 31, 2016, solar projects have had the lowest project completion rates across all technology types in either project classification. Landfill gas projects have had the highest project completion rates.

Table 12-22 Status of all generation queue projects as percent of total projects by classification: January 1, 1997 through March 31, 2016

Project Status	Project Classification	Percent of Total Project MW by Classification											
		Natural	Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG
In Service	New Generation	14.3%	11.9%	14.1%	8.9%	10.0%	17.0%	30.8%	15.9%	10.7%	23.1%	44.5%	33.3%
	Upgrade	48.1%	40.0%	70.3%	17.9%	67.3%	80.0%	51.9%	57.1%	20.0%	66.7%	45.5%	40.0%
Under Construction	New Generation	5.9%	5.1%	3.1%	8.6%	10.0%	7.5%	0.0%	4.5%	23.0%	7.7%	4.5%	0.0%
	Upgrade	10.5%	0.0%	6.3%	42.9%	1.8%	0.0%	0.0%	28.6%	20.0%	0.0%	18.2%	20.0%
Suspended	New Generation	2.3%	3.6%	0.0%	2.8%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	1.3%	0.0%
	Upgrade	0.4%	5.7%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Withdrawn	New Generation	64.7%	70.4%	82.8%	66.6%	80.0%	75.5%	69.2%	79.5%	32.8%	69.2%	44.5%	66.7%
	Upgrade	23.3%	37.1%	18.8%	25.0%	16.4%	10.0%	48.1%	14.3%	20.0%	33.3%	31.8%	20.0%
Active	New Generation	12.9%	8.9%	0.0%	13.2%	0.0%	0.0%	0.0%	0.0%	33.6%	0.0%	5.2%	0.0%
	Upgrade	17.7%	17.1%	4.7%	14.3%	14.5%	10.0%	0.0%	0.0%	40.0%	0.0%	4.5%	20.0%

Table 12-23 shows the nameplate capacity of projects in the PJM generation queue by technology type and project classification. For example, the 348 new generation wind projects that have been withdrawn from the queue as of March 31, 2016, listed in Table 12-21, include 54,435.5 MW of capacity. The 372 natural gas projects that have been withdrawn in the same time period include 174,261.4 MW of nameplate generating capacity.

**Table 12-23 Status of all generation capacity (MW) in the PJM generation queue: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Project MW												TOTAL
		Natural Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	Diesel	
In Service	New Generation	20,448.9	6,881.3	1,378.0	571.6	9.0	465.6	607.0	253.8	139.0	50.0	366.6	69.5	31,240.2
	Upgrade	5,966.9	33.7	755.5	8.9	3,730.8	605.6	125.8	28.8	36.4	547.5	37.5	25.3	11,902.6
Under Construction	New Generation	16,891.1	4,075.7	1,790.0	884.3	1,594.0	123.1	0.0	17.9	65.7	132.0	41.5	0.0	25,615.2
	Upgrade	1,205.1	0.0	84.0	5.0	102.0	0.0	0.0	62.5	72.0	0.0	11.8	25.0	1,567.2
Suspended	New Generation	1,988.3	3,231.6	0.0	242.5	0.0	0.0	0.0	0.0	0.0	0.0	4.9	0.0	5,467.2
	Upgrade	1.6	75.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	76.6
Withdrawn	New Generation	174,261.4	54,435.4	31,721.6	7,303.2	6,567.0	1,988.0	1,721.0	1,242.7	488.6	711.8	396.8	63.9	280,901.5
	Upgrade	7,786.9	289.0	815.0	47.8	916.0	56.0	589.0	12.1	32.0	24.0	39.4	4.0	10,611.2
Active	New Generation	32,998.5	8,109.7	0.0	3,191.0	0.0	0.0	0.0	0.0	505.8	0.0	49.1	0.0	44,854.1
	Upgrade	3,560.5	194.2	83.0	193.9	130.0	74.0	0.0	0.0	110.0	0.0	4.0	6.1	4,355.7
Total Projects	New Generation	246,588.2	76,733.8	34,889.6	12,192.5	8,170.0	2,576.7	2,328.0	1,514.4	1,199.1	893.8	858.8	133.4	388,078.3
	Upgrade	18,521.0	591.9	1,737.5	255.6	4,878.8	735.6	714.8	103.4	250.4	571.5	92.7	60.4	28,513.5

Table 12-24 shows the MW in Table 12-23 by share by classification as new generation or upgrade. Within a fuel type the shares of upgrades add to 100 percent and the shares of new generation add to 100 percent. For example, 43.5 percent of all coal projects classified as upgrades are currently in service in PJM, 4.8 percent are under construction, 46.9 percent were withdrawn and 4.8 percent are active.

**Table 12-24 Status of all generation queue projects as percent of total MW in project classification: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Percent of Total Project MW by Classification											
		Natural Gas	Wind	Coal	Solar	Nuclear	Hydro	Oil	Biomass	Storage	Other	LFG	Diesel
In Service	New Generation	8.3%	9.0%	3.9%	4.7%	0.1%	18.1%	26.1%	16.8%	11.6%	5.6%	42.7%	52.1%
	Upgrade	32.2%	5.7%	43.5%	3.5%	76.5%	82.3%	17.6%	27.9%	14.5%	95.8%	40.5%	41.9%
Under Construction	New Generation	6.8%	5.3%	5.1%	7.3%	19.5%	4.8%	0.0%	1.2%	5.5%	14.8%	4.8%	0.0%
	Upgrade	6.5%	0.0%	4.8%	2.0%	2.1%	0.0%	0.0%	60.4%	28.8%	0.0%	12.7%	41.4%
Suspended	New Generation	0.8%	4.2%	0.0%	2.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.6%	0.0%
	Upgrade	0.0%	12.7%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
Withdrawn	New Generation	70.7%	70.9%	90.9%	59.9%	80.4%	77.2%	73.9%	82.1%	40.7%	79.6%	46.2%	47.9%
	Upgrade	42.0%	48.8%	46.9%	18.7%	18.8%	7.6%	82.4%	11.7%	12.8%	4.2%	42.5%	6.6%
Active	New Generation	13.4%	10.6%	0.0%	26.2%	0.0%	0.0%	0.0%	0.0%	42.2%	0.0%	5.7%	0.0%
	Upgrade	19.2%	32.8%	4.8%	75.9%	2.7%	10.1%	0.0%	0.0%	43.9%	0.0%	4.3%	10.1%

Table 12-25 shows the status of all gas projects by number of projects that entered PJM generation queues from January 1, 1997 through March 31, 2016, by zone.

**Table 12-25 Status of all natural gas generation queue projects: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Number of Projects																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	7	1	7	0	5	2	0	1	4	7	0	0	8	3	6	5	6	8	12	0	82
	Upgrade	7	6	6	1	1	8	6	0	26	14	0	0	5	1	10	4	4	6	23	0	128
Under Construction	New Generation	0	3	1	2	2	0	0	1	3	0	1	0	1	0	2	5	4	6	3	0	34
	Upgrade	0	7	2	0	0	6	0	0	3	2	0	0	1	0	2	0	2	1	2	0	28
Suspended	New Generation	3	1	6	0	0	0	0	0	0	1	0	0	0	0	2	0	0	0	0	0	13
	Upgrade	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	1
Withdrawn	New Generation	20	11	32	10	8	6	0	1	16	15	2	2	20	24	42	40	33	37	51	2	372
	Upgrade	4	0	4	3	0	1	0	1	7	4	0	0	5	6	2	5	3	4	13	0	62
Active	New Generation	4	5	9	7	0	11	0	0	1	1	0	1	5	3	1	15	0	6	5	0	74
	Upgrade	3	9	4	2	0	4	0	0	5	0	0	0	1	1	3	2	2	5	6	0	47
Total Projects	New Generation	34	21	55	19	15	19	0	3	24	24	3	3	34	30	51	67	43	57	71	2	575
	Upgrade	14	22	16	6	1	19	6	1	41	20	0	0	12	8	17	12	11	16	44	0	266

Table 12-26 shows the status of all gas projects by MW that entered PJM generation queues from January 1, 1997 through March 31, 2016, by zone.

**Table 12-26 Status of all natural gas generation capacity (MW) in the PJM generation queue: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Project MW																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	1,016.2	580.0	1,701.0	0.0	134.0	629.0	0.0	20.0	3,211.0	1,122.2	0.0	0.0	2,070.3	1,397.0	2,464.0	1,207.4	115.0	1,976.9	2,804.9	0.0	20,448.9
	Upgrade	265.7	107.0	796.7	40.0	2.5	784.0	60.0	0.0	1,363.7	193.0	0.0	0.0	224.0	10.0	800.5	29.5	61.1	327.3	901.9	0.0	5,966.9
Under Construction	New Generation	0.0	2,452.0	930.0	1,599.0	257.3	0.0	0.0	513.0	3,315.1	0.0	205.0	0.0	440.0	0.0	760.5	108.6	2,374.0	3,924.0	12.6	0.0	16,891.1
	Upgrade	0.0	178.0	16.0	0.0	0.0	112.6	0.0	0.0	225.0	7.0	0.0	0.0	200.0	0.0	132.0	0.0	124.5	0.0	210.0	0.0	1,205.1
Suspended	New Generation	1,058.0	525.0	76.1	0.0	0.0	0.0	0.0	0.0	0.0	291.0	0.0	0.0	0.0	0.0	0.0	38.2	0.0	0.0	0.0	0.0	1,988.3
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1.6	0.0	0.0	0.0	0.0	1.6
Withdrawn	New Generation	6,916.9	5,535.0	14,361.7	5,361.0	3,122.1	3,621.0	0.0	134.5	10,421.0	4,545.4	665.0	377.8	9,816.4	11,439.5	23,120.0	14,484.9	20,414.2	17,081.7	22,836.5	6.9	174,261.4
	Upgrade	115.3	0.0	567.0	86.0	0.0	10.0	0.0	36.0	305.3	668.0	0.0	0.0	253.0	1,730.0	205.0	1,040.6	85.0	480.0	2,205.7	0.0	7,786.9
Active	New Generation	734.5	3,381.0	3,372.9	4,106.7	0.0	4,896.3	0.0	0.0	884.5	451.0	0.0	1,150.0	2,736.8	2,311.5	220.0	4,169.1	0.0	2,078.8	2,505.4	0.0	32,998.5
	Upgrade	154.5	835.0	75.0	301.0	0.0	570.0	0.0	0.0	412.3	0.0	0.0	0.0	0.0	34.1	109.0	98.5	144.1	657.0	170.0	0.0	3,560.5
Total Projects	New Generation	9,725.6	12,473.0	20,441.7	11,066.7	3,513.4	9,146.3	0.0	667.5	17,831.6	6,409.6	870.0	1,527.8	15,063.5	15,148.0	26,564.5	20,008.2	22,903.2	25,061.4	28,159.4	6.9	246,588.2
	Upgrade	535.5	1,120.0	1,454.7	427.0	2.5	1,476.6	60.0	36.0	2,306.3	868.0	0.0	0.0	677.0	1,774.1	1,246.5	1,170.2	414.7	1,464.3	3,487.6	0.0	18,521.0

Table 12-27 shows the status of all wind generation projects that entered PJM generation queues from January 1, 1997 through March 31, 2016, by zone. There were 319 wind projects in ComEd, AEP and PENELEC, 64.6 percent of all wind projects in PJM generation queues. Of the 73 wind projects to achieve in service status, 64 projects, 87.7 percent are located within ComEd, AEP, AP and PENELEC. Of the 50 wind projects currently active in the PJM generation queue, 38 projects, 76.0 percent are located within AEP, ComEd and AP.

**Table 12-27 Status of all wind generation queue projects: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Number of Projects																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	1	8	11	0	0	16	0	0	0	0	0	0	0	0	0	19	0	4	0	0	59
	Upgrade	0	0	3	0	0	1	0	0	0	0	0	0	0	0	0	6	0	4	0	0	14
Under Construction	New Generation	0	10	3	1	0	4	0	0	4	2	0	0	0	0	0	1	0	0	0	0	25
	Upgrade	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Suspended	New Generation	2	6	0	0	0	2	2	0	2	0	0	0	0	0	0	3	0	1	0	0	18
	Upgrade	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
Withdrawn	New Generation	14	72	36	6	0	88	13	0	13	6	0	1	0	0	0	60	0	38	1	0	348
	Upgrade	1	0	6	0	0	1	0	0	0	0	0	0	0	0	0	3	0	2	0	0	13
Active	New Generation	0	18	5	1	0	10	0	0	3	2	0	0	0	0	0	2	0	3	0	0	44
	Upgrade	0	0	3	0	0	2	0	0	0	0	0	0	0	0	0	1	0	0	0	0	6
Total Projects	New Generation	17	114	55	8	0	120	15	0	22	10	0	1	0	0	0	85	0	46	1	0	494
	Upgrade	2	0	13	0	0	4	0	0	0	0	0	0	0	0	0	10	0	6	0	0	35

Table 12-28 Status of all wind generation capacity (MW) in the PJM generation queue: January 1, 1997 through March 31, 2016 Table 12-28 shows the wind project capacity in MW of all wind generation projects that have entered the PJM generation queue from January 1, 1997 through March 31, 2016, by zone. Wind projects in ComEd, AEP and PENELEC accounted for 56,069 MW, or 72.5 of all nameplate wind generation capacity in the PJM generation queue. Of the 6,915 MW of wind generation capacity to complete the generation queue process and achieve in service status, 6,681 MW, or 96.6 percent of nameplate capacity is located within ComEd, AEP, AP and PENELEC. Of the 8,304 MW of wind generation capacity currently active in the PJM generation queue, 6,892 MW of generation capacity or 83.0 percent is located within AEP, ComEd and AP.

**Table 12-28 Status of all wind generation capacity (MW) in the PJM generation queue: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Project MW																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	7.5	2,052.0	1,031.4	0.0	0.0	2,634.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	956.7	0.0	199.2	0.0	0.0	6,881.3
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6.4	0.0	27.3	0.0	0.0	33.7
Under Construction	New Generation	0.0	1,446.6	298.0	500.0	0.0	802.5	0.0	0.0	740.3	250.0	0.0	0.0	0.0	0.0	0.0	38.3	0.0	0.0	0.0	0.0	4,075.7
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Suspended	New Generation	368.0	1,170.0	0.0	0.0	0.0	710.0	300.0	0.0	373.6	0.0	0.0	0.0	0.0	0.0	0.0	210.0	0.0	100.0	0.0	0.0	3,231.6
	Upgrade	5.0	0.0	70.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	75.0
Withdrawn	New Generation	3,278.4	13,504.2	2,653.5	645.6	0.0	20,855.8	1,828.0	0.0	1,837.9	2,155.0	0.0	150.3	0.0	0.0	0.0	5,009.0	0.0	2,497.8	20.0	0.0	54,435.5
	Upgrade	0.0	0.0	100.0	0.0	0.0	4.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	179.0	0.0	6.0	0.0	0.0	289.0
Active	New Generation	0.0	4,309.6	547.8	18.0	0.0	1,860.0	0.0	0.0	358.2	499.6	0.0	0.0	0.0	0.0	0.0	150.0	0.0	366.5	0.0	0.0	8,109.7
	Upgrade	0.0	0.0	24.2	0.0	0.0	150.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	20.0	0.0	0.0	0.0	0.0	194.2
Total Projects	New Generation	3,653.9	22,482.4	4,530.7	1,163.6	0.0	26,862.8	2,128.0	0.0	3,310.0	2,904.6	0.0	150.3	0.0	0.0	0.0	6,364.0	0.0	3,163.5	20.0	0.0	76,733.8
	Upgrade	5.0	0.0	194.2	0.0	0.0	154.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	205.4	0.0	33.3	0.0	0.0	591.9

Table 12-29 shows the status of all solar generation projects that have entered the PJM generation queue from January 1, 1997 through March 31, 2016, by zone. Solar projects have been highly concentrated in several zones as of March 31, 2016. Out of a total 886 solar projects in the PJM generation queue, 573 projects or 66.7 percent are in JCPL, AECO, DPL and PSEG. Of these four zones, AECO has the lowest completion rates for new generation and upgrade solar projects. Excluding currently active projects, only 5.8 percent of solar projects classified as new generation or upgrades in AECO are either in service or under construction. Of these four zones, PSEG has the highest completion rates. Excluding currently active projects, 41.2 percent of solar projects classified as either new generation or upgrades in PSEG are either in service or under construction.

The number of currently active new generation solar projects is also highly concentrated in several zones. Out of 113 active new generation projects, 89 projects, or 78.8 percent of all currently active new generation solar projects, are located in Dominion, AP and DPL.

**Table 12-29 Status of all solar generation queue projects: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Number of Projects																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	5	1	2	0	0	1	0	0	6	3	0	0	22	0	1	0	0	2	33	0	76
	Upgrade	0	0	0	0	0	0	0	0	2	0	0	0	3	0	0	0	0	0	0	0	5
Under Construction	New Generation	4	1	5	0	2	0	3	0	5	14	0	0	29	1	0	0	0	3	7	0	74
	Upgrade	0	0	0	0	0	0	0	0	1	9	0	0	2	0	0	0	0	0	0	0	12
Suspended	New Generation	0	4	2	0	0	0	0	0	1	0	0	0	14	0	0	1	0	0	2	0	24
	Upgrade	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Withdrawn	New Generation	145	14	34	6	3	7	4	4	34	71	0	0	136	11	6	10	7	24	55	0	571
	Upgrade	1	1	0	0	0	0	0	0	1	0	0	0	4	0	0	0	0	0	0	0	7
Active	New Generation	6	8	23	0	1	0	0	1	47	19	0	0	4	0	0	0	0	0	4	0	113
	Upgrade	0	0	0	0	0	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	4
Total Projects	New Generation	160	28	66	6	6	8	7	5	93	107	0	0	205	12	7	11	7	29	101	0	858
	Upgrade	1	1	0	0	0	0	0	0	8	9	0	0	9	0	0	0	0	0	0	0	28

Table 12-30 shows the MW for solar projects in the generation queue. Dominion, JCPL and DPL accounted for 657 MW of nameplate solar capacity, 74.3 percent of all new generation solar generation capacity currently under construction.

**Table 12-30 Current status of all solar generation capacity (MW) in the PJM generation queue: January 1, 1997 through March 31, 2016**

Project Status	Project Classification	Project MW																				
		AECO	AEP	AP	ATSI	BGE	ComEd	DAY	DEOK	Dominion	DPL	DLCO	EKPC	JCPL	Met-Ed	PECO	PENELEC	Pepco	PPL	PSEG	RECO	TOTAL
In Service	New Generation	38.5	2.5	34.0	0.0	0.0	9.0	0.0	0.0	157.0	22.4	0.0	0.0	140.3	0.0	3.3	0.0	0.0	15.0	149.6	0.0	571.6
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3.1	0.0	0.0	0.0	5.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	8.9
Under Construction	New Generation	28.7	20.0	54.5	0.0	22.0	0.0	25.9	0.0	243.5	177.5	0.0	0.0	236.0	3.0	0.0	0.0	0.0	16.0	57.2	0.0	884.3
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	4.5	0.0	0.0	0.0	0.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5.0
Suspended	New Generation	0.0	51.7	7.0	0.0	0.0	0.0	0.0	0.0	5.0	0.0	0.0	0.0	155.6	0.0	0.0	13.5	0.0	0.0	9.7	0.0	242.5
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Withdrawn	New Generation	1,600.9	309.2	652.3	60.1	4.2	84.8	51.5	63.0	1,170.2	998.5	0.0	0.0	1,135.4	367.0	51.4	34.3	62.1	267.7	390.6	0.0	7,303.2
	Upgrade	10.0	6.0	0.0	0.0	0.0	0.0	0.0	0.0	8.0	0.0	0.0	0.0	23.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	47.8
Active	New Generation	41.5	47.5	282.3	0.0	1.1	0.0	0.0	125.0	2,013.9	619.3	0.0	0.0	44.6	0.0	0.0	0.0	0.0	0.0	15.8	0.0	3,191.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	193.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	193.9
Total Projects	New Generation	1,709.6	430.9	1,030.1	60.1	27.3	93.8	77.4	188.0	3,589.6	1,817.7	0.0	0.0	1,711.9	370.0	54.7	47.8	62.1	298.7	623.0	0.0	12,192.5
	Upgrade	10.0	6.0	0.0	0.0	0.0	0.0	0.0	0.0	209.5	0.0	0.0	0.0	30.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	255.6

## Role of Transmission Owners in Transmission Planning Study Phase

According to PJM Manual 14A, PJM, in coordination with the TOs, conducts the feasibility, system impact and facilities studies for every interconnection queue project. It is clear that the TOs perform the studies.<sup>25</sup> The coordination begins with PJM identifying transmission issues resulting from the generation projects. The TOs perform the studies and provide the mitigation requirements. A facilities study is required only for new generation and significant generation additions. For a facilities study, the interconnected TO (ITO) and any other affected TOs are required to conduct their own facilities study and provide a summary and results to PJM. PJM compiles these results, along with inputs from the developer, into PJM's models to confirm that the TOs' defined upgrades will resolve the issue. PJM writes the final facilities report, which includes the inputs, a description of the issues to be resolved, and the findings of all contributing TOs.<sup>26</sup>

Of 651 active projects analyzed, the developer and TO are part of the same company for 48 of the projects, or 7,697.0 MW of a total 81,936.3 MW, or

9.4 percent. Where the TO is a vertically integrated company that also owns generation, there is a potential conflict of interest when the TO evaluates the interconnection requirements of new generation which is part of the same company. There is also a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is a competitor to the generation of its parent company.

Table 12-31 is a summary of the number of projects and total MW, by transmission owner parent company, which identifies the number of projects for which the developer and transmission owner are part of the same company. The Dominion Zone has nine related projects which account for 4,370.9 MW, 46.2 percent of the total MW currently in the queue in the Dominion Zone. Of that, 2,745.1 MW (62.8 percent) are natural gas projects, 1,594.0 MW are nuclear, and 31.8 MW are renewable. Renewable projects comprise 4,009.6 MW, 65.7 percent, of unrelated projects in the queue in the Dominion Zone. In contrast, the AEP Zone has 12 related projects, but they account for only 2.5 percent of its total MW currently in the queue.

<sup>25</sup> See PJM, OATT, Part VI, § 210.

<sup>26</sup> See PJM, "Manual 14A: "Generation and Transmission Interconnection Process," Revision 17, (January 22, 2015), <<http://www.pjm.com/documents/manuals.aspx>>.

Table 12-31 Summary of project developer relationship to TO parent company

Parent Company	Number of Projects		Percent Related	Total MW		Percent Related
	Related	Unrelated		Related	Unrelated	
AEP	12	83	12.6%	370.2	14,620.2	2.5%
AES	3	5	37.5%	34.5	325.3	9.6%
DLCO	0	2	0.0%	0.0	225.0	0.0%
Dominion	9	76	10.6%	4,370.9	6,101.4	41.7%
Duke	0	5	0.0%	0.0	654.4	0.0%
Exelon	0	1	0.0%	0.0	1,150.0	0.0%
First Energy	12	94	11.3%	446.0	10,698.6	4.0%
Pepco	1	202	0.5%	1,710.0	23,654.6	6.7%
PPL	0	86	0.0%	0.0	7,375.2	0.0%
PSEG	0	29	0.0%	0.0	7,193.3	0.0%
EKPC	11	20	35.5%	765.4	2,241.3	25.5%
Total	48	603	7.4%	7,697.0	74,239.3	9.4%

These projects are shown by fuel type in Table 12-32. Natural gas generators comprise 50.4 percent of the total related MW in this table. Developers of coal and nuclear projects are almost entirely related to the TO, with 93.5 percent and 100.0 percent of MW. Developers are related to the TO for 6.8 percent of the natural gas project MW in the queue, 8.2 percent of the storage project MW, and 17.3 percent of the hydro project MW. All other fuel types projects have no more than 1.3 percent of MW in development related to the TO.

Table 12-32 Developer-transmission owner relationship by fuel type

Parent Company	Transmission Owner	Related to Developer	Number of Projects	MW by Fuel Type											Total MW
				Biomass	Coal	Diesel	Hydro	Landfill Gas	Natural Gas	Nuclear	Other	Solar	Storage	Wind	
AEP	AEP	Related	12	0.0	83.0	0.0	34.0	0.0	137.0	102.0	0.0	12.2	2.0	0.0	370.2
		Unrelated	83	0.0	128.0	0.0	100.0	13.0	7,234.0	0.0	0.0	107.0	112.0	6,926.2	14,620.2
AES	DAY	Related	3	0.0	12.0	0.0	0.0	0.0	0.0	0.0	0.0	2.5	20.0	0.0	34.5
		Unrelated	5	1.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	23.4	0.0	300.0	325.3
DLCO	DLCO	Unrelated	2	0.0	0.0	0.0	0.0	0.0	205.0	0.0	0.0	0.0	20.0	0.0	225.0
Dominion	Dominion	Related	9	0.0	0.0	0.0	0.0	0.0	2,745.1	1,594.0	0.0	19.8	0.0	12.0	4,370.9
		Unrelated	76	62.5	0.0	0.0	0.0	12.0	2,091.8	0.0	0.0	2,441.0	34.0	1,460.1	6,101.4
Duke	DEOK	Unrelated	5	0.0	0.0	0.0	0.0	6.4	513.0	0.0	0.0	125.0	10.0	0.0	654.4
EKPC	EKPC	Unrelated	1	0.0	0.0	0.0	0.0	0.0	1,150.0	0.0	0.0	0.0	0.0	0.0	1,150.0
Exelon	BGE	Related	3	0.0	0.0	0.0	0.0	0.0	256.0	0.0	0.0	20.0	20.0	0.0	296.0
		Unrelated	27	0.0	0.0	25.0	0.4	4.0	1.3	0.0	132.0	3.1	0.1	0.0	165.9
	ComEd	Related	4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	80.0	0.0	0.0	0.0	80.0
		Unrelated	54	0.0	0.0	0.0	22.7	46.1	5,578.9	0.0	0.0	0.0	111.1	3,522.5	9,281.3
	PECO	Related	5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	50.0	0.0	0.0	20.0	0.0
Unrelated		12	0.0	0.0	6.1	0.0	2.0	1,221.5	0.0	0.0	0.0	20.8	0.0	1,250.4	
First Energy	AP	Related	1	0.0	1,710.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,710.0
		Unrelated	72	0.0	0.0	0.0	0.0	15.2	4,470.0	0.0	0.0	343.8	73.0	940.0	5,842.0
	ATSI	Unrelated	18	0.0	0.0	0.0	0.0	5.6	6,006.7	0.0	0.0	0.0	12.5	518.0	6,542.8
	JCPL	Unrelated	72	0.0	0.0	0.0	0.0	0.0	3,376.8	0.0	0.0	436.7	181.0	0.0	3,994.5
	Met-Ed	Unrelated	5	0.0	0.0	0.0	0.0	0.0	2,345.6	0.0	0.0	3.0	0.0	0.0	2,348.6
	PENELEC	Unrelated	36	0.0	0.0	0.0	40.0	0.0	4,416.0	0.0	0.0	13.5	40.0	418.3	4,927.8
Pepco	AECO	Unrelated	25	0.0	0.0	0.0	0.0	0.0	1,947.0	0.0	0.0	70.2	21.0	373.0	2,411.2
	DPL	Unrelated	53	0.0	0.0	0.0	0.0	2.0	749.0	0.0	0.0	796.8	24.0	749.6	2,321.4
	Pepco	Unrelated	8	0.0	0.0	0.0	0.0	0.0	2,642.6	0.0	0.0	0.0	0.0	0.0	2,642.6
PPL	PPL	Unrelated	29	16.0	0.0	0.0	0.0	5.0	6,659.8	0.0	0.0	16.0	30.0	466.5	7,193.3
PSEG	PSEG	Related	11	0.0	24.0	0.0	0.0	0.0	738.0	0.0	0.0	3.4	0.0	0.0	765.4
		Unrelated	20	0.0	0.0	0.0	0.0	0.0	2,160.0	0.0	0.0	79.3	2.0	0.0	2,241.3
Total		Related	48	0.0	1,829.0	0.0	34.0	0.0	3,876.1	1,826.0	0.0	57.9	62.0	12.0	7,697.0
		Unrelated	603	80.4	128.0	31.1	163.1	111.3	52,769.0	0.0	132.0	4,458.8	691.5	15,674.2	74,239.3




## Regional Transmission Expansion Plan (RTEP)

PJM's Transmission Expansion Advisory Committee (TEAC), made up of PJM staff, is responsible for the Regional Transmission Expansion Plan (RTEP).<sup>27</sup> Transmission upgrades can be divided into three categories: network, supplemental, and baseline. Network upgrades are initiated by generation queue projects and are funded by the developers of the generation projects. Supplemental upgrades are initiated and funded by the TOs. Baseline upgrades are initiated by the TEAC to resolve market efficiency and reliability criteria violations not addressed in other ways. Per FERC Order 1000, the TEAC solicits proposals via fixed proposal windows to address these needs. The TEAC evaluates the proposals and recommends proposals to the PJM Board of Managers for approval. All approved baseline projects are added to the RTEP via amendments to the tariff. Retired generators are included in this analysis for one year after their retirement to reflect the ownership of CIRs.

### RTEP Cost Allocation

The costs of RTEP baseline projects are allocated to all transmission owners, based on the size of the project, the facility voltage, and whether the project addresses a reliability issue or market efficiency. In addition, the allocation methods attempt to distribute the costs proportionally with respect to who will benefit from the upgrade. The allocation rules are summarized in Figure 12-3.

Figure 12-3 RTEP cost allocation rules



For reliability projects, upgrade costs are allocated based on distribution factors (dfax). The distribution factors used in the current allocation method are a measure of the use of the transmission upgrade by zonal loads and by merchant transmission facilities, based on power flow analysis. Under this allocation method (solutions based method), a zone with a distribution factor less than 0.01 is not allocated any costs regardless of its load on the line.<sup>28</sup> This approach to cost allocation replaced the earlier method which was based on distribution factors as a measure of contributions to the reasons for the transmission upgrade.<sup>29</sup>

<sup>27</sup> See PJM, "Manual 14B: PJM Region Transmission Planning Process," Revision 30 (February 26, 2015), Section 2, p.14.

<sup>28</sup> OATT, Schedule 12(b)(iii), (p.595)

<sup>29</sup> See *PJM Interconnection, LLC*, 142 FERC ¶ 61,214 (2013).

## Cost Allocation Issues

The RTEP Baseline Upgrade filings, ER14-972-000 on January 10, 2014, and ER14-1485-000 on March 13, 2014, represented the first time the new allocation rules were used. They resulted in approximately \$1.5 billion in additional baseline transmission enhancements and expansions. PJM approved additional RTEP upgrades (Docket Nos. ER15-2562 and ER15-2563) on July 29, 2015.

In response to complaints about the cost allocations in these filings, on November 24, 2015, FERC accepted, and immediately suspended for five months, both of the July 29, 2015 filings. FERC concluded that “the proposed Tariff amendments have not been shown to be just and reasonable.”<sup>30</sup>

FERC ordered a technical conference, which took place on January 12, 2016, to address the complaints in proceedings EL15-18-000 (ConEd), EL15-67-000 (Linden), and EL15-95-000 (Artificial Island). FERC identified two main discussion points: Whether there is “a definable category of reliability projects within PJM for which the solution-based dfax cost allocation method may not be just and reasonable” and whether there is “an alternative just and reasonable ex ante cost allocation method that could be established for any such category of projects.”<sup>31</sup>

The issues identified in the complaints and at the technical conference include: whether the solutions based allocation method is appropriate for upgrades not related to transmission overload issues; whether the solutions based allocation method correctly identifies all the beneficiaries of the upgrades; whether it is reasonable to allocate a level of costs to a merchant transmission project that could force bankruptcy; and whether the significant shifts in allocation that result from use of the .01 distribution factor cutoff are appropriate.

On April 22, 2016, FERC denied all of the complaints and requests for rehearings in these proceedings.<sup>32</sup> The Commission found that the cost allocations were just and reasonable and that the solutions based DFAX method is appropriate

<sup>30</sup> 153 FERC ¶ 61,245 (November 24, 2015).

<sup>31</sup> “Supplemental Notice of Technical Conference re PJM Interconnection, LLC et al under ER15-2562 et al,” Docket No. E15-95-000 (December 30, 2015).

<sup>32</sup> 155 FERC ¶ 61,088; 155 FERC ¶ 61,091.

for all RTEP projects, including the ones disputed in these complaints. Commissioner LaFleur dissented, stating that the arguments presented by the complainants did adequately identify a class of upgrades where the solution based DFAX method is not appropriate.<sup>33</sup> Commissioner LaFleur recommended that the Commission direct PJM to develop an alternative ex ante approach for this type of project.<sup>34</sup>

The MMU recognizes that the allocation issues are difficult. Nonetheless the allocation methods affect the efficiency of the markets and the incentives for merchant transmission owners to compete to build new transmission. It appears that use of the arbitrary .01 distribution factor cutoff can result in large shifts in cost allocation. It also appears that if the intent of the use of the .01 cutoff is to help eliminate small, arbitrary cost allocations to geographically distant areas, another approach would be to add a threshold for a minimum usage impact on the line. The MMU recommends consideration of changing the minimum distribution factor in the method of allocating costs for baseline projects from .01 to .00 and adding a threshold minimum usage impact on the line.

## TranSource

TranSource LLC filed a complaint against PJM on June 23, 2015, amended February 10, 2016, seeking work papers explaining how PJM performed System Impact Studies (SIS) for three TranSource transmission projects.<sup>35</sup> TranSource complains, in addition, that PJM “fail[ed] to provide TranSource with open access on a nondiscriminatory basis to the PJM transmission planning process and to Auction Revenue Rights (ARR) associated with transmission upgrades” and “violated its requirement to provide TranSource with a transparent, replicable process for evaluating transmission upgrade requests.”<sup>36</sup> PJM responded that it has provided all work papers relevant to the SIS and objects to the complaint on procedural grounds.<sup>37</sup> On September

<sup>33</sup> 155 FERC ¶ 61,088 (LaFleur dissent).

<sup>34</sup> *Id.* at 2.

<sup>35</sup> TranSource Complaint, Amended and Restated Complaint and Request for Fast Track Processing of TranSource, LLC, FERC Docket No. EL15-79-000.

<sup>36</sup> *Id.* at 1-2.

<sup>37</sup> See Motion to Dismiss Complaint and Answer to Complaint Submitted on Behalf of PJM Interconnection, L.L.C., Docket No. EL15-79-000 (July 10, 2015).

24, 2015, the Commission issued an order establishing hearing and settlement judge procedures.<sup>38</sup> The MMU is participating in this process.

## Backbone Facilities

PJM backbone projects are a subset of baseline upgrade projects that have been given the informal designation of backbone due to their relative significance. Backbone upgrades are on the extra high voltage (EHV) system and resolve a wide range of reliability criteria violations and market congestion issues. Designated backbone projects in 2015 included Mount Storm-Doubs, Jacks Mountain, Susquehanna-Roseland, and Surry Skiffes Creek 500kV. Figure 12-4 shows the location of these four projects. Surry Skiffes Creek 500kV is the only remaining active backbone project.

Figure 12-4 PJM Backbone Projects



Two of these projects, Mount Storm-Doubs and Susquehanna-Roseland, were completed in 2015 and are currently in service. The Jacks Mountain backbone project has been cancelled. It was initiated to resolve voltage problems for load deliverability starting June 1, 2017.

38 152 FERC ¶ 61,229.

The Surry Skiffes Creek 500kV was initiated in the fall of 2014 to relieve the overload of the James River Crossing Double Circuit Towerline anticipated to result from the retirement of Chesapeake units 1-4, which occurred in December 2014, and Yorktown 1, which is pending. The initial project includes a new 7.7 mile 500kV line between Surry and Skiffes, a new 20.25 mile 230kV line between Skiffes Creek and Wheelton, and a new Skiffes Creek 500/230kV switching station. PJM's required in service date for the 500kv portion was June 1, 2015. This project has been delayed by legal challenges. BASF Corporation raised environmental concerns with the siting and the design. James City County and James River Association (JCC) argued that the switching station is not part of the transmission line and therefore should be subject to local zoning ordinances. In an April 16, 2015, ruling, the Supreme Court of Virginia rejected BASF's claim but agreed with JCC.<sup>39</sup> On April 30, 2015, Dominion filed a petition for rehearing, which was rejected, and the case was remanded to the State Corporation Commission (SCC). The SCC issued an order on June 5, 2015, stressing the need for this project to be completed, extending the completion date to December 31, 2015.<sup>40</sup> The SCC issued another order on December 4, 2015, temporarily suspending this updated completion date, pending the Army Corps of Engineers' (ACE) issuance of a construction permit.<sup>41</sup> The ACE is currently studying the effects of the project as currently proposed, as well as an alternative approach. The JCC Board will vote on the final action in January, 2016 or later, at which point an energization date can be established.<sup>42</sup>

## Transmission Facility Outages

### Scheduling Transmission Facility Outage Requests

A transmission facility is designated as reportable by PJM if a change in its status can affect a transmission constraint on any Monitored Transmission Facility or could impede free flowing ties within the PJM RTO and/or adjacent

39 BASF Corporation v SCC, et al., Record No. 141009 et al.

40 See Commonwealth of Virginia State Corporation Commission Order in Case No. PUE-2012-00029, June 5, 2015 at <<https://www.dom.com/library/domcom/pdfs/electric-transmission/surry-skiffes-creek/scc-order-060515.pdf>>.

41 See Commonwealth of Virginia State Corporation Commission Order in Case No. PUE-2012-00029, December 4, 2015 at <<https://www.dom.com/library/domcom/pdfs/electric-transmission/surry-skiffes-creek/dec-date-order-120415.pdf?la=en>>.

42 See "Surry-Skiffes Creek 500kV and Skiffes Creek-Wheelton 230kV Projects," which can be accessed at: <<https://www.dom.com/corporate/what-we-do/electricity/transmission-lines-and-projects/surry-skiffes-creek-500kv-and-skiffes-creek-wheelton-230kv-projects>>.

areas.<sup>43</sup> When one of the reportable transmission facilities needs to be taken out of service, the TO is required to submit an outage request as early as possible.<sup>44</sup>

Transmission outages have significant impacts on PJM markets. There are impacts on FTR auctions, on congestion, and on expected market outcomes in the day-ahead and real-time markets. It is important for the efficient functioning of the markets that there be clear, enforceable rules governing transmission outages.

Transmission outages are categorized by duration: greater than 30 calendar days; less than or equal to 30 calendar days and greater than five calendar days; or less than or equal to five calendar days.<sup>45</sup> Table 12-33 shows that 85.6 percent of the requested outages were planned for less than or equal to five days and 1.6 percent of requested outages were planned for greater than 30 days in the first three months of 2016. All of the outage data in this section are for outages scheduled to occur in the first three months of 2015 and 2016, regardless of when they were initially submitted.<sup>46</sup>

**Table 12-33 Transmission facility outage request summary by planned duration: January through March of 2015 and 2016**

Planned Duration (Days)	2015 (Jan - Mar)		2016 (Jan - Mar)	
	Outage Requests	Percent	Outage Requests	Percent
<=5	3,199	74.8%	3,470	85.6%
>5 &lt;=30	746	17.4%	519	12.8%
>30	331	7.7%	63	1.6%
<b>Total</b>	<b>4,276</b>	<b>100.0%</b>	<b>4,052</b>	<b>100.0%</b>

After receiving a transmission facility outage request from a TO, PJM assigns a received status to the request based on its submission date, outage planned starting and ending date, and outage planned duration. The received status can be on time, late or past deadline, as defined in Table 12-34.<sup>47</sup>

<sup>43</sup> If a transmission facility is not modeled in the PJM EMS or the facility is not expected to significantly impact PJM system security or congestion management, it is not reportable. See PJM, "Manual 3A: Energy Management System (EMS) Model Updates and Quality Assurance (QA), Revision 10 (June 25, 2015).

<sup>44</sup> See PJM, "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p.57.

<sup>45</sup> See PJM, "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p.58.

<sup>46</sup> The hotline tickets, EMS tripping tickets or test outage tickets were excluded. We only included all the transmission outage tickets submitted by PJM internal companies which are currently active.

<sup>47</sup> See PJM, "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p.58 and p.59.

The purpose of the rules defined in Table 12-34 is to require the TOs to submit transmission facility outages prior to the Financial Transmission Right (FTR) auctions so that market participants have complete information about market conditions on which to base their FTR bids and so that PJM can accurately model market conditions.<sup>48</sup>

**Table 12-34 PJM transmission facility outage request received status definition**

Planned Duration (Days)	Ticket Submission Date	Received Status
<=5	Before the 1st of the month one month prior to the starting month of the outage	On Time
	After or on the 1st of the month one month prior to the starting month of the outage	Late
	After 8:00AM three days prior to the outage	Past Deadline
> 5 &lt;=30	Before the 1st of the month six months prior to the starting month of the outage	On Time
	After or on the 1st of the month six months prior to the starting month of the outage	Late
	After 8:00AM three days prior to the outage	Past Deadline
>30	The earlier of 1) February 1st, 2) the 1st of the month six months prior to the starting month of the outage	On Time
	After or on the earlier of 1) February 1st, 2) the 1st of the month six months prior to the starting month of the outage	Late
	After 8:00AM three days prior to the outage	Past Deadline

Table 12-35 shows a summary of requests by received status. In the first three months of 2016, 53.9 percent of outage requests received were late.

<sup>48</sup> See "Report of PJM Interconnection, LLC on Transmission Oversight Procedures," Docket No. EL01-122-000 (November 2, 2001).

**Table 12-35 Transmission facility outage request summary by received status: January through March of 2015 and 2016**

Planned Duration (Days)	2015 (Jan - Mar)				2016 (Jan - Mar)			
	On Time	Late	Total	Percent Late	On Time	Late	Total	Percent Late
<=5	1,631	1,568	3,199	49.0%	1,598	1,872	3,470	53.9%
>5 &lt;=30	401	345	746	46.2%	249	270	519	52.0%
>30	120	211	331	63.7%	33	30	63	47.6%
Total	2,152	2,124	4,276	49.7%	1,880	2,172	4,052	53.6%

Once received, PJM processes outage requests in priority order: emergency transmission outage request; transmission outage requests submitted on time; and transmission outage request submitted late. PJM retains the right to deny all transmission outage requests that are submitted past the relevant deadline unless the request is an emergency.<sup>49</sup>

Outages with emergency status will be approved even if submitted past the relevant deadline after PJM determines that the outage does not result in Emergency Procedures. PJM cancels or withholds approval of any outage that results in Emergency Procedures.<sup>50</sup> Table 12-36 is a summary of outage requests by emergency status. Of all outage requests scheduled to occur in the first three months of 2016, 16.2 percent were for emergency outages. Of all outage requests scheduled to occur in the first three months of 2015, 15.4 percent were for emergency outages.

**Table 12-36 Transmission facility outage request summary by emergency: January through March of 2015 and 2016**

Planned Duration (Days)	2015 (Jan - Mar)				2016 (Jan - Mar)			
	Emergency	Non Emergency	Total	Percent Emergency	Emergency	Non Emergency	Total	Percent Emergency
<=5	518	2,681	3,199	16.2%	565	2,905	3,470	16.3%
>5 &lt;=30	107	639	746	14.3%	85	434	519	16.4%
>30	34	297	331	10.3%	6	57	63	9.5%
Total	659	3,617	4,276	15.4%	656	3,396	4,052	16.2%

49 PJM. "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p. 69.

50 PJM. "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p. 67 and p.68.

PJM will approve all transmission outage requests that are submitted on time and do not jeopardize the reliability of the PJM system. PJM will approve all transmission outage requests that are submitted late and do not cause congestion on the PJM system and do not jeopardize the reliability of the PJM system.

After PJM determines that a late request may cause congestion, PJM informs the Transmission Owner of solutions available to eliminate the congestion. For example, if a generator planned or maintenance outage request is contributing to the congestion, PJM can request that the Generation Owner defer the outage. If no solutions are available, PJM may require the Transmission Owner to reschedule or cancel the outage. Table 12-37 is a summary of outage requests by congestion status. Of all outage requests submitted to occur in the first three months of 2016, 8.0 percent were expected to cause congestion. Of all the outage requests that were expected to cause congestion, 4.0 percent (13 out of 324) were denied by PJM in the first three months of 2016 (Table 12-39).

**Table 12-37 Transmission facility outage request summary by congestion: January through March of 2015 and 2016**

Planned Duration (Days)	2015 (Jan - Mar)				2016 (Jan - Mar)			
	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
<=5	309	2,890	3,199	9.7%	242	3,228	3,470	7.0%
>5 &lt;=30	84	662	746	11.3%	71	448	519	13.7%
>30	40	291	331	12.1%	11	52	63	17.5%
Total	433	3,843	4,276	10.1%	324	3,728	4,052	8.0%

Table 12-38 shows the outage requests summary by received status, congestion status and emergency status. In the first three months of 2016, 70.0 percent of late requests were non-emergency outages while 5.1 percent of late non-emergency outage requests were expected to cause congestion.

**Table 12-38 Transmission facility outage requests that by received status, congestion and emergency: January through March of 2015 and 2016**

		2015 (Jan - Mar)				2016 (Jan - Mar)			
Submission Status		No Congestion		Percent Congestion	No Congestion		Percent Congestion		
		Expected	Expected		Expected	Expected			
Late	Emergency	24	633	657	3.7%	18	634	652	2.8%
	Non Emergency	73	1,394	1,467	5.0%	78	1,442	1,520	5.1%
On Time	Emergency	0	2	2	0.0%	0	4	4	0.0%
	Non Emergency	336	1,814	2,150	15.6%	228	1,648	1,876	12.2%
Total		433	3,843	4,276	10.1%	324	3,728	4,052	8.0%

Once PJM processes an outage request, the outage request is labelled as submitted, received, denied, approved, cancelled by company, revised, active or complete according to the processed stage of a request.<sup>51</sup> Table 12-39 shows the detailed process status for outage requests only for the outage requests that are expected to cause congestion. All process status categories except cancelled, complete or denied are in the In Process category in Table 12-39. Table 12-39 shows that 71.8 (56 out of 78) percent of late, non-emergency, outage requests which were expected to cause congestion were approved and completed and 4.0 percent (13 out of 324) of the outage requests which were expected to cause congestion were denied in 2015.

**Table 12-39 Transmission facility outage requests that might cause congestion status summary: January through March of 2015 and 2016**

		2015 (Jan - Mar)						2016 (Jan - Mar)					
Submission Status		Cancelled	Complete	In Process	Denied	Congestion		Cancelled	Complete	In Process	Denied	Congestion	
						Expected	Percent Complete					Expected	Percent Complete
Late	Emergency	5	18	0	1	24	75.0%	0	18	0	0	18	100.0%
	Non Emergency	17	46	0	10	73	63.0%	14	56	0	8	78	71.8%
On Time	Emergency	107	211	1	17	336	62.8%	62	161	0	5	228	70.6%
	Non Emergency	0	0	0	0	0	0.0%	0	0	0	0	0	0.0%
Total		129	275	1	28	433	63.5%	76	235	0	13	324	72.5%

There are clear rules defined for assigning on time or late status for submitted outage requests in both the PJM Tariff and PJM Manuals.<sup>52</sup> However, the on

<sup>51</sup> See PJM, "Outage Information," <<http://www.pjm.com/markets-and-operations/etools/oasis/system-information/outage-info.aspx>> (November 1, 2015).

<sup>52</sup> OATT Attachment K Appendix § 1.9.2 (Outage Scheduling).

time or late status only affects the priority that PJM assigns for processing the outage request. Many (71.8 percent) non-emergency, expected to cause congestion, late transmission outages were approved and completed. The expected impact on congestion is the basis for PJM's treatment of late outage requests. But there is no rule or clear definition of this congestion analysis in the PJM Manuals. The MMU recommends that PJM draft a clear definition of the congestion analysis required for transmission outage requests to include in Manual 3 after appropriate review.

## Rescheduling Transmission Facility Outage Requests

A TO can reschedule or cancel an outage after initial submission. Table 12-40 is a summary of all the outage requests planned for the first three months of 2015 and 2016 which were approved and then cancelled or rescheduled by TOs at least once. If an outage request was submitted, approved and subsequently rescheduled at least once, the outage request will be counted as Approved and Rescheduled. If an outage request was submitted, approved and subsequently cancelled at least once, the outage request will be counted as Approved and Cancelled. In the first three months of 2016, 17.9 percent of transmission outage requests were approved by PJM and then rescheduled by

the TOs, and 8.8 percent of the transmission outages were approved by PJM and subsequently cancelled by the TOs.

**Table 12-40 Rescheduled and cancelled transmission outage request summary: January through March of 2015 and 2016**

Days	2015 (Jan - Mar)					2016 (Jan - Mar)				
	Outage Requests	Approved and Rescheduled	Percent Approved and Rescheduled	Approved and Cancelled	Percent Approved and Cancelled	Outage Requests	Approved and Rescheduled	Percent Approved and Rescheduled	Approved and Cancelled	Percent Approved and Cancelled
<=5	3,199	350	10.9%	453	14.2%	3,470	425	12.2%	333	9.6%
>5 Et <=30	746	343	46.0%	50	6.7%	519	263	50.7%	22	4.2%
>30	331	184	55.6%	32	9.7%	63	37	58.7%	3	4.8%
Total	4,276	877	20.5%	535	12.5%	4,052	725	17.9%	358	8.8%

If a requested outage is determined to be late and TO reschedules the outage, the outage will be reevaluated by PJM again as on time or late.

A transmission outage ticket with a duration of five days or less with an on time status can retain its on time status if the outage is rescheduled within the original scheduled month.<sup>53</sup> This rule allows a TO to reschedule within the same month with very little notice.

A transmission outage ticket with a duration exceeding five days with an on time status can retain its on time status if the outage is rescheduled to a future month, and the revision is submitted by the first of the month prior to the revised month in which the outage will occur.<sup>54</sup> This rescheduling rule is much less strict than the rule that applies to the first submission of outage requests with similar duration. When first submitted, the outage request with a duration exceeding five days needs to be submitted before the first of the month six months prior to the month in which the outage was expected to occur.

The MMU recommends that PJM reevaluate all transmission outage tickets as on time or late as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages.

## Long Duration Transmission Facility Outage Requests

PJM rules (Table 12-34) define a transmission outage request as on time or late based on the planned outage duration and the time of submission. The rule has stricter submission requirements for transmission outage requests planned for longer than 30 days. In order to avoid the stricter submission requirement, some transmission owners divided the duration of outage requests longer than 30 days into shorter segments for the same equipment and submitted one request for each segment. The MMU recommends that PJM not permit transmission owners to divide long duration outages into smaller segments to avoid complying with the requirements for long duration outages. Table 12-41 shows that there were 3,262 transmission equipment planned outages in the first three months of 2016, of which 76 were planned outages longer than 30 days, and of which 13 or 0.4 percent were scheduled longer than 30 days if the duration of the outages were combined for the same equipment. The duration of those outages could potentially be longer than 30 days, however were divided into shorter periods by transmission owners.

<sup>53</sup> PJM. "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p. 63.

<sup>54</sup> PJM. "Manual 3: Transmission Operations," Revision 48 (December 1, 2015), p. 64.

**Table 12-41 Transmission outage summary: January through March of 2015 and 2016**

Duration	Divided into Shorter Periods	2015 (Jan - Mar)		2016 (Jan - Mar)	
		Number of Outages	Percent	Number of Outages	Percent
> 30 Days	No	302	9.3%	63	1.9%
	Yes	15	0.5%	13	0.4%
<= 30 Days		2,947	90.3%	3,186	97.7%
Total		3,264	100.0%	3,262	100.0%

Table 12-42 shows the details of potentially long duration (> 30 days) outages when combining the duration of the outages for the same equipment. The actual duration of scheduled outages would be longer than 30 days if the duration of the outages were combined for the same equipment within a period of days. In the first three months of 2016, there would have been one outages with a combined duration longer than 30 days that were instead scheduled to occur as shorter outages within a period of less than or equal to 31 days. In the first three months of 2016, there would have been three outages with a combined duration longer than 30 days that were instead scheduled to occur as shorter outages within a period of more than 62 days and less than 93 days.

**Table 12-42 Summary of potentially long duration (> 30 days) outages: January through March of 2015 and 2016**

Days	2015 (Jan - Mar)		2016 (Jan - Mar)	
	Number of Outages	Percent	Number of Outages	Percent
<=31	5	33.3%	1	7.7%
>31 &lt;=62	5	33.3%	9	69.2%
>62 and <=93	5	33.3%	3	23.1%
>93	0	0.0%	0	0.0%
Total	15	100.0%	13	100.0%

## Transmission Facility Outage Analysis for the FTR Market

Transmission facility outages affect the price and quantity outcomes of FTR auctions. The purpose of the rules is to ensure that outages are known with enough lead time prior to FTR auctions both so that market participants can

understand market conditions and so that PJM can accurately model market conditions. Outage requests must be submitted according to rules based on planned outage duration (Table 12-34). The rules defining when an outage is late are based on the timing of FTR auctions. When an outage request is submitted late, the outage will be marked as late and may be denied if it is expected to cause congestion. Table 12-46 shows that 819 outage requests with a duration of two weeks or longer but shorter than two months were late, and only four of them were denied by PJM. Table 12-46 also shows that 209 outage requests with a duration of two months or longer were late and none of them were denied by PJM in the 2015 to 2016 planning year.

There are Long Term, Annual and Monthly Balance of Planning Period auctions in the FTR market. When modeling transmission outages in the annual ARR allocation and FTR auction, PJM does not consider outages with planned durations shorter than two weeks, does consider some outages with planned duration longer than two weeks but shorter than two months, and does consider all outages with planned duration longer than or equal to two months. PJM posts an FTR outage list to the FTR web page usually at least one week before the auction bidding opening day.<sup>55</sup>

Table 12-43 shows that 89.8 percent of the outage requests for outages expected to occur during the planning period 2015 to 2016 had a planned duration of less than two weeks and that 47.4 (8,880 out of 18,929) percent of all outage requests for the planning period were submitted late according to outage submission rules.

**Table 12-43 Transmission facility outage requests by received status: Planning periods 2014 to 2015 and 2015 to 2016**

Planned Duration	2014/2015				2015/2016			
	On Time	Late	Total	Percent	On Time	Late	Total	Percent
<2 weeks	9,306	8,382	17,688	88.7%	9,039	7,952	16,991	89.8%
>=2 weeks &lt; 2 months	844	896	1,740	8.7%	771	819	1,590	8.4%
>=2 months	201	317	518	2.6%	139	209	348	1.8%
Total	10,351	9,595	19,946	100.0%	9,949	8,980	18,929	100.0%

<sup>55</sup> PJM Financial Transmission Rights, "Annual ARR Allocation and FTR Auction Transmission outage Modeling," <<http://www.pjm.com/~media/markets-ops/ftr/annual-ftr-auction/2015-2016/2015-2016-annual-outage-modeling.ashx>> (April 1, 2015).



Table 12-44 shows outage requests summary by emergency status. Of all outage requests for outages expected to occur in the 2015 to 2016 planning year and submitted late, 74.0 percent were for non-emergency outages.

**Table 12-44 Transmission facility outage requests by received status and emergency: Planning periods 2014 to 2015 and 2015 to 2016**

Planned Duration	2014/2015				2015/2016			
	Emergency	Non Emergency	Total	Percent Non Emergency	Emergency	Non Emergency	Total	Percent Non Emergency
On Time <2 weeks	13	9,293	9,306	99.9%	16	9,023	9,039	99.8%
>=2 weeks & <2 months	0	844	844	100.0%	2	769	771	99.7%
>=2 months	0	201	201	100.0%	0	139	139	100.0%
Total	13	10,338	10,351	99.9%	18	9,931	9,949	99.8%
Late <2 weeks	2,370	6,012	8,382	71.7%	2,161	5,791	7,952	72.8%
>=2 weeks & <2 months	169	727	896	81.1%	138	681	819	83.2%
>=2 months	63	254	317	80.1%	34	175	209	83.7%
Total	2,602	6,993	9,595	72.9%	2,333	6,647	8,980	74.0%

PJM analyzes expected congestion for both on time and late outage requests. A late outage request may be denied or cancelled if it is expected to cause congestion. Table 12-45 shows a summary of requests by expected congestion and received status. Overall, 4.6 percent of all outage requests for outages expected to occur in the 2015 to 2016 planning year and submitted late were requests that were expected to cause congestion.

**Table 12-45 Transmission facility outage requests by submission status and congestion: Planning periods 2014 to 2015 and 2015 to 2016**

Planned Duration	2014/2015				2015/2016			
	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
On Time <2 weeks	1,339	7,967	9,306	14.4%	1,179	7,860	9,039	13.0%
>=2 weeks & <2 months	168	676	844	19.9%	164	607	771	21.3%
>=2 months	38	163	201	18.9%	32	107	139	23.0%
Total	1,545	8,806	10,351	14.9%	1,375	8,574	9,949	13.8%
Late <2 weeks	447	7,935	8,382	5.3%	355	7,597	7,952	4.5%
>=2 weeks & <2 months	45	851	896	5.0%	44	775	819	5.4%
>=2 months	9	308	317	2.8%	10	199	209	4.8%
Total	501	9,094	9,595	5.2%	409	8,571	8,980	4.6%

Table 12-46 shows that 70.5 percent of late outage requests with a duration of two weeks or longer but shorter than two months were completed, 0.5 percent were denied by PJM and 13.0 percent of late outage requests with a duration of two weeks or longer but shorter than two months were approved or active in the 2015 to 2016 planning year. The table also shows that 71.8 percent of late outage requests with duration of two months or longer were completed, none of them were denied, and 19.1 percent were approved and active in the 2015 to 2016 planning year.

Table 12-46 Transmission facility outage requests by received status and processed status: Planning periods 2014 to 2015 and 2015 to 2016

Planned Duration	Processed Status	2014/2015				2015/2016			
		On Time	Percent	Late	Percent	On Time	Percent	Late	Percent
<2 weeks	In Progress	21	0.2%	146	1.7%	1,415	15.7%	400	5.0%
	Denied	106	1.1%	100	1.2%	69	0.8%	51	0.6%
	Approved	0	0.0%	0	0.0%	51	0.6%	40	0.5%
	Cancelled by Company	2,761	29.7%	1,205	14.4%	2,277	25.2%	937	11.8%
	Revised	0	0.0%	0	0.0%	8	0.1%	2	0.0%
	Active	0	0.0%	0	0.0%	95	1.1%	69	0.9%
	Completed	6,418	69.0%	6,931	82.7%	5,124	56.7%	6,453	81.1%
Total Submission		9,306	100.0%	8,382	100.0%	9,039	100.0%	7,952	100.0%
>=2 weeks & <2 months	In Progress	1	0.1%	9	1.0%	50	6.5%	52	6.3%
	Denied	0	0.0%	4	0.4%	1	0.1%	4	0.5%
	Approved	0	0.0%	0	0.0%	3	0.4%	4	0.5%
	Cancelled by Company	199	23.6%	106	11.8%	208	27.0%	80	9.8%
	Revised	0	0.0%	0	0.0%	4	0.5%	0	0.0%
	Active	0	0.0%	0	0.0%	64	8.3%	102	12.5%
	Completed	644	76.3%	777	86.7%	441	57.2%	577	70.5%
Total Submission		844	100.0%	896	100.0%	771	100.0%	819	100.0%
>=2 months	In Progress	0	0.0%	7	2.2%	0	0.0%	4	1.9%
	Denied	0	0.0%	0	0.0%	0	0.0%	0	0.0%
	Approved	0	0.0%	0	0.0%	0	0.0%	0	0.0%
	Cancelled by Company	42	20.9%	31	9.8%	30	21.6%	15	7.2%
	Revised	0	0.0%	0	0.0%	0	0.0%	0	0.0%
	Active	0	0.0%	1	0.3%	24	17.3%	40	19.1%
	Completed	159	79.1%	278	87.7%	85	61.2%	150	71.8%
Total Submission		201	100.0%	317	100.0%	139	100.0%	209	100.0%

Table 12-47 shows that there were 819 outage requests with a duration of two weeks or longer but shorter than two months submitted late, of which 41 were non-emergency and expected to cause congestion in the 2015 to 2016 planning year. Of the 41 such requests, three were approved and active, and 31 were complete. For the outages planned for two months or longer, there were 348 total outages, of which 209 requests were late. Of the late requests, nine outages that were non-emergency and expected to cause congestion were all approved.

Table 12-47 Transmission facility outage requests by received status, processed status, emergency and congestion: Planning periods 2014 to 2015 and 2015 to 2016

Planned Duration	Processed Status	2014/2015						2015/2016					
		On Time			Late			On Time			Late		
		Non Emergency and Congestion Expected	Total	Percent	Non Emergency and Congestion Expected	Total	Percent	Non Emergency and Congestion Expected	Total	Percent	Non Emergency and Congestion Expected	Total	Percent
<2 weeks	In Progress	2	21	9.5%	3	146	2.1%	173	1,415	12.2%	16	400	4.0%
	Denied	70	106	66.0%	39	100	39.0%	32	69	46.4%	17	51	33.3%
	Approved	0	0	0.0%	0	0	0.0%	3	51	5.9%	1	40	2.5%
	Cancelled by Company	362	2,761	13.1%	75	1,205	6.2%	277	2,277	12.2%	50	937	5.3%
	Revised	0	0	0.0%	0	0	0.0%	2	8	25.0%	0	2	0.0%
	Active	0	0	0.0%	0	0	0.0%	14	95	14.7%	2	69	2.9%
	Completed	904	6,418	14.1%	224	6,931	3.2%	675	5,124	13.2%	187	6,453	2.9%
Total Submission		1,338	9,306	14.4%	341	8,382	4.1%	1,176	9,039	13.0%	273	7,952	3.4%
>=2 weeks & <2 months	In Progress	1	1	100.0%	0	9	0.0%	21	50	42.0%	3	52	5.8%
	Denied	0	0	0.0%	2	4	50.0%	1	1	100.0%	0	4	0.0%
	Approved	0	0	0.0%	0	0	0.0%	0	3	0.0%	0	4	0.0%
	Cancelled by Company	31	199	15.6%	6	106	5.7%	22	208	10.6%	4	80	5.0%
	Revised	0	0	0.0%	0	0	0.0%	2	4	50.0%	0	0	0.0%
	Active	0	0	0.0%	0	0	0.0%	12	64	18.8%	3	102	2.9%
	Completed	136	644	21.1%	33	777	4.2%	106	441	24.0%	31	577	5.4%
Total Submission		168	844	19.9%	41	896	4.6%	164	771	21.3%	41	819	5.0%
>=2 months	In Progress	0	0	0.0%	0	7	0.0%	0	0	0.0%	0	4	0.0%
	Denied	0	0	0.0%	0	0	0.0%	0	0	0.0%	0	0	0.0%
	Approved	0	0	0.0%	0	0	0.0%	0	0	0.0%	0	0	0.0%
	Cancelled by Company	3	42	7.1%	1	31	3.2%	2	30	6.7%	0	15	0.0%
	Revised	0	0	0.0%	0	0	0.0%	0	0	0.0%	0	0	0.0%
	Active	0	0	0.0%	0	1	0.0%	8	24	33.3%	3	40	7.5%
	Completed	35	159	22.0%	8	278	2.9%	22	85	25.9%	6	150	4.0%
Total Submission		38	201	18.9%	9	317	2.8%	32	139	23.0%	9	209	4.3%

If an outage request were submitted after the Annual FTR Auction bidding opening date, the outage would not be considered in the FTR model. If an outage were submitted on time according to the transmission outage rules, it may not be modeled in the FTR model if it is submitted after the Annual FTR Auction bidding opening date. Table 12-48 shows that 91.2 percent of outage requests labelled on time according to rules were submitted or rescheduled after the annual FTR bidding opening date in the 2015 to 2016 planning year.

**Table 12-48 Transmission facility outage requests by received status and bidding opening date: Planning periods 2014 to 2015 and 2015 to 2016**

Planned Duration	2014/2015						2015/2016					
	On Time			Late			On Time			Late		
	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After
<2 weeks	566	8,740	93.9%	13	8,369	99.8%	640	8,399	92.9%	10	7,942	99.9%
>=2 weeks & <2 months	173	671	79.5%	14	882	98.4%	195	576	74.7%	12	807	98.5%
>=2 months	45	156	77.6%	2	315	99.4%	36	103	74.1%	6	203	97.1%
Total	784	9,567	92.4%	29	9,566	99.7%	871	9,078	91.2%	28	8,952	98.3%

Table 12-49 shows that 80.0 percent of late outage requests which were submitted or rescheduled after the Annual FTR Auction bidding opening date were approved and complete in the 2015 to 2016 planning.

**Table 12-49 Late transmission facility outage requests that are submitted after annual bidding opening date: Planning periods 2014 to 2015 and 2015 to 2016**

Planned Duration	2014/2015			2015/2016		
	Completed Outages	Total	Percent	Completed Outages	Total	Percent
<2 weeks	6,926	8,369	82.8%	6,447	7,942	81.2%
>=2 weeks & <2 months	772	882	87.5%	570	807	70.6%
>=2 months	277	315	87.9%	149	203	73.4%
Total	7,975	9,566	83.4%	7,166	8,952	80.0%

Thus, although the definition of late outages was developed in order to prevent outages for the planning period being submitted after the Annual FTR Auction bidding opening date, the rules have not worked to prevent this since the rule has no direct connection to the annual FTR auction opening date. The MMU recommends that PJM modify the rules to reduce or eliminate the approval of late outage requests submitted or rescheduled after the FTR Auction bidding opening date.

## Transmission Facility Outage Analysis in the Day-Ahead Market

Transmission facility outages also affect the energy market. Just as with the FTR Market, it is critical that outages that affect the operating day are known prior to the submission of offers in the Day-Ahead Energy Market both, so that market participants can understand market conditions and so that PJM can accurately model market conditions.

PJM maintains the history of outage requests including all the processed status changes and all the starting or ending date changes. Any such status change is defined as an instance. For example, if an outage request were submitted, received, approved and completed, the four occurrences, termed instances, of the outage request will be stored in the database. If an outage request is revised, that is an instance. There may be more than one instance for each outage request due to the change of the processed status. In the day-ahead market transmission outage analysis, all instances of the outages when either the status of the request is changed planned to occur in the first three months of 2015 and 2016 are included. In the day-ahead market transmission analysis, all submissions or changes of outage requests at or after 12:00 pm on the day before the planned starting date until the hour beginning 23:00 pm on the planned starting date will be defined as late for day-ahead market.

Table 12-50 shows that in the first three months of 2016 8.5 percent of non-emergency outage request instances were submitted late for the day-ahead market and PJM expected them to cause congestion.

**Table 12-50 Transmission facility outage request instance summary by congestion and emergency: January through March of 2015 and 2016**

For Day-ahead Market	Submission Status	2015 (Jan - Mar)				2016 (Jan - Mar)			
		Congestion Expected	No Congestion Expected	Total	Percent Congestion	Congestion Expected	No Congestion Expected	Total	Percent Congestion
Late	Emergency	86	942	1,028	8.4%	34	926	960	3.5%
	Non Emergency	478	3,268	3,746	12.8%	287	3,081	3,368	8.5%
On Time	Emergency	174	3,425	3,599	4.8%	102	2,241	2,343	4.4%
	Non Emergency	3,874	20,730	24,604	15.7%	2,111	16,106	18,217	11.6%
Total		4,612	28,365	32,977	14.0%	2,534	22,354	24,888	10.2%

Table 12-51 shows that there were 4,328 late outage request instances which were submitted in the first three months of 2016, of which 605 (14.0 percent) had the status submitted, cancelled by company or revised and 23 (0.5 percent) non-emergency instances had the status submitted, cancelled by company or revised and were expected to cause congestion.

**Table 12-51 Late transmission facility outage request instance status summary by congestion and emergency: January through March of 2015 and 2016**

Processed Status	2015 (Jan - Mar)			2016 (Jan - Mar)		
	Non Emergency and Congestion Expected	Total	Percent	Non Emergency and Congestion Expected	Total	Percent
Submitted	12	428	2.8%	4	396	1.0%
Cancelled by Company	19	214	8.9%	10	109	9.2%
Revised	8	106	7.5%	9	100	9.0%
Other	439	4,026	10.9%	264	3,723	7.1%
Total	478	4,774	10.0%	287	4,328	6.6%

Table 52 shows that the top five zones accounted for 56.0 percent of all outages that were submitted, cancelled or revised late for the day-ahead market in the first three months of 2016. These zones were: AEP, ATSI, ComEd, GPU, and Dominion.

**Table 12-52 Transmission facility outage request instances submitted, cancelled or revised late for the Day-ahead Market summary by transmission owner/zone: January through March of 2015 and 2016**

Transmission Owner/Company	2015 (Jan - Mar)			2016 (Jan - Mar)		
	Late for Day Ahead Market	On Time for Day Ahead Market	Percent of Total Late	Late for Day Ahead Market	On Time for Day Ahead Market	Percent of Total Late
AECO	26	694	3.5%	32	504	5.3%
AEP	107	1,393	14.3%	108	709	17.9%
AP	64	468	8.6%	44	296	7.3%
ATSI	128	1,356	17.1%	69	891	11.4%
BGE	41	359	5.5%	32	342	5.3%
CPP	2	7	0.3%	3	43	0.5%
ComEd	49	1,179	6.6%	59	905	9.8%
DAY	1	36	0.1%	10	44	1.7%
DEOK	13	150	1.7%	14	102	2.3%
DLCO	14	386	1.9%	6	269	1.0%
DPL	39	627	5.2%	25	425	4.1%
Dominion	55	1,213	7.4%	46	905	7.6%
EKPC	15	99	2.0%	11	60	1.8%
GPU	73	862	9.8%	57	595	9.4%
Linden	3	5	0.4%	1	2	0.2%
Neptune	0	3	0.0%	2	5	0.3%
PECO	24	611	3.2%	23	365	3.8%
PPL	30	275	4.0%	23	156	3.8%
PSEG	38	1,796	5.1%	28	581	4.6%
Pepco	17	227	2.3%	10	228	1.7%
RECO	6	21	0.8%	2	19	0.3%
UGI	3	27	0.4%	0	16	0.0%
Total	748	11,794	100.0%	605	7,462	100.0%

