

# Generation and Transmission Planning<sup>1</sup>

## Overview

### Generation Interconnection Planning

#### Existing Generation Mix

- As of December 31, 2018, PJM had a total installed capacity of 199,489.0 MW, of which 57,891.9 MW (29.0 percent) are coal fired steam units, 46,207.1 MW (23.2 percent) are combined cycle units and 34,257.6 MW (17.2 percent) are nuclear units. This measure of installed capacity differs from capacity market installed capacity because it includes energy only units, excludes all external units, and uses nameplate values for solar and wind resources.
- The AEP zone has the most total installed capacity of any PJM zone. Of the 199,489.0 MW of PJM total installed capacity, 31,643.0 MW (15.9 percent) are in the AEP Zone, of which 14,727.8 MW (46.5 percent) are coal fired steam units, 6,990.0 MW (22.1 percent) are combined cycle units and 2,071.0 MW (6.5 percent) are nuclear units.
- Pennsylvania has the most total installed capacity of any PJM state. Of the 199,489.0 MW of installed capacity, 44,753.1 MW (22.4 percent) are in Pennsylvania, of which 9,467.7 MW (21.2 percent) are coal fired steam units, 13,656.5 MW (30.5 percent) are combined cycle units and 9,648.8 MW (21.6 percent) are nuclear units.
- Of the 199,489.0 MW of installed capacity, 76,587.5 MW (38.4 percent) are from units older than 40 years, of which 41,426.7 MW (54.1 percent) are coal fired steam units, 16,044.9 MW (20.9 percent) are nuclear units, and 532.0 MW (0.7 percent) are combined cycle units.

#### Generation Retirements<sup>2</sup>

- There are 44,684.1 MW of generation that have been, or are planned to be, retired between 2011 and 2022, of which 31,621.4 MW (70.8 percent) are coal fired steam units. Coal unit retirements are primarily

a result of the inability of coal units to compete with efficient combined cycle units burning low cost gas.

- In 2018, 5,522.7 MW of generation retired. The largest generator that retired in 2018 was the 614.5 MW Oyster Creek Nuclear Generating Station owned by Exelon Corporation and located in the Jersey Central Power and Light (JCPL) Zone. Of the 5,522.7 MW of generation that retired, 2,364.0 MW (42.8 percent) were located in the DAY Zone.
- There are 13,398.0 MW of generation that have requested retirement after December 31, 2018, of which 6,791.0 MW (50.7 percent) are located in the ATSI Zone. Of the ATSI generation requesting retirement, 7,829.3 MW (58.4 percent) are coal fired steam units and 4,716.0 MW (35.2 percent) are nuclear units. The largest generator pending retirement is the 1,240 MW Perry U1 Nuclear Generating Unit located in the ATSI Zone.

#### Generation Queue<sup>3</sup>

- The total MW in generation queues increased by 41,846.2 MW (57.2 percent) from 73,107.6 MW at the end of 2017 to 114,953.7 MW on December 31, 2018.
- A significant shift in the distribution of unit types within the PJM footprint continues to develop as natural gas fired units enter the queue and coal fired steam units retire. As of December 31, 2018, there were 52,804.2 MW of natural gas fired capacity active, suspended or under construction in PJM queues (including combined cycle units, CTs, RICE units, and natural gas fired steam units). As of December 31, 2018, there were only 147.0 MW of coal fired steam capacity active, suspended or under construction in PJM queues.
- As of December 31, 2018, 4,144 projects, representing 529,165.5 MW, have entered the queue process since its inception in 1998. Of those, 816 projects, representing 61,128.0 MW, went into service. Of the projects that entered the queue process, 2,392 projects, representing 353,083.9 MW (66.7 percent of the MW) withdrew prior to completion. Such projects may create barriers to entry for projects that would otherwise be completed by taking up

<sup>1</sup> Totals presented in this section include corrections to historical data and may not match totals presented in previous reports.

<sup>2</sup> See PJM "Generator Deactivations," at <http://www.pjm.com/planning/services-requests/gen-deactivations.aspx>.

<sup>3</sup> See PJM "New Services Queue," at <https://www.pjm.com/planning/services-requests/interconnection-queues.aspx>.

queue positions, increasing interconnection costs and creating uncertainty.

## Regional Transmission Expansion Plan (RTEP)

### Backbone Facilities

- There are currently three backbone projects under development, Surry Skiffes Creek 500kV, and the conversion of the Marion-Bayonne and Bayway-Linden lines from 138 kV to 345 kV.<sup>4</sup>

### Market Efficiency Process

- PJM's first market efficiency analysis was performed in 2013, prior to Order 1000. This analysis evaluated the reasons for congestion on 25 flowgates.<sup>5</sup> The proposal window was open from August 12, 2013, through September 26, 2013. PJM received 38 proposals from six entities. One project was approved by the PJM Board.
- Through December 31, 2018, PJM has completed two market efficiency cycles under Order No. 1000. In the first cycle, PJM received 93 proposals for 57 identified sources of congestion. In the second cycle, PJM received 96 proposals for four identified sources of congestion. The proposal window for 2018/2019 opened on November 1, 2018, and will close on February 28, 2019.
- Approved market efficiency projects periodically undergo a reevaluation process to ensure that the benefit/cost ratio continues to meet the 1.25:1 threshold. The Transource AP-South project was reevaluated in September 2017, February 2018, and again in September 2018. The project exceeded the 1.25:1 threshold in all reevaluations.
- There are significant issues with PJM's benefit/cost analysis that should be addressed prior to approval of additional projects.

4 See "2017 RTEP Process Scope and Input Assumptions White Paper," at 25. <<http://www.pjm.com/-/media/library/reports-notices/2017-rtep/20170731-rtep-input-assumptions-and-scope-whitepaper.ashx?la=en>>.

5 Historical congestion drivers are identified using the historical congestion tables presented in the 2018 *State of the Market Report for PJM*, Section 11: Congestion and Marginal Losses, historical analysis of real time constraints, the NERC Book of Flowgates and PROMOD simulations.

## PJM MISO Interregional Targeted Market Efficiency Process (TMEP)

- The first Targeted Market Efficiency Process (TMEP) analysis occurred in 2017 and included the investigation of congestion on 50 market to market flowgates. The study resulted in the evaluation of 13 potential upgrades, resulting in the recommendation of five TMEP projects. The five projects address \$59 million in historical congestion, with a TMEP benefit of \$99.6 million. The projects have a total cost of \$20 million, with a 5.0 average benefit/cost ratio. PJM and MISO presented the five recommended projects to their boards in December, 2017, and both boards approved all five projects.<sup>6</sup>
- The 2018 TMEP analysis included the investigation of congestion on 61 market to market flowgates. The study resulted in the evaluation of 19 potential upgrades, resulting in the recommendation of two TMEP projects. The two projects address \$25 million in historical congestion, with a TMEP benefit of \$31.9 million. The projects have a total cost of \$4.5 million, with a 7.1 average benefit/cost ratio. PJM and MISO presented the two recommended projects to their boards in December, 2018, and both boards approved the projects.<sup>7</sup>

## Supplemental Transmission Projects

- Supplemental projects are "transmission expansions or enhancements that are not required for compliance with PJM criteria and are not state public policy projects according to the PJM Operating Agreement. These projects are used as inputs to RTEP models, but are not required for reliability, economic efficiency or operational performance criteria, as determined by PJM."<sup>8</sup> Supplemental projects are exempt from the competitive planning process.
- The average number of supplemental projects in each expected in service year increased by 520.0 percent, from 20 for years 1998 through 2007 (pre Order 890) to 124 for years 2008 through 2018 (post Order 890).

6 See PJM, "MISO PJM IPSAC" (January 12, 2018) <<http://www.pjm.com/-/media/committees-groups/stakeholder-meetings/ipsac/20180112/20180112-ipsac-presentation.ashx>>.

7 See PJM, "MISO PJM IPSAC," (January 18, 2019) <<https://www.pjm.com/-/media/committees-groups/stakeholder-meetings/ipsac/20190118/20190118-ipsac-presentation.ashx>>.

8 See PJM, "Transmission Construction Status," (January 23, 2018) <<http://www.pjm.com/planning/rtep-upgrades-status/construct-status.aspx>>.

## End of Life Transmission Projects

- An end of life transmission project is a project submitted for the purpose of replacing existing infrastructure that is at, or is approaching, the end of its useful life. End of life transmission projects fall under the Transmission Owner Form 715 Planning Criteria, and are currently exempt from the competitive planning process.<sup>9</sup> End of life transmission projects are already included in the supplemental projects totals or, if included in the transmission owners' reliability plan, will be included in the baseline project list as a reliability criteria project.
- End of life transmission projects should be subject to a transparent, robust and clearly defined mechanism to permit competition to build the project.

## Board Authorized Transmission Upgrades

- The Transmission Expansion Advisory Committee (TEAC) reviews internal and external proposals to improve transmission reliability throughout PJM. These proposals, which include reliability baseline, network, market efficiency and targeted market efficiency projects, but exclude supplemental and end of life projects, are periodically presented to the PJM Board of Managers for authorization.<sup>10</sup> In 2018, the PJM Board approved \$1.98 billion in upgrades. As of December 31, 2018, the PJM Board has approved \$37.1 billion in system enhancements since 1999

## Transmission Competition

- The MMU makes several recommendations related to the competitive transmission planning process. The recommendations include improved process transparency, incorporation of competition between transmission and generation alternatives and the removal of barriers to competition from merchant transmission. These recommendations will ensure that the process is an open and transparent process that results in the most cost effective solutions.
- On May 24, 2018, the PJM Markets and Reliability Committee (MRC) approved a motion that required

PJM, with input from the MMU, to develop a comparative framework to evaluate the quality and effectiveness of binding cost containment proposals versus proposals without cost containment provisions.

## Qualifying Transmission Upgrades (QTU)

- A Qualifying Transmission Upgrade (QTU) is an upgrade to the transmission system that increases the Capacity Emergency Transfer Limit into an LDA and can be offered into capacity auctions as capacity.
- QTU projects are submitted and tracked through the PJM queue.<sup>11</sup> A total of 51 QTU projects have entered the queue since 2007. Of the 51 submitted QTU projects, 37 projects (72.5 percent) have been withdrawn, five (10.0 percent) are in service and nine (17.5 percent) are currently in active development.

## Transmission Facility Outages

- PJM maintains a list of reportable transmission facilities. When the reportable transmission facilities need to be taken out of service, PJM transmission owners are required to report planned transmission facility outages as early as possible. PJM processes the transmission facility outage requests according to rules in PJM's Manual 3 to decide if the outage is on time or late and whether or not they will allow the outage.<sup>12</sup>
- There were 16,790 transmission outage requests submitted in the 2018/2019 planning period. Of the requested outages, 74.4 percent of the requested outages were planned for less than or equal to five days and 8.8 percent of requested outages were planned for greater than 30 days. Of the requested outages, 42.8 percent were late according to the rules in PJM's Manual 3.

<sup>9</sup> See PJM Operating Agreement Schedule 6 § 1.5.8(o).

<sup>10</sup> Supplemental Projects, including the end of life subset of supplemental projects, do not require PJM Board of Managers authorization.

<sup>11</sup> See PJM "New Services Queue," at <<https://www.pjm.com/planning/services-requests/interconnection-queues.aspx>>.

<sup>12</sup> PJM, "Manual 03: Transmission Operations," Rev. 54 (Dec. 10, 2018).

## Recommendations

The MMU recommends improvements to the planning process:

### Generation Retirements

- The MMU recommends that the question of whether Capacity Injection Rights (CIRs) should persist after the retirement of a unit, or the conversion from CP to energy only status, be addressed. The rules need to ensure that incumbents cannot exploit control of CIRs to block or postpone entry of competitors.<sup>13</sup> (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that rules be implemented to ensure that CIRs are terminated within one year if units cannot qualify to be capacity resources and, if requested, after one CP must offer exception to permit the issue of CP status to be addressed. (Priority: Low. New recommendation. Status: Not adopted.)

### Generation Queue

- The MMU recommends that barriers to entry be addressed in a timely manner in order to help ensure that the capacity market will result in the entry of new capacity to meet the needs of PJM market participants and reflect the uncertainty and resultant risks in the cost of new entry used to establish the capacity market demand curve in RPM. (Priority: Low. First reported 2012. Status: Not adopted.)
- The MMU recommends improvements in queue management including that PJM establish a review process to ensure that projects are removed from the queue if they are not viable, as well as a process to allow commercially viable projects to advance in the queue ahead of projects which have failed to make progress, subject to rules to prevent gaming. (Priority: Medium. First reported 2013. Status: Partially adopted.)
- The MMU recommends continuing analysis of the study phase of PJM's transmission planning to reduce the need for postponements of study results,

to decrease study completion times, and to improve the likelihood that a project at a given phase in the study process will successfully go into service. (Priority: Medium. First reported 2014. Status: Partially adopted.)

- The MMU recommends outsourcing interconnection studies to an independent party to avoid potential conflicts of interest. Currently, these studies are performed by incumbent transmission owners under PJM's direction. This creates potential conflicts of interest, particularly when transmission owners are vertically integrated and the owner of transmission also owns generation. (Priority: Low. First reported 2013. Status: Not adopted.)

### Market Efficiency Process

- The MMU recommends that PJM modify the rules governing benefit/cost analysis, the evaluation process for selecting among competing market efficiency projects and cost allocation for economic projects in order to ensure that all costs, including congestion costs, in all zones are included. (Priority: Medium. First reported Q3, 2018. Status: Not adopted.)
- The MMU recommends that PJM modify the rules governing the market efficiency process benefit/cost analysis so that competing projects with different in service dates are evaluated on a symmetric, comparable basis. (Priority: Medium. New recommendation. Status: Not adopted.)

### Supplemental Transmission Projects

- The MMU recommends, to increase the role of competition, that the exemption of supplemental projects from the Order No. 1000 competitive process be terminated and that the basis for all such exemptions be reviewed. (Priority: Medium. First reported 2017. Status: Not adopted.)

### Transmission Competition

- The MMU recommends that PJM enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant

<sup>13</sup> See "Comments of the Independent Market Monitor for PJM," Docket No. ER12-1177-000 (March 12, 2012) <[http://www.monitoringanalytics.com/Filings/2012/IMM\\_Comments\\_ER12-1177-000\\_20120312.PDF](http://www.monitoringanalytics.com/Filings/2012/IMM_Comments_ER12-1177-000_20120312.PDF)>.

transmission. (Priority: Medium. First reported 2015. Status: Not adopted.)

- The MMU recommends that PJM continue to incorporate the principle that the goal of transmission planning should be the incorporation of transmission investment decisions into market driven processes as much as possible. (Priority: Low. First reported 2001. Status: Not adopted.)
- The MMU recommends the creation of a mechanism to permit a direct comparison, or competition, between transmission and generation alternatives, including which alternative is less costly and who bears the risks associated with each alternative. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that PJM establish fair terms of access to rights of way and property, such as at substations, in order to remove any barriers to entry and permit competition between incumbent transmission providers and merchant transmission providers in the RTEP. (Priority: Medium. First reported 2014. Status: Not adopted.)
- The MMU recommends that rules be implemented to permit competition to provide financing for transmission projects. This competition could reduce the cost of capital for transmission projects and significantly reduce total costs to customers. (Priority: Low. First reported 2013. Status: Not adopted.)
- The MMU recommends that rules be implemented to require that project cost caps on new transmission projects be part of the evaluation of competing projects. (Priority: Medium. First reported 2015. Status: Not adopted.)

## Transmission Facility Outages

- The MMU recommends consideration of changing the minimum distribution factor in the allocation from 0.01 to 0.00 and adding a threshold minimum usage impact on the line.<sup>14</sup> (Priority: Medium. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM reevaluate all transmission outage tickets as on time or late as

if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages. (Priority: Low. First reported 2014. Status: Not adopted.)

- The MMU recommends that PJM draft a clear definition of the congestion analysis required for transmission outage requests to include in Manual 3 after appropriate review. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM modify the rules to reduce or eliminate the approval of late outage requests submitted or rescheduled after the FTR auction bidding opening date. (Priority: Low. First reported 2015. Status: Not adopted.)
- The MMU recommends that PJM not permit transmission owners to divide long duration outages into smaller segments to avoid complying with the requirements for long duration outages. (Priority: Low. First reported 2015. Status: Not adopted.)

## Conclusion

The goal of PJM market design should be to enhance competition and to ensure that competition is the driver for all the key elements of PJM markets. But transmission investments have not been fully incorporated into competitive markets. The construction of new transmission facilities has significant impacts on the energy and capacity markets. But when generating units retire or load increases, there is no market mechanism in place that would require direct competition between transmission and generation to meet loads in the affected area. In addition, despite FERC Order No. 1000, there is not yet a transparent, robust and clearly defined mechanism to permit competition to build transmission projects, to ensure that competitors provide a total project cost cap, or to obtain least cost financing through the capital markets.

The addition of a planned transmission project changes the parameters of the capacity auction for the area, changes the amount of capacity needed in the area, changes the capacity market supply and demand fundamentals in the area and may effectively forestall the ability of generation to compete. But there is no mechanism to permit a direct comparison, let alone competition, between transmission and generation alternatives. There is no mechanism to evaluate whether

<sup>14</sup> See the 2015 State of the Market Report for PJM, Section 12: Generation and Transmission Planning, at p. 463, Cost Allocation Issues.

the generation or transmission alternative is less costly, whether there is more risk associated with the generation or transmission alternatives, or who bears the risks associated with each alternative. Creating such a mechanism should be an explicit goal of PJM market design.

Managing the generation queues is a highly complex process. The PJM queue evaluation process has been substantially improved in recent years and it is more efficient and effective as a result. The PJM queue evaluation process should continue to be improved to help ensure that barriers to competition for new generation investments are not created. Issues that need to be addressed include the ownership rights to CIRs, whether transmission owners should perform interconnection studies, and improvements in queue management to ensure that projects are removed from the queue if they are not viable, as well as a process to allow commercially viable projects to advance in the queue ahead of projects which have failed to make progress.

The PJM rules for competitive transmission development through the RTEP should build upon FERC Order No. 1000 to create real competition between incumbent transmission providers and merchant transmission providers. The ability of transmission owners to block competition for supplemental projects and end of life projects and reasons for that policy should be reevaluated. PJM should enhance the transparency and queue management process for merchant transmission investment. Issues related to data access and complete explanations of cost impacts should be addressed. The goal should be to remove barriers to competition from merchant transmission. Another element of opening competition would be to consider transmission owners' ownership of property and rights of way at or around transmission substations. In many cases, the land acquired included property intended to support future expansion of the grid. Incumbents have included the costs of the property in their rate base. Because PJM now has the responsibility for planning the development of the grid under its RTEP process, property bought to facilitate future expansion should be a part of the RTEP process and be made available to all providers on equal terms.

The process for determining the reasonableness or purpose of supplemental transmission projects that are not needed for reliability, economic efficiency or operational performance as defined under the RTEP process needs additional oversight and transparency. If there is a need for a supplemental project, that need should be clearly defined and there should be a transparent, robust and clearly defined mechanism to permit competition to build the project. If there is no defined need for of a supplemental project for reliability, economic efficiency or operational performance then the project should not be included in rates.

The inclusion of market efficiency transmission projects in the transmission planning process, in addition to reliability projects, effectively results in direct competition between generation and transmission to address congestion issues in the wholesale power market, including congestion in the energy and capacity markets. The role of the market efficiency process and its impact on competition should be more thoroughly evaluated. But PJM fails to explicitly address this fact in the design of the market efficiency process. While the market efficiency process and metrics require improvement, for example to ensure that all congestion is measured, the role of the market efficiency process and its impact on competition should also be more thoroughly evaluated. Building transmission under cost of service regulation already provides a significant competitive advantage to transmission over generation which is built entirely based on market prices and for which investors take the risks. The risks of cost increases for transmission projects should be incorporated in the cost benefit analysis.

There are significant issues with PJM's benefit/cost analysis that should be addressed prior to approval of additional projects. The current benefit/cost analysis for a regional project, for example, explicitly and incorrectly ignores the increased congestion in zones that results from an RTEP project when calculating the energy market benefits. All costs should be included in all zones and LDAs.

The benefit/cost analysis should also account for the fact that the transmission project costs are not subject to cost caps and may exceed the estimated costs by a wide margin. When actual costs exceed estimated costs, the cost benefit analysis is effectively meaningless and low

estimated costs may result in inappropriately favoring transmission projects over market generation projects. The risk of cost increases for transmission projects should be incorporated in the cost benefit analysis.

The current rules governing the benefit/cost analysis evaluate competing projects with different in service dates on an asymmetric basis. Under the current rules, projects are evaluated on a present value, benefit/cost basis over a 15 year service horizon, starting with the in service date of the project. A better approach would be to establish a common end date for all evaluated competing projects so that the minimum included years for any evaluated project was 15 years. This means that if there were an RTEP year zero project and a RTEP year +2 project competing, the benefit/cost ratio analysis would include the benefits and costs for both projects for every year from RTEP year zero to RTEP+16. Under this approach all projects would be evaluated over an identical term rather than an artificially truncated term and all projects would be evaluated on a present value basis at year zero.<sup>15</sup>

There are currently no market incentives for transmission owners to submit and complete transmission outages in a timely and efficient manner. Requiring transmission owners to pay does not create an effective incentive when those payments are passed through to transmission customers. The process for the submission of planned transmission outages needs to be carefully reviewed and redesigned to limit the ability of transmission owners to submit transmission outages that are late for FTR auction bid submission dates and are late for the Day-Ahead Energy Market. The submission of late transmission outages can inappropriately affect market outcomes when market participants do not have the ability to modify market bids and offers.

## Generation Interconnection Planning

### Existing Generation Mix

Table 12-1 shows the existing PJM capacity by control zone and unit type.<sup>16</sup> As of December 31, 2018, PJM had an installed capacity of 199,489.0 MW, of which

57,891.9 MW (29.0 percent) are coal fired steam units, 46,207.1 MW (23.2 percent) are combined cycle units and 34,257.6 MW (17.2 percent) are nuclear units. This measure of installed capacity differs from capacity market installed capacity because it includes energy only units, excludes all external units, and uses nameplate values for solar and wind resources.

The AEP Zone has the most total installed capacity of any PJM zone. Of the 199,489.0 MW of PJM total installed capacity, 31,643.0 MW (15.9 percent) are in the AEP Zone, of which 14,727.8 MW (46.5 percent) are coal fired steam units, 6,990.0 MW (22.1 percent) are combined cycle units and 2,071.0 MW (6.5 percent) are nuclear units.

<sup>15</sup> See "Comments of the Independent Market Monitor for PJM," (January 11, 2019) <[http://www.monitoringanalytics.com/Filings/2019/IMM\\_Comments\\_Docket\\_No\\_ER19-80\\_20190111.pdf](http://www.monitoringanalytics.com/Filings/2019/IMM_Comments_Docket_No_ER19-80_20190111.pdf)>.

<sup>16</sup> The unit type RICE refers to Reciprocating Internal Combustion Engines.

**Table 12-1 Existing PJM capacity: December 31, 2018 (By zone and unit type (MW))<sup>17</sup>**

Zone	CT -		Hydro -		Hydro -		RICE -			Steam -					Wind	Total			
	Battery	Combined Cycle	Natural Gas	CT - Oil	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Coal	Natural Gas			Steam - Oil	Steam - Other	
AECO	0.0	901.9	544.7	0.0	26.0	1.6	0.0	0.0	0.0	0.0	4.0	10.6	59.4	613.9	0.0	0.0	0.0	7.5	2,169.5
AP	6.0	6,990.0	3,661.2	0.0	21.0	0.0	66.0	486.9	2,071.0	0.0	0.0	20.4	14.7	14,727.8	738.0	0.0	50.0	2,790.0	31,643.0
APS	80.4	2,179.0	1,223.3	0.0	2.0	0.0	0.0	129.2	0.0	0.0	29.6	18.3	55.1	5,409.0	0.0	0.0	0.0	1,191.5	10,317.4
ATSI	0.0	2,150.5	958.0	0.0	659.4	0.0	0.0	0.0	2,134.0	0.0	18.5	46.1	0.0	5,394.0	325.0	0.0	0.0	0.0	11,685.5
BGE	0.0	0.0	500.1	0.0	267.8	0.0	0.0	0.4	1,716.0	0.0	0.0	7.2	1.1	1,713.0	240.5	397.0	57.0	0.0	4,900.1
ComEd	148.5	2,621.1	6,969.3	0.0	226.2	0.0	0.0	0.0	10,473.5	0.0	0.0	38.3	9.0	4,124.1	1,326.0	0.0	0.0	3,584.9	29,520.9
DAY	0.0	0.0	1,344.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	34.0	4.5	1.1	0.0	0.0	0.0	0.0	0.0	1,384.1
DEOK	20.0	522.2	598.0	0.0	56.0	0.0	0.0	112.0	0.0	0.0	4.8	0.0	0.0	1,857.0	47.0	0.0	0.0	0.0	3,217.0
DLO	0.0	244.0	0.0	0.0	15.0	0.0	0.0	6.3	1,777.0	0.0	0.0	0.0	0.0	565.0	0.0	0.0	0.0	0.0	2,607.3
Dominion	0.0	9,099.6	3,835.3	0.0	266.4	0.0	3,003.0	586.3	3,581.3	0.0	39.0	112.8	622.3	4,705.6	351.0	1,586.0	368.4	208.0	28,365.0
DPL	0.0	1,742.5	1,298.2	0.0	478.2	30.0	0.0	0.0	0.0	0.0	88.0	14.1	213.4	410.0	882.0	153.0	0.0	0.0	5,309.4
EKPC	0.0	0.0	774.0	0.0	0.0	0.0	0.0	70.0	0.0	0.0	0.0	0.0	0.0	1,687.0	0.0	0.0	0.0	0.0	2,531.0
JCPL	20.0	2,402.5	531.1	0.0	232.0	0.4	400.0	0.0	0.0	0.0	16.1	287.4	0.0	0.0	0.0	10.0	0.0	0.0	3,899.6
Met-Ed	0.0	1,616.0	2.0	0.0	398.5	0.0	0.0	19.0	805.0	0.0	0.0	33.4	0.0	115.0	0.0	0.0	60.0	0.0	3,048.9
OVEC	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2,388.8	0.0	0.0	0.0	0.0	2,388.8
PECO	0.0	3,209.0	50.8	0.0	834.0	0.0	1,070.0	572.0	4,546.8	0.0	2.0	0.9	3.0	3.3	762.0	0.0	163.0	0.0	11,216.8
PENELEC	28.4	850.0	350.5	0.0	57.0	0.0	513.0	77.8	0.0	0.0	106.8	17.8	0.0	6,141.5	610.0	0.0	42.0	1,028.8	9,823.6
Pepco	0.0	1,710.0	764.2	0.0	308.0	0.0	0.0	0.0	0.0	0.0	11.1	0.0	2,433.0	1,164.1	0.0	52.0	0.0	0.0	6,442.4
PPL	20.0	5,558.5	252.0	0.0	150.1	0.0	0.0	706.6	2,520.0	0.0	17.0	24.7	15.0	2,642.9	2,449.0	10.0	29.0	216.5	14,611.3
PSEG	5.7	4,410.3	1,039.2	0.0	0.0	0.0	0.0	5.0	3,493.0	0.0	0.0	6.0	195.6	0.0	3.0	0.0	188.1	0.0	9,345.8
XIC	0.0	0.0	691.6	0.0	0.0	0.0	0.0	269.1	1,140.0	0.0	0.0	0.0	0.0	2,961.0	0.0	0.0	0.0	0.0	5,061.7
Total	329.0	46,207.1	25,388.0	0.0	3,997.6	32.0	5,052.0	3,040.6	34,257.6	0.0	338.9	387.0	1,477.1	57,891.9	8,897.6	2,146.0	1,019.5	9,027.2	199,489.0

Table 12-2 shows the installed capacity by state for each fuel type. Pennsylvania has the most total installed capacity of any PJM state. Of the 199,489.0 MW of installed capacity, 44,753.1 MW (22.4 percent) are in Pennsylvania, of which 9,467.7 MW (21.2 percent) are coal fired steam units, 13,656.5 MW (30.5 percent) are combined cycle units and 9,648.8 MW (21.6 percent) are nuclear units.

**Table 12-2 Existing PJM capacity: December 31, 2018 (By state and unit type (MW))**

State	CT -		Hydro -		Hydro -		RICE -			Steam -					Wind	Total			
	Battery	Combined Cycle	Natural Gas	CT - Oil	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Coal	Natural Gas			Steam - Oil	Steam - Other	
DE	0.0	742.5	325.5	0.0	116.3	30.0	0.0	0.0	0.0	0.0	8.1	0.0	410.0	882.0	0.0	0.0	0.0	0.0	2,514.4
IL	148.5	2,621.1	6,969.3	0.0	226.2	0.0	0.0	0.0	10,473.5	0.0	0.0	38.3	9.0	4,124.1	1,326.0	0.0	0.0	3,584.9	29,520.9
IN	0.0	1,835.0	441.4	0.0	0.0	0.0	0.0	8.2	0.0	0.0	3.2	10.1	3,923.8	0.0	0.0	0.0	2,023.2	8,244.9	
KY	0.0	0.0	1,618.1	0.0	0.0	0.0	0.0	136.0	0.0	0.0	0.0	0.0	0.0	1,687.0	278.0	0.0	0.0	0.0	3,719.1
MD	20.0	2,710.0	2,237.0	0.0	591.7	0.0	0.0	0.4	1,716.0	0.0	76.0	24.3	239.6	4,386.0	1,404.6	550.0	109.0	295.0	14,359.6
MI	0.0	1,200.0	0.0	0.0	4.8	0.0	0.0	11.8	2,071.0	0.0	0.0	3.2	4.6	0.0	0.0	0.0	0.0	0.0	3,295.4
NC	0.0	165.0	0.0	0.0	0.0	0.0	0.0	315.0	0.0	0.0	18.0	0.0	352.7	115.5	0.0	0.0	0.0	208.0	1,174.2
NJ	25.7	7,714.7	2,115.0	0.0	258.0	2.0	400.0	5.0	3,493.0	0.0	4.0	32.7	542.4	613.9	3.0	0.0	198.1	7.5	15,414.9
OH	24.0	6,627.7	4,201.2	0.0	731.6	0.0	0.0	200.0	2,134.0	0.0	52.5	55.4	1.1	14,083.8	372.0	0.0	0.0	766.8	29,250.1
PA	49.9	13,656.5	1,542.7	0.0	1,454.6	0.0	1,583.0	1,445.7	9,648.8	0.0	155.4	95.1	18.0	9,467.7	3,821.0	10.0	294.0	1,510.7	44,753.1
TN	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	50.0	0.0	50.0
VA	0.0	8,934.6	4,172.3	0.0	603.4	0.0	3,069.0	460.1	3,581.3	0.0	33.0	118.8	299.6	3,585.1	811.0	1,586.0	368.4	0.0	27,622.6
WV	60.9	0.0	1,073.9	0.0	11.0	0.0	0.0	189.3	0.0	0.0	8.0	0.0	0.0	12,534.0	0.0	0.0	0.0	631.1	14,508.2
XIC	0.0	0.0	691.6	0.0	0.0	0.0	0.0	269.1	1,140.0	0.0	0.0	0.0	0.0	2,961.0	0.0	0.0	0.0	0.0	5,061.7
Total	329.0	46,207.1	25,388.0	0.0	3,997.6	32.0	5,052.0	3,040.6	34,257.6	0.0	338.9	387.0	1,477.1	57,891.9	8,897.6	2,146.0	1,019.5	9,027.2	199,489.0


Table 12-3 and Figure 12-1 show the age of existing PJM generators, by unit type, as of December 31, 2018. Of the 199,489.0 MW of installed capacity, 76,587.5 MW (38.4 percent) are from units older than 40 years, of which 41,426.7 MW (54.1 percent) are coal fired steam units, 16,044.9 MW (20.9 percent) are nuclear units, and 532.0 MW (0.7 percent) are combined cycle units.

**Table 12-3 PJM capacity (MW) by unit type and age (years): December 31, 2018**

Age (years)	CT -		Hydro -		Hydro -		RICE -			Steam -					Wind	Total			
	Battery	Combined Cycle	Natural Gas	CT - Oil	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Coal	Natural Gas			Steam - Oil	Steam - Other	
Less than 20	329.0	41,231.6	20,656.2	0.0	799.0	32.0	0.0	339.2	0.0	0.0	128.4	341.6	1,477.1	3,655.0	82.0	0.0	97.4	9,027.2	78,195.6
20 to 40	0.0	4,443.5	4,029.6	0.0	217.2	0.0	3,003.0	385.2	18,212.7	0.0	37.0	45.4	0.0	12,810.2	600.0	0.0	922.1	0.0	44,705.9
40 to 60	0.0	532.0	702.2	0.0	2,981.4	0.0	2,049.0	340.0	16,044.9	0.0	173.5	0.0	0.0	37,892.4	6,901.1	2,146.0	0.0	0.0	69,762.5
Greater than 60	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,976.2	0.0	0.0	0.0	0.0	0.0	3,534.3	1,314.5	0.0	0.0	0.0	6,825.0
Total	329.0	46,207.1	25,388.0	0.0	3,997.6	32.0	5,052.0	3,040.6	34,257.6	0.0	338.9	387.0	1,477.1	57,891.9	8,897.6	2,146.0	1,019.5	9,027.2	199,489.0

<sup>17</sup> The capacity described in this section refers to all capacity in PJM at the summer installed capacity rating, regardless of whether the capacity entered the RPM Auction. This table previously included external units.

**Figure 12-1 PJM capacity (MW) by age (years):  
December 31, 2018**



## Generation Retirements<sup>18</sup>

Generating units generally plan to retire when they are not economic and do not expect to be economic. The MMU performs an analysis of the economics of all units that plan to retire in order to verify that the units are not economic and there is no potential exercise of market power through physical withholding that could advantage the owner's portfolio.<sup>19</sup> The definition of economic is that unit net revenues are greater than or equal to the unit's avoidable or going forward costs.

PJM does not have the authority to order generating plants to continue operating. PJM's responsibility is to ensure system reliability. When a unit retirement creates reliability issues based on existing and planned generation facilities and on existing and planned transmission facilities, PJM identifies transmission solutions.<sup>20</sup>

Rules that preserve the Capacity Injection Rights (CIRs) associated with retired units, and with the conversion from CP to energy only status, impose significant costs on new entrants. Currently, CIRs persist for one year if unused, and they can be further extended, at no cost, if assigned to a new project in the interconnection queue at the same point of interconnection.<sup>21</sup> There are currently no rules governing the retention of CIRs

when units want to convert to energy only status or require time to upgrade to retain CP status. The rules governing conversion or upgrades should be the same as the rules governing retired units. Reforms that require the holders of CIRs to use or lose them, and/or impose costs to holding or transferring them, could make new entry appropriately more attractive. The economic and policy rationale for extending CIRs for inactive units is not clear. Incumbent providers receive a significant advantage simply by imposing on new entrants the entire cost of system upgrades needed to accommodate new entrants. The policy question of whether CIRs should persist after the retirement of a unit should be addressed. Even if the policy treatment of such CIRs remains unchanged, the rules need to ensure that incumbents cannot exploit control of CIRs to block or postpone entry of competitors.

In May 2012, PJM stakeholders (through the Interconnection Process Senior Task Force (IPSTF)) modified the rules to reduce the length of time for which CIRs are retained by the current owner after unit retirements from three years to one.<sup>22</sup> The MMU recognized the progress made in this rule change, but it did not fully address the issues. The MMU recommends that the question of whether Capacity Injection Rights (CIRs) should persist after the retirement of a unit, or conversion from CP to energy only status, be addressed. The rules need to ensure that incumbents cannot exploit control of CIRs to block or postpone entry of competitors.<sup>23</sup>

## Generation Retirements 2011 through 2022

Table 12-4 shows that there are 44,684.1 MW of generation that have been, or are planned to be, retired between 2011 and 2022, of which 31,621.4 MW (70.8 percent) are coal fired steam units. Coal unit retirements are primarily a result of the inability of coal units to compete with efficient combined cycle units burning low cost gas.

<sup>18</sup> See PJM, "Generator Deactivations," at <<http://www.pjm.com/planning/services-requests/gen-deactivations.aspx>>.

<sup>19</sup> See OATT Section V and Attachment M-Appendix S IV.

<sup>20</sup> See PJM, "Explaining Power Plant Retirements in PJM," at <<http://learn.pjm.com/three-priorities/planning-for-the-future/explaining-power-plant-retirements.aspx>>.

<sup>21</sup> See OATT § 230.3.3.

<sup>22</sup> See PJM Interconnection, LLC, Docket No. ER12-1177 (Feb. 29, 2012).

<sup>23</sup> See "Comments of the Independent Market Monitor for PJM," Docket No. ER12-1177-000 (March 12, 2012) <[http://www.monitoringanalytics.com/Filings/2012/IMM\\_Comments\\_ER12-1177-000\\_20120312.PDF](http://www.monitoringanalytics.com/Filings/2012/IMM_Comments_ER12-1177-000_20120312.PDF)>.

Table 12-4 Summary of PJM unit retirements by unit type (MW): 2011 through 2022

	CT -					Fuel Cell	Hydro - Pumped Storage	Hydro - Run of River	RICE -				Steam - Coal	
	Battery	Combined Cycle	Natural Gas	CT - Oil	Other				Natural Gas	RICE - Oil	RICE - Other	Solar		
Retirements 2011	0.0	0.0	0.0	0.0	128.3	0.0	0.0	0.0	0.0	0.0	2.7	0.0	0.0	543.0
Retirements 2012	0.0	0.0	250.0	0.0	240.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5,907.9
Retirements 2013	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	5.9	7.0	0.0	2,589.9
Retirements 2014	0.0	0.0	136.0	0.0	422.0	0.0	0.0	0.0	0.0	0.0	0.0	15.3	0.0	2,239.0
Retirements 2015	0.0	0.0	1,319.0	0.0	858.2	0.0	0.0	0.0	0.0	0.0	10.3	0.0	0.0	7,064.8
Retirements 2016	0.0	0.0	0.0	0.0	71.0	0.0	0.5	0.0	0.0	0.0	8.0	3.9	0.0	243.0
Retirements 2017	40.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.8	0.0	2,038.0
Retirements 2018	1.0	425.0	0.0	0.0	39.6	0.0	0.0	0.0	614.5	0.0	17.2	6.9	0.0	3,166.5
Planned Retirements (November 2018 and later)	0.0	0.0	579.3	0.0	75.4	0.0	0.0	0.0	4,716.0	0.0	13.0	8.0	0.0	7,829.3
<b>Total</b>	<b>41.0</b>	<b>425.0</b>	<b>2,284.3</b>	<b>0.0</b>	<b>1,834.5</b>	<b>0.0</b>	<b>0.5</b>	<b>0.0</b>	<b>5,330.5</b>	<b>0.0</b>	<b>57.1</b>	<b>41.9</b>	<b>0.0</b>	<b>31,621.4</b>

	Steam -				Total
	Natural Gas	Steam - Oil	Steam - Other	Wind	
Retirements 2011	522.5	0.0	0.0	0.0	1,196.5
Retirements 2012	0.0	548.0	16.0	0.0	6,961.9
Retirements 2013	82.0	166.0	8.0	0.0	2,858.8
Retirements 2014	158.0	0.0	0.0	0.0	2,970.3
Retirements 2015	0.0	0.0	0.0	10.4	9,262.7
Retirements 2016	74.0	0.0	0.0	0.0	400.4
Retirements 2017	34.0	0.0	0.0	0.0	2,112.8
Retirements 2018	996.0	148.0	108.0	0.0	5,522.7
Planned Retirements (November 2018 and later)	97.0	10.0	70.0	0.0	13,398.0
<b>Total</b>	<b>1,963.5</b>	<b>872.0</b>	<b>202.0</b>	<b>10.4</b>	<b>44,684.1</b>

Table 12-5 shows the capacity, average size, and average age of units retiring in PJM, from 2011 through 2022, while Table 12-6 shows these retirements by state. Of the 44,684.1 MW of units that has been, or are planned to be, retired between 2011 and 2022, 31,621.4 MW (70.8 percent) are coal fired steam units. These coal fired steam units have an average age of 52.9 years and an average size of 195.2 MW. Over half of the retiring coal fired steam units, 58.8 percent, are located in either Ohio or Pennsylvania. Retirements have generally consisted of smaller subcritical coal fired steam units and those without adequate environmental controls to remain viable in the future.

Table 12-5 Retirements by unit type: 2011 through 2022


Unit Type	Number of Units	Avg. Size (MW)	Avg. Age at Retirement (Years)	Total	
				MW	Percent
Battery	2	20.5	7.0	41.0	0.1%
Combined Cycle	2	212.5	25.5	425.0	1.0%
Combustion Turbine	113	36.4	41.3	4,118.8	9.2%
Natural Gas	59	38.7	41.3	2,284.3	5.1%
Oil	0	0.0	0.0	0.0	0.0%
Other	54	34.0	41.2	1,834.5	4.1%
Fuel Cell	0	0.0	0.0	0.0	0.0%
Hydro	1	0.5	113.8	0.5	0.0%
Pumped Storage	1	0.5	113.8	0.5	0.0%
Run of River	0	0.0	0.0	0.0	0.0%
Nuclear	6	888.4	41.6	5,330.5	11.9%
RICE	23	4.4	29.3	99.0	0.2%
Natural Gas	0	0.0	0.0	0.0	0.0%
Oil	11	5.2	46.1	57.1	0.1%
Other	12	3.5	12.5	41.9	0.1%
Solar	0	0.0	0.0	0.0	0.0%
Steam	191	128.5	46.3	34,658.9	77.6%
Coal	162	195.2	52.9	31,621.4	70.8%
Natural Gas	17	115.5	61.7	1,963.5	4.4%
Oil	5	174.4	45.6	872.0	2.0%
Other	7	28.9	25.1	202.0	0.5%
Wind	1	10.4	15.6	10.4	0.0%
<b>Total</b>	<b>339</b>	<b>131.8</b>	<b>46.6</b>	<b>44,684.1</b>	<b>100.0%</b>

Table 12-6 Retirements (MW) by unit type and state: 2011 through 2022

State	CT -					Hydro -		RICE -				Steam -				Wind	Total		
	Battery	Combined Cycle	Natural Gas	CT - Oil	CT - Other	Fuel Cell	Pumped Storage	Hydro - Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Steam - Coal	Steam - Natural Gas			Steam - Oil	Steam - Other
DC	0.0	0.0	0.0	0.0	240.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	548.0	0.0	0.0	788.0
DE	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	254.0	34.0	0.0	0.0	0.0	288.0
IL	0.0	0.0	296.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	12.5	0.0	0.0	1,624.0	0.0	0.0	0.0	0.0	1,932.5
IN	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	982.0	0.0	0.0	0.0	0.0	982.0
KY	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	995.0	0.0	0.0	0.0	0.0	995.0
MD	0.0	0.0	347.5	0.0	105.6	0.0	0.0	0.0	0.0	0.0	3.8	0.0	0.0	635.0	171.0	0.0	0.0	0.0	1,262.9
NC	0.0	0.0	0.0	0.0	31.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	324.5	0.0	0.0	0.0	0.0	355.5
NJ	0.0	158.0	1,590.0	0.0	1,046.6	0.0	0.5	0.0	614.5	0.0	8.0	9.8	0.0	1,543.0	932.5	148.0	10.0	0.0	6,060.9
OH	40.0	0.0	0.0	0.0	286.0	0.0	0.0	0.0	2,134.0	0.0	32.3	0.9	0.0	13,892.6	0.0	0.0	0.0	0.0	16,385.8
PA	1.0	0.0	50.8	0.0	58.0	0.0	0.0	0.0	2,582.0	0.0	13.9	13.0	0.0	4,713.3	283.0	176.0	109.0	10.4	8,010.4
VA	0.0	267.0	0.0	0.0	67.3	0.0	0.0	0.0	0.0	0.0	2.9	2.0	0.0	2,739.0	543.0	0.0	83.0	0.0	3,704.2
WV	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3,919.0	0.0	0.0	0.0	0.0	3,919.0
Total	41.0	425.0	2,284.3	0.0	1,834.5	0.0	0.5	0.0	5,330.5	0.0	57.1	41.9	0.0	31,621.4	1,963.5	872.0	202.0	10.4	44,684.1

Figure 12-2 is a map of unit retirements between 2011 and 2022, with a mapping to unit names in Table 12-7.

Figure 12-2 Map of PJM unit retirements: 2011 through 2022



**Table 12-7 Unit identification for map of PJM unit retirements: 2011 through 2022**

ID	Unit	ID	Unit	ID	Unit	ID	Unit
1	AES Beaver Valley	36	Burlington 8,11	71	Eastlake 4	106	Indian River 3
2	Albright 1	37	Burlington 9	72	Eastlake 5	107	Ingenco Petersburg
3	Albright 2	38	Buzzard Point East Banks 1,2,4-8	73	Eastlake 6	108	Kammer 1-3
4	Albright 3	39	Buzzard Point West Banks 1-9	74	Eddystone 1	109	Kanawha River 1-2
5	Armstrong 1	40	Cedar 1	75	Eddystone 2	110	Kearny 10
6	Armstrong 2	41	Cedar 2	76	Edgecomb NUG (Rocky 1-2)	111	Kearny 11
7	Arnold (Green Mtn. Wind Farm)	42	Chesapeake 1-4	77	Edison 1-3	112	Kearny 9
8	Ashtabula 5	43	Chesapeake 7-10	78	Elrama 1	113	Killen 2
9	Avon Lake 7	44	Chesterfield 3	79	Elrama 2	114	Killen CT
10	BL England 1	45	Chesterfield 4	80	Elrama 3	115	Kimberly Clark Generator
11	BL England 2	46	Clinch River 3	81	Elrama 4	116	Kinsley Landfill
12	BL England 3	47	Columbia Dam Hydro	82	Essex 10-11	117	Kitty Hawk GT 1
13	BL England Diesel Units 1-4	48	Colver Power Project	83	Essex 12	118	Kitty Hawk GT 2
14	Barbados AES Battery	49	Conesville 3	84	Evergreen Power United Corstack	119	Koppers Co. IPP
15	Bay Shore 2	50	Conesville 5	85	Fairless Hills Landfill A	120	Lake Kingman
16	Bay Shore 3	51	Conesville 6	86	Fairless Hills Landfill B	121	Lake Shore 18
17	Bay Shore 4	52	Crane 1	87	Fauquier County Landfill	122	Lake Shore EMD
18	Bayonne Cogen Plant (CC)	53	Crane 2	88	Fisk Street 19	123	MH50 Markus Hook Co-gen
19	Beaver Valley U1 Nuclear Generating Unit	54	Crane GT1	89	GUDE Landfill	124	Mad River Cfs A
20	Beaver Valley U2 Nuclear Generating Unit	55	Crawford 7	90	Gilbert 1-4	125	Mad River Cfs B
21	Bellemeade	56	Crawford 8	91	Glen Gardner 1-8	126	Mansfield 1
22	Benning 15	57	Cromby 1	92	Glen Lyn 5-6	127	Mansfield 2
23	Benning 16	58	Cromby 2	93	Gould Street Generation Station	128	Mansfield 3
24	Bergen 3	59	Cromby D	94	Harrisburg 4 CT	129	McKee 1
25	Bethlehem Renewable Energy Generator (Landfill)	60	Dale 1-2	95	Hatfield's Ferry 1	130	McKee 2
26	Big Sandy 2	61	Dale 3	96	Hatfield's Ferry 2	131	Mercer 1
27	Bremo 3	62	Dale 4	97	Hatfield's Ferry 3	132	Mercer 2
28	Bremo 4	63	Davis Besse U1 Nuclear Generating Unit	98	Hopewell James River Cogeneration	133	Mercer 3
29	Brunner Island Diesels	64	Deepwater 1	99	Howard Down 10	134	Miami Fort 6
30	Brunot Island 1B	65	Deepwater 6	100	Hudson 1	135	Middle 1-3
31	Brunot Island 1C	66	Dixon Lee Landfill Generator	101	Hudson 2	136	Missouri Ave B,C,D
32	Buggs Island 1 (Mecklenberg)	67	Eastern Landfill Gas Generator	102	Hurt NUG	137	Mitchell 2
33	Buggs Island 2 (Mecklenberg)	68	Eastlake 1	103	Hutchings 1-3, 5-6	138	Mitchell 3
34	Burger 3	69	Eastlake 2	104	Hutchings 4	139	Modern Power Landfill NUG
35	Burger EMD	70	Eastlake 3	105	Indian River 1	140	Monmouth NUG landfill

ID	Unit	ID	Unit	ID	Unit
141	Montour ATG	176	R Paul Smith 4	211	Spruance NUG2 (Rich 3-4)
142	Morris Landfill Generator	177	Reichs Ford Road Landfill Generator	212	State Line 3
143	Muskingum River 1-5	178	Riverside 4	213	State Line 4
144	National Park 1	179	Riverside 6	214	Stuart 1
145	Niles 1	180	Riverside 7	215	Stuart 2
146	Niles 2	181	Riverside 8	216	Stuart 3
147	Northeastern Power NEPCO	182	Riversville 5	217	Stuart 4
148	Notch Cliff GT1	183	Riversville 6	218	Stuart Diesels 1-4
149	Notch Cliff GT2	184	Roanoke Valley 1	219	Stuart Diesels 1-4
150	Notch Cliff GT3	185	Roanoke Valley 2	220	Sunbury 1-4
151	Notch Cliff GT4	186	Rolling Hills Landfill Generator	221	Tait Battery
152	Notch Cliff GT5	187	SMART Paper	222	Tanners Creek 1-4
153	Notch Cliff GT6	188	Sammis 1-4	223	Three Mile Island Unit 1
154	Notch Cliff GT7	189	Sammis 5	224	Titus 1
155	Notch Cliff GT8	190	Sammis 6	225	Titus 2
156	Oyster Creek	191	Sammis 7	226	Titus 3
157	Pennsbury Generator Landfill 1	192	Sammis Diesel	227	Viking Energy NUG
158	Pennsbury Generator Landfill 2	193	Schuylkill 1	228	Wagner 2
159	Perry U1 Nuclear Generating Unit	194	Schuylkill Diesel	229	Walter C Beckjord 1
160	Perryman 2	195	Sewaren 1	230	Walter C Beckjord 2
161	Picway 5	196	Sewaren 2	231	Walter C Beckjord 3
162	Piney Creek NUG	197	Sewaren 3	232	Walter C Beckjord 4
163	Pleasants Power Station U1	198	Sewaren 4	233	Walter C Beckjord 5-6
164	Pleasants Power Station U2	199	Sewaren 6	234	Walter C Beckjord GT 1-4
165	Portland 1	200	Southeast Chicago CT11	235	Warren County Landfill
166	Portland 2	201	Southeast Chicago CT12	236	Warren County NUG
167	Possum Point 3	202	Southeast Chicago CT5	237	Werner 1-4
168	Possum Point 4	203	Southeast Chicago CT6	238	Westport 5
169	Potomac River 1	204	Southeast Chicago CT7	239	Will County 3
170	Potomac River 2	205	Southeast Chicago CT8	240	Willow Island 1
171	Potomac River 3	206	Southeast Chicago GT10	241	Willow Island 2
172	Potomac River 4	207	Southeast Chicago GT9	242	Winnebago Landfill
173	Potomac River 5	208	Sporn 1-4	243	Yorktown 1-2
174	Pottstown LF (Moser)	209	Sporn 5	244	Zanesville Landfill
175	R Paul Smith 3	210	Spruance NUG1 (Rich 1-2)		

## Current Year Generation Retirements

Table 12-8 shows that in 2018, 5,522.7 MW of generation retired. The largest generator that retired in 2018 was the 614.5 MW Oyster Creek Nuclear Generating Station owned by Exelon Corporation and located in the Jersey Central Power and Light (JCPL) Zone. Of the 5,522.7 MW of generation that retired, 2,364.0 MW (42.8 percent) were located in the DAY Zone.

**Table 12-8 Unit deactivations: 2018<sup>24</sup>**

Company	Unit Name	ICAP (MW)	Unit Type	Zone Name	Age (Years)	Retirement Date
Biogas Energy Solutions, LLC	Dixon Lee Landfill Generator	4.0	RICE-Other	ComEd	4.8	10-Jan-18
Rockland Capital Energy Investments, LLC	BL England 3	148.0	Steam-Oil	AECO	43.2	24-Jan-18
Riverstone Holdings LLC	Brunner Island Diesels	8.2	RICE-Oil	PPL	50.8	25-Feb-18
Dominion Resources, Inc.	Buggs Island 1 (Mecklenberg)	69.0	Steam-Coal	Dominion	25.5	09-Apr-18
Dominion Resources, Inc.	Buggs Island 2 (Mecklenberg)	69.0	Steam-Coal	Dominion	25.5	09-Apr-18
Dominion Resources, Inc.	Bellemeade	267.0	Combined Cycle	Dominion	21.2	16-Apr-18
Dominion Resources, Inc.	Bremo 3	71.0	Steam-Natural Gas	Dominion	67.9	16-Apr-18
Dominion Resources, Inc.	Bremo 4	156.0	Steam-Natural Gas	Dominion	59.7	16-Apr-18
Evergreen Community Power LLC	Evergreen Power United Corstack	25.0	Steam-Other	Met-Ed	8.7	01-May-18
Biogas Energy Solutions, LLC	Morris Landfill Generator	2.1	RICE-Other	ComEd	5.0	31-May-18
South Jersey Industries, Inc.	Reichs Ford Road Landfill Generator	1.6	CT-Other	APS	8.1	31-May-18
American Electric Power Company, Inc.	Stuart 2	150.0	Steam-Coal	DAY	47.7	01-Jun-18
American Electric Power Company, Inc.	Stuart 3	150.0	Steam-Coal	DAY	46.1	01-Jun-18
American Electric Power Company, Inc.	Stuart 4	150.0	Steam-Coal	DAY	44.0	01-Jun-18
American Electric Power Company, Inc.	Stuart Diesels 1-4	2.4	RICE-Oil	DAY	48.7	01-Jun-18
Avenue Capital Group LLC	Crane 1	190.0	Steam-Coal	BGE	57.0	01-Jun-18
Avenue Capital Group LLC	Crane 2	195.0	Steam-Coal	BGE	55.4	01-Jun-18
Avenue Capital Group LLC	Crane GT1	14.0	CT-Other	BGE	50.9	01-Jun-18
Riverstone Holdings LLC	Bayonne Cogen Plant (CC)	158.0	Combined Cycle	PSEG	29.7	01-Jun-18
The AES Corporation	Killen 2	402.0	Steam-Coal	DAY	36.0	01-Jun-18
The AES Corporation	Killen CT	18.0	CT-Other	DAY	35.2	01-Jun-18
The AES Corporation	Stuart 2	202.0	Steam-Coal	DAY	47.7	01-Jun-18
The AES Corporation	Stuart 3	202.0	Steam-Coal	DAY	46.1	01-Jun-18
The AES Corporation	Stuart 4	202.0	Steam-Coal	DAY	44.0	01-Jun-18
The AES Corporation	Stuart Diesels 1-4	3.0	RICE-Oil	DAY	48.7	01-Jun-18
Vistra Energy Corp	Killen 2	198.0	Steam-Coal	DAY	36.0	01-Jun-18
Vistra Energy Corp	Killen CT	6.0	CT-Other	DAY	35.2	01-Jun-18
Vistra Energy Corp	Stuart 2	225.0	Steam-Coal	DAY	47.7	01-Jun-18
Vistra Energy Corp	Stuart 3	225.0	Steam-Coal	DAY	46.1	01-Jun-18
Vistra Energy Corp	Stuart 4	225.0	Steam-Coal	DAY	44.0	01-Jun-18
Vistra Energy Corp	Stuart Diesels 1-4	3.6	RICE-Oil	DAY	48.7	01-Jun-18
Public Service Enterprise Group Incorporated	Sewaren 1	104.0	Steam-Natural Gas	PSEG	69.6	06-Jun-18
Public Service Enterprise Group Incorporated	Sewaren 2	118.0	Steam-Natural Gas	PSEG	69.6	06-Jun-18
Public Service Enterprise Group Incorporated	Sewaren 3	107.0	Steam-Natural Gas	PSEG	68.7	06-Jun-18
Public Service Enterprise Group Incorporated	Sewaren 4	124.0	Steam-Natural Gas	PSEG	67.0	06-Jun-18
Dominion Resources, Inc.	Hurt NUG	83.0	Steam-Other	Dominion	24.2	24-Jul-18
The AES Corporation	Barbados AES Battery	1.0	Battery	PECO	9.7	29-Jul-18
Quasar Energy Group, LLC	Zanesville Landfill	0.9	RICE-Other	AEP	6.1	08-Sep-18
Exelon Corporation	Oyster Creek Nuclear Generating Station	614.5	Nuclear	JCPL	48.8	17-Sep-18
Vistra Energy Corp	Northeastern Power NEPCO	52.0	Steam-Coal	PPL	26.2	24-Oct-18
Dominion Resources, Inc.	Chesterfield 3	97.5	Steam-Coal	Dominion	66.1	13-Dec-18
Dominion Resources, Inc.	Chesterfield 4	163.0	Steam-Coal	Dominion	58.6	13-Dec-18
Dominion Resources, Inc.	Possum Point 3	96.0	Steam-Natural Gas	Dominion	63.6	13-Dec-18
Dominion Resources, Inc.	Possum Point 4	220.0	Steam-Natural Gas	Dominion	56.7	13-Dec-18
<b>Total</b>		<b>5,522.7</b>				

<sup>24</sup> The Killen 2, Killen CT, Stuart 2, 3 and 4 and Stuart Diesels 1-4 units are jointly owned. The MW displayed in each row represents the individual company's share of the retiring unit.

## Planned Generation Retirements

Table 12-9 shows that there are 13,398.0 MW of generation that have requested retirement after December 31, 2018, of which 6,791.0 MW (50.7 percent) are located in the ATSI Zone, 7,829.3 MW (58.4 percent) are coal fired steam units and 4,716.0 MW (35.2 percent) are nuclear units. The largest generator pending retirement is the 1,240 MW Perry U1 Nuclear Generating Unit located in the ATSI Zone.

**Table 12-9 Planned retirement of PJM units: December 31, 2018**

Unit	Zone	ICAP (MW)	Unit Type	Projected Deactivation Date
Spruance NUG1 (aka Spruance 1 Rich 1-2)	Dominion	115.5	Steam-Coal	12-Jan-19
Spruance NUG2 (aka Spruance 2 Rich 3-4)	Dominion	85.0	Steam-Coal	12-Jan-19
Mansfield 1	ATSI	830.0	Steam-Coal	05-Feb-19
Mansfield 2	ATSI	830.0	Steam-Coal	05-Feb-19
Montour ATG	PPL	10.0	Steam-Oil	18-Feb-19
Yorktown 1-2	Dominion	323.0	Steam-Coal	08-Mar-19
Riverside 7	BGE	19.0	CT-Other	14-Mar-19
Hopewell James River Cogeneration	Dominion	89.0	Steam-Coal	31-Mar-19
BL England 2	AECO	155.0	Steam-Coal	30-Apr-19
Monmouth NUG landfill	JCPL	6.4	CT-Other	31-May-19
Conesville 5	AEP	400.0	Steam-Coal	01-Jun-19
Conesville 6	AEP	400.0	Steam-Coal	01-Jun-19
Warren County NUG	JCPL	10.0	Steam-Other	01-Jun-19
MH50 Markus Hook Co-gen	PECO	50.8	CT-Natural Gas	01-Jun-19
Kimberly Clark Generator	PECO	3.3	Steam-Coal	01-Aug-19
Three Mile Island Unit 1 Nuclear Generating Station	Met-Ed	805.0	Nuclear	30-Sep-19
Davis Besse U1 Nuclear Generating Unit	ATSI	894.0	Nuclear	31-May-20
Samms 1-4	ATSI	640.0	Steam-Coal	31-May-20
Notch Cliff GT1	BGE	14.0	CT-Natural Gas	01-Jun-20
Notch Cliff GT2	BGE	14.0	CT-Natural Gas	01-Jun-20
Notch Cliff GT3	BGE	14.0	CT-Natural Gas	01-Jun-20
Notch Cliff GT4	BGE	14.0	CT-Natural Gas	01-Jun-20
Notch Cliff GT5	BGE	14.6	CT-Natural Gas	01-Jun-20
Notch Cliff GT6	BGE	15.6	CT-Natural Gas	01-Jun-20
Notch Cliff GT7	BGE	14.5	CT-Natural Gas	01-Jun-20
Notch Cliff GT8	BGE	16.0	CT-Natural Gas	01-Jun-20
Westport 5	BGE	115.8	CT-Natural Gas	01-Jun-20
Riverside 8	BGE	20.0	CT-Other	01-Jun-20
Eastern Landfill Gas Generator	BGE	3.0	RICE-Other	01-Jun-20
Wagner 2	BGE	135.0	Steam-Coal	01-Jun-20
Gould Street Generation Station	BGE	97.0	Steam-Natural Gas	01-Jun-20
Southeast Chicago CT5	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago CT6	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago CT7	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago CT8	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago GT9	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago GT10	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago CT11	ComEd	37.0	CT-Natural Gas	01-Jun-20
Southeast Chicago CT12	ComEd	37.0	CT-Natural Gas	01-Jun-20
Pennsbury Generator Landfill 1	PECO	3.0	CT-Other	01-Jun-20
Pennsbury Generator Landfill 2	PECO	3.0	CT-Other	01-Jun-20
Fairless Hills Landfill A	PECO	30.0	Steam-Other	01-Jun-20
Fairless Hills Landfill B	PECO	30.0	Steam-Other	01-Jun-20
Bethlehem Renewable Energy Generator (Landfill)	PPL	5.0	RICE-Other	01-Jun-20
Colver Power Project	PENELEC	110.0	Steam-Coal	01-Sep-20
Edgecomb NUG (aka Edgecomb Rocky 1-2)	Dominion	115.5	Steam-Coal	31-Oct-20
Perry U1 Nuclear Generating Unit	ATSI	1,240.0	Nuclear	31-May-21
Beaver Valley U1 Nuclear Generating Unit	DLCO	892.0	Nuclear	31-May-21
Eastlake 6	ATSI	24.0	CT-Other	01-Jun-21
Samms Diesel	ATSI	13.0	RICE-Oil	01-Jun-21
Mansfield 3	ATSI	830.0	Steam-Coal	01-Jun-21
Beaver Valley U2 Nuclear Generating Unit	DLCO	885.0	Nuclear	31-Oct-21
Pleasants Power Station U1	APS	639.0	Steam-Coal	01-Jun-22
Pleasants Power Station U2	APS	639.0	Steam-Coal	01-Jun-22
Samms 5	ATSI	290.0	Steam-Coal	01-Jun-22
Samms 6	ATSI	600.0	Steam-Coal	01-Jun-22
Samms 7	ATSI	600.0	Steam-Coal	01-Jun-22
Total		13,398.0		

## Generation Queue

Any entity that requests interconnection of a new generating facility, including increases to the capacity of an existing generating unit, or that requests interconnection of a merchant transmission facility, must follow the process defined in the PJM tariff to obtain interconnection service.<sup>25</sup> PJM's process is designed to ensure that new generation is added in a reliable and systematic manner. The process is complex and time consuming at least in part as a result of the required analyses. The cost, time and uncertainty associated with interconnecting to the grid may create barriers to entry for potential entrants. The MMU recommends that barriers to entry be addressed in a timely manner in order to help ensure that the market will result in the entry of new capacity to meet the needs of PJM market participants.

Generation request queues are groups of proposed projects, including new units, reratings of existing units, capacity resources and energy only resources. Each queue is open for a fixed amount of time. Studies commence on all projects in a given queue when that queue closes. Queues A and B were open for a year. Queues C through T were open for six months. Starting in February 2008, Queues U through Y1 were open for three months. In May 2012, the duration of the queue period was reset to six months, starting with Queue Y2. Queue AD2 began on October 1, 2017 and closed on March 31, 2018. Queue AE1 began on April 1, 2018 and closed on September 30, 2018. Queue AF1 began on October 1, 2018 and will close on March 31, 2019.

Projects that do not meet submission requirements are removed from the queue. All projects that have entered a queue and have met the submission requirements have a status assigned. Projects listed as active are undergoing one of the studies (feasibility, system impact, facility) required to proceed. Other status options are under construction, suspended, and in service. A project cannot be suspended until it has reached the status of under construction. Any project that entered the queue before February 1, 2011, can be suspended for up to three years. Projects that entered the queue after February 1, 2011, face an additional restriction in that the suspension period is reduced to one year if they

affect any project later in the queue.<sup>26</sup> When a project is suspended, PJM extends the scheduled milestones by the duration of the suspension. If, at any time, a milestone is not met, PJM will initiate the termination of the Interconnection Service Agreement (ISA) and the corresponding cancellation costs must be paid by the customer.<sup>27</sup>

The PJM queue evaluation process has been substantially improved in recent years and it is more efficient and effective as a result.<sup>28</sup> The PJM queue evaluation process should continue to be improved to help ensure that barriers to competition from new generation investments are not created. The MMU recommends improvements in queue management including that PJM establish a review process to ensure that projects are removed from the queue if they are not viable, as well as a process to allow commercially viable projects to advance in the queue ahead of projects which have failed to make progress, subject to rules to prevent gaming.

## Process Timelines

In the study phase of the interconnection planning process, a series of studies are performed to determine the feasibility, impact, and cost of projects in the queue. Table 12-10 is an overview of PJM's study process. System impact and facilities studies are often redone when a project is withdrawn in order to determine the impact on the projects remaining in the queue.

In 2016, the PJM Earlier Queue Submitted Task Force stakeholder group made changes to the interconnection process to address some of the issues related to delays observed in the various stages of the study phase. The changes became effective with the AC2 Queue that closed on March 31, 2017. Until there has been additional time and queue processing to validate the effectiveness of these changes, the MMU recommends continuing analysis of the study phase of PJM's transmission planning to reduce the need for postponements of study results, to decrease study completion times, and to improve the likelihood that a project at a given phase in the study process will successfully go into service.

<sup>26</sup> See "PJM Manual 14C: Generation and Transmission Interconnection Process," Rev. 13 (Aug.23, 2018).

<sup>27</sup> PJM does not track the duration of suspensions or PJM termination of projects.

<sup>28</sup> See *PJM Interconnection, LLC*, Docket No. ER12-1177 (Feb. 29, 2012).

<sup>25</sup> See OATT Parts IV & VI.

**Table 12-10 PJM generation planning process**

Process Step	Start on	Financial Obligation	Days for PJM to Complete	Days for Applicant to Decide Whether to Continue
Feasibility Study	Close of current queue	Cost of study (partially refundable deposit)	90	30
System Impact Study	Upon acceptance of the System Impact Study Agreement	Cost of study (partially refundable deposit)	120	30
Facilities Study	Upon acceptance of the Facilities Study Agreement	Cost of study (refundable deposit)	Varies	60
Schedule of Work	Upon acceptance of Interconnection Service Agreement (ISA)	Letter of credit for upgrade costs	Varies	37
Construction (only for new generation)	Upon acceptance of Interconnection Construction Service Agreement (ICSA)	None	Varies	NA

## Planned Generation Additions

Expected net revenues provide incentives to build new generation to serve PJM markets. The amount of planned new generation in PJM reflects investors' perception of the incentives provided by the combination of revenues from the PJM energy, capacity and ancillary service markets. On December 31, 2018, 114,953.7 MW of capacity were in generation request queues for construction through 2029. Although it is clear that not all generation in the queues will be built, PJM has added capacity steadily since markets were implemented on April 1, 1999.<sup>29</sup>

Table 12-11 shows MW in queues by expected completion year and MW changes in the queue between December 31, 2017, and December 31, 2018, for ongoing projects, i.e. projects with the status active, under construction or suspended.<sup>30</sup> Projects that are already in service are not included here. Projects that have been withdrawn or removed from the queue are no longer included in the totals. The total MW in queues increased by 41,846.2 MW (57.2 percent) from 73,107.6 MW at the end of 2017 to 114,953.7 MW on December 31, 2018.

**Table 12-11 Queue comparison by expected completion year (MW): December 31, 2017 and December 31, 2018<sup>31</sup>**

Year	Year Change			
	As of 12/31/2017	As of 12/31/2018	MW	Percent
2008	12.0	12.0	0.0	0.0%
2009	0.0	0.0	0.0	0.0%
2010	0.0	0.0	0.0	0.0%
2011	102.5	102.5	0.0	0.0%
2012	91.2	91.2	0.0	0.0%
2013	210.5	210.5	0.0	0.0%
2014	25.0	10.0	(15.0)	(60.0%)
2015	439.9	234.1	(205.8)	(46.8%)
2016	1,879.5	725.3	(1,154.2)	(61.4%)
2017	3,975.9	2,273.5	(1,702.4)	(42.8%)
2018	12,088.2	8,218.9	(3,869.3)	(32.0%)
2019	21,910.1	24,348.3	2,438.3	11.1%
2020	22,811.9	28,623.8	5,811.8	25.5%
2021	7,100.0	26,125.7	19,025.7	268.0%
2022	2,460.9	13,756.1	11,295.2	459.0%
2023	0.0	5,715.5	5,715.5	0.0%
2024	0.0	2,106.0	2,106.0	0.0%
2025	0.0	800.1	800.1	0.0%
2026	0.0	0.0	0.0	0.0%
2027	0.0	800.1	800.1	0.0%
2028	0.0	0.0	0.0	0.0%
2029	0.0	800.1	800.1	0.0%
Total	73,107.6	114,953.7	41,846.2	57.2%

Table 12-12 shows the project status changes in more detail and how scheduled queue capacity has changed between December 31, 2017, and December 31, 2018. For example, 55,177.6 MW entered the queue in 2018. Of those 55,177.6 MW, 13,331.5 MW have been withdrawn. Of the total 71,354.4 MW marked as active on December 31, 2017, 14,480.9 MW were withdrawn, 2,214.2 MW were suspended, 868.8 MW started construction, and 514.1 MW went into service by December 31, 2018. Analysis of projects that were suspended on December

<sup>29</sup> See Monitoring Analytics, "New Generation in the PJM Capacity Market: MW and Funding Sources for Delivery Years 2007/2008 through 2018/2019," <[http://www.monitoringanalytics.com/reports/Reports/2016/New\\_Generation\\_in\\_the\\_PJM\\_Capacity\\_Market\\_20160504.pdf](http://www.monitoringanalytics.com/reports/Reports/2016/New_Generation_in_the_PJM_Capacity_Market_20160504.pdf)>.

<sup>30</sup> Expected completion dates are entered when the project enters the queue. Actual completion dates are generally different than expected completion dates.

<sup>31</sup> Wind and solar capacity in Table 12-11 through Table 12-15 have not been adjusted to reflect derating.

31, 2017 show that 3,800.5 MW came out of suspension and are now active and 20.0 MW began construction in 2018.

**Table 12-12 Change in project status (MW): December 31, 2017 to December 31, 2018**

Status as 12/31/2017	Status at 12/31/2018					
	Total at 12/31/2017	Under				
(Entered during 2018)	Active	In Service	Construction	Suspended	Withdrawn	
0.0	41,846.2	0.0	0.0	0.0	0.0	13,331.5
Active	71,354.4	53,276.4	514.1	868.8	2,214.2	14,480.9
In Service	51,676.6	0.0	51,674.7	0.0	0.0	1.9
Under Construction	18,753.2	0.0	8,819.1	9,052.6	594.6	286.9
Suspended	9,356.1	3,800.5	120.0	20.0	3,280.5	2,135.1
Withdrawn	322,847.7	0.0	0.0	0.0	0.0	322,847.7
Total	473,987.9	98,923.1	61,128.0	9,941.4	6,089.3	353,083.9

On December 31, 2018, 114,953.7 MW of capacity were in generation request queues in the status of active, suspended or under construction. Table 12-13 shows each status by unit type. Of the 98,923.1 MW in the status of Active on December 31, 2018, 36,176.1 MW (36.6 percent) were combined cycle projects. Of the 9,941.4 MW in the status of under construction, 6,810.6 MW (68.5 percent) were combined cycle projects.

**Table 12-13 Current project status (MW) by unit type: December 31, 2018**

	CT -		CT -		Fuel Cell	Hydro -		Hydro -		RICE -			Steam -					Wind	Total
	Battery	Combined Cycle	Natural Gas	Oil		Other	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Steam - Coal	Natural Gas	Steam - Oil	Steam - Other		
Active	1,063.3	36,176.1	5,151.9	14.0	0.0	0.0	1,034.0	20.5	167.5	91.9	4.0	6.8	32,699.0	99.0	94.0	0.0	40.0	22,261.1	98,923.1
Suspended	86.3	3,857.1	268.8	0.0	0.0	0.0	0.0	0.0	0.0	79.6	0.0	0.0	424.9	0.0	0.0	0.0	16.0	1,356.6	6,089.3
Under Construction	46.1	6,810.6	253.0	0.0	3.2	0.0	0.0	22.7	0.0	21.2	0.0	0.0	357.8	48.0	0.0	0.0	62.5	2,316.3	9,941.4
Total	1,195.6	46,843.8	5,673.7	14.0	3.2	0.0	1,034.0	43.2	167.5	192.7	4.0	6.8	33,481.7	147.0	94.0	0.0	118.5	25,934.0	114,953.7

A significant shift in the distribution of unit types within the PJM footprint continues to develop as natural gas fired units enter the queue and coal fired steam units retire. As of December 31, 2018, there were 52,804.2 MW of natural gas fired capacity active, suspended or under construction in PJM queues (including combined cycle units, CTs, RICE units, and natural gas fired steam units). As of December 31, 2018, there were only 147.0 MW of coal fired steam capacity active, suspended or under construction in PJM queues.

There are 7,829.3 MW of coal fired steam capacity and 676.3 MW of natural gas capacity slated for deactivation between December 31, 2018, and December 31, 2022 (See Table 12-9). The replacement of coal fired steam units by natural gas units will significantly affect future congestion, the role of firm and interruptible gas supply, and natural gas supply infrastructure.

Table 12-14 shows the amount of capacity active, in service, under construction, suspended, or withdrawn for each queue since the beginning of the RTEP process and the total amount of capacity that had been included in each queue. All items in queues A-M are either in service or have been withdrawn. As of December 31, 2018, there are 114,953.7 MW of capacity in queues that are not yet in service or withdrawn, of which 5.3 percent are suspended, 8.6 percent are under construction and 86.1 percent have not begun construction.

Table 12-14 Capacity in PJM queues (MW): December 31, 2018<sup>32</sup>

Queue	Active	In Service	Under			Withdrawn	Total
			Construction	Suspended			
A Expired 31-Jan-98	0.0	9,094.0	0.0	0.0	0.0	17,252.0	26,346.0
B Expired 31-Jan-99	0.0	4,645.5	0.0	0.0	0.0	14,956.7	19,602.2
C Expired 31-Jul-99	0.0	531.0	0.0	0.0	0.0	3,558.3	4,089.3
D Expired 31-Jan-00	0.0	850.6	0.0	0.0	0.0	7,358.0	8,208.6
E Expired 31-Jul-00	0.0	795.2	0.0	0.0	0.0	8,021.8	8,817.0
F Expired 31-Jan-01	0.0	52.0	0.0	0.0	0.0	3,092.5	3,144.5
G Expired 31-Jul-01	0.0	1,189.6	0.0	0.0	0.0	17,961.8	19,151.4
H Expired 31-Jan-02	0.0	702.5	0.0	0.0	0.0	8,421.9	9,124.4
I Expired 31-Jul-02	0.0	103.0	0.0	0.0	0.0	3,728.4	3,831.4
J Expired 31-Jan-03	0.0	42.0	0.0	0.0	0.0	846.0	888.0
K Expired 31-Jul-03	0.0	93.1	0.0	0.0	0.0	485.3	578.4
L Expired 31-Jan-04	0.0	256.5	0.0	0.0	0.0	4,033.7	4,290.2
M Expired 31-Jul-04	0.0	504.8	0.0	0.0	0.0	3,705.6	4,210.4
N Expired 31-Jan-05	0.0	2,398.8	38.0	0.0	0.0	8,090.2	10,527.0
O Expired 31-Jul-05	0.0	1,665.2	225.0	0.0	0.0	5,466.8	7,357.0
P Expired 31-Jan-06	0.0	3,037.3	253.0	0.0	0.0	5,320.5	8,610.8
Q Expired 31-Jul-06	0.0	3,147.9	0.0	0.0	0.0	11,385.7	14,533.6
R Expired 31-Jan-07	600.0	1,986.4	0.0	440.0	0.0	19,668.9	22,695.3
S Expired 31-Jul-07	70.0	3,543.5	0.0	0.0	0.0	12,396.5	16,010.0
T Expired 31-Jan-08	0.0	3,116.5	1,080.0	0.0	0.0	23,313.3	27,509.8
U1 Expired 30-Apr-08	0.0	206.9	12.0	0.0	0.0	7,937.8	8,156.7
U2 Expired 31-Jul-08	420.0	267.5	260.0	300.0	0.0	15,932.2	17,179.7
U3 Expired 31-Oct-08	100.0	333.0	20.0	0.0	0.0	2,515.6	2,968.6
U4 Expired 31-Jan-09	500.0	85.2	0.0	0.0	0.0	4,445.0	5,030.2
V1 Expired 30-Apr-09	40.0	197.9	0.0	0.0	0.0	2,532.8	2,770.7
V2 Expired 31-Jul-09	0.0	989.9	16.1	150.0	0.0	3,475.1	4,631.1
V3 Expired 31-Oct-09	200.0	912.0	0.0	20.0	0.0	3,822.7	4,954.7
V4 Expired 31-Jan-10	0.0	748.8	0.0	205.0	0.0	3,503.0	4,456.8
W1 Expired 30-Apr-10	13.5	345.9	300.0	0.0	0.0	5,139.5	5,798.9
W2 Expired 31-Jul-10	10.0	351.7	0.0	23.0	0.0	3,018.7	3,403.4
W3 Expired 31-Oct-10	371.0	490.3	57.7	100.0	0.0	8,203.1	9,222.0
W4 Expired 31-Jan-11	5.0	1,101.8	399.9	0.0	0.0	4,115.6	5,622.3
X1 Expired 30-Apr-11	0.0	1,103.8	0.0	0.0	0.0	6,200.6	7,304.4
X2 Expired 31-Jul-11	0.0	3,544.4	187.5	585.0	0.0	5,578.4	9,895.2
X3 Expired 31-Oct-11	0.0	89.2	20.0	894.0	0.0	6,771.9	7,775.1
X4 Expired 31-Jan-12	0.0	2,929.4	19.5	0.0	0.0	2,419.4	5,368.3
Y1 Expired 30-Apr-12	34.0	1,797.5	452.0	72.0	0.0	5,721.7	8,077.2
Y2 Expired 31-Oct-12	378.3	1,051.8	387.1	229.0	0.0	9,247.5	11,293.7
Y3 Expired 30-Apr-13	0.0	626.3	1,004.2	0.0	0.0	4,609.2	6,239.6
Z1 Expired 31-Oct-13	713.0	1,247.0	2,127.8	39.8	0.0	3,997.2	8,124.8
Z2 Expired 30-Apr-14	220.6	2,272.4	585.0	72.9	0.0	2,949.9	6,100.8
AA1 Expired 31-Oct-14	3,113.0	1,009.7	1,363.0	601.1	0.0	5,911.9	11,998.7
AA2 Expired 30-Apr-15	5,011.2	496.9	614.7	790.0	0.0	9,153.5	16,066.3
AB1 Expired 31-Oct-15	9,397.0	846.5	243.8	221.3	0.0	9,744.0	20,452.6
AB2 Expired 31-Mar-16	8,974.7	122.5	55.0	118.6	0.0	5,946.6	15,217.4
AC1 Expired 30-Sep-16	11,990.3	103.2	219.5	1,203.7	0.0	6,558.9	20,075.6
AC2 Expired 30-Apr-17	5,186.6	80.0	0.6	23.9	0.0	7,330.6	12,621.6
AD1 Expired 30-Sep-17	9,085.0	21.2	0.0	0.0	0.0	2,354.9	11,461.1
AD2 Expired 31-Mar-18	12,589.6	0.0	0.0	0.0	0.0	7,880.9	20,470.5
AE1 Expired 30-Sep-18	26,683.9	0.0	0.0	0.0	0.0	6,942.0	33,625.9
AE2 Through 31-Mar-19	3,216.3	0.0	0.0	0.0	0.0	60.0	3,276.3
Total	98,923.1	61,128.0	9,941.4	6,089.3	353,083.9	529,165.5	

Table 12-15 shows the projects with a status of active, suspended or under construction, by unit type, and control zone. As of December 31, 2018, 114,953.7 MW of capacity were in generation request queues for construction through 2029.<sup>33</sup> Table 12-15 also shows the planned retirements for each zone.

<sup>32</sup> Projects listed as partially in service are counted as in service for the purposes of this analysis.

<sup>33</sup> Since wind resources cannot be dispatched on demand, PJM rules previously required that the unforced capacity of wind resources be derated to 20 percent of nameplate capacity until actual generation data are available. Beginning with Queue U, PJM derated wind resources to 13 percent of nameplate capacity until there is operational data to support a different conclusion. PJM derated solar resources to 38 percent of nameplate capacity. Effective June 1, 2017, PJM adjusted the derates of wind and solar resources. The capacity factor derates for wind resources are dependent on the wind farm locations and have an average derate of 16.2 percent. The capacity factor derates for solar resources are dependent on the solar installation type and have an average derate of 46.7 percent. Based on the derating of 25,934.0 MW of wind resources and 33,481.7 MW of solar resources, using the average derate factors, the 114,953.7 MW currently under construction, suspended or active in the queue would be reduced to 74,545.4 MW.

**Table 12-15 Queue totals for projects (active, suspended and under construction) by LDA, control zone and unit type (MW): December 31, 2018<sup>34</sup>**

LDA	Zone	Battery	CT -				Hydro -			RICE -			Steam -				Wind	Total Queue Capacity	Planned Retirements		
			Natural	CC	Gas	Oil	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural	RICE - Gas	RICE - Oil	Solar	Coal	Natural Gas				Oil	Other
EMAAC	AECO	100.0	1,448.6	388.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	521.0	2,769.1	155.0
	DPL	21.0	451.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6.0	1,442.2	0.0	0.0	0.0	0.0	599.8	2,520.0	0.0
	JCPL	154.9	1,175.0	200.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	177.7	0.0	0.0	0.0	0.0	3,016.0	4,723.5	16.4
	PECO	0.0	982.0	29.0	0.0	0.0	0.0	0.0	0.0	94.0	0.0	4.0	0.0	18.0	0.0	0.0	0.0	0.0	0.0	1,127.0	120.1
	PSEG	2.0	3,710.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	92.3	0.0	0.0	0.0	0.0	0.0	3,804.8	0.0
	RECO	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	0.0	60.0	0.0
	EMAAC Total	277.8	7,767.1	617.0	0.0	0.0	0.0	0.0	0.0	94.0	0.0	4.0	6.0	2,101.6	0.0	0.0	0.0	0.0	4,136.8	15,004.3	291.5
SWMAAC	BGE	0.1	0.0	153.6	14.0	0.0	0.0	0.0	0.0	45.5	1.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	214.5	506.5
	Pepeco	0.0	1,197.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	176.5	0.0	0.0	0.0	0.0	0.0	1,373.6	0.0
	SWMAAC Total	0.1	1,197.1	153.6	14.0	0.0	0.0	0.0	0.0	45.5	1.3	0.0	0.0	176.5	0.0	0.0	0.0	0.0	0.0	1,588.1	506.5
WMAAC	Met-Ed	0.0	598.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	544.6	0.0	0.0	0.0	0.0	0.0	1,143.5	805.0
	PENELEC	0.0	1,348.0	549.8	0.0	0.0	0.0	0.0	0.0	119.6	0.0	0.0	0.0	458.8	0.0	0.0	0.0	0.0	290.3	2,766.5	110.0
	PPL	238.8	2,205.8	0.0	0.0	0.0	0.0	1,000.0	0.0	0.0	0.0	0.0	0.0	174.6	0.0	0.0	0.0	16.0	355.3	3,990.5	15.0
	WMAAC Total	238.8	4,152.7	549.8	0.0	0.0	0.0	1,000.0	0.0	0.0	119.6	0.0	0.0	1,178.0	0.0	0.0	0.0	16.0	645.6	7,900.5	930.0
Non-MAAC	AEP	226.0	8,016.0	1,491.0	0.0	3.2	0.0	34.0	0.0	28.0	12.0	0.0	0.8	7,776.9	101.0	30.0	0.0	40.0	6,689.3	24,448.2	800.0
	APS	145.5	7,595.7	120.0	0.0	0.0	0.0	0.0	15.0	0.0	59.8	0.0	0.0	1,360.7	0.0	0.0	0.0	0.0	1,102.4	10,399.1	1,278.0
	ATSI	8.8	5,805.0	70.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	999.1	0.0	0.0	0.0	0.0	816.1	7,698.9	6,791.0
	ComEd	158.9	6,709.2	1,238.0	0.0	0.0	0.0	0.0	22.7	0.0	0.0	0.0	0.0	2,618.5	0.0	64.0	0.0	0.0	9,322.7	20,134.0	296.0
	DAY	19.9	1,150.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,136.5	12.0	0.0	0.0	0.0	100.0	2,418.4	0.0
	DEOK	19.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	380.0	20.0	0.0	0.0	0.0	0.0	419.8	0.0
	DLCO	20.0	0.0	205.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	20.0	0.0	0.0	0.0	0.0	0.0	245.0	1,777.0
	Dominion	80.0	4,451.0	1,156.3	0.0	0.0	0.0	0.0	5.5	0.0	0.0	0.0	0.0	14,748.0	14.0	0.0	0.0	62.5	3,121.2	23,638.5	728.0
	EKPC	0.0	0.0	73.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	986.0	0.0	0.0	0.0	0.0	0.0	1,059.0	0.0
	OVEC	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	RMU	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Non-MAAC Total	678.9	33,726.9	4,353.3	0.0	3.2	0.0	34.0	43.2	28.0	71.8	0.0	0.8	30,025.7	147.0	94.0	0.0	102.5	21,151.6	90,460.8	11,670.0
	Total	1,195.6	46,843.8	5,673.7	14.0	3.2	0.0	1,034.0	43.2	167.5	192.7	4.0	6.8	33,481.7	147.0	94.0	0.0	118.5	25,934.0	114,953.7	13,398.0

### Withdrawn Projects

The queue contains a substantial number of projects that are not likely to be built. The queue process results in a substantial number of projects that are withdrawn. Manual 14B requires PJM to apply a commercial probability factor at the feasibility study stage to improve the accuracy of capacity and cost estimates. The commercial probability factor is based on the historical incidence of projects dropping out of the queue at the impact study stage, but the actual calculation of commercial probability factors is less than transparent.<sup>35</sup> The impact and facilities studies are performed using the full amount of planned generation in the queues. The actual withdrawal rates are shown in Table 12-16 and Table 12-17.

Table 12-16 shows the milestone status when projects were withdrawn, for all withdrawn projects. Of the 2,392 projects withdrawn, 1,164 (48.7 percent) were withdrawn before the system impact study was completed. Once a Construction Service Agreement (CSA) is executed, the financial obligation for any necessary transmission upgrades cannot be retracted. Of the 2,392 projects withdrawn, 463 (19.4 percent) were withdrawn after the completion of a Construction Service Agreement.

**Table 12-16 Last milestone at time of withdrawal: January 1997 through December 2018**

Milestone Completed	Projects		Average Days	Maximum Days
	Withdrawn	Percent		
Never Started	397	16.6%	95	875
Feasibility Study	767	32.1%	274	1,633
System Impact Study	485	20.3%	752	3,248
Facilities Study	280	11.7%	1,072	3,454
Construction Service Agreement (CSA) or beyond	463	19.4%	1,266	4,249
Total	2,392	100.0%		

<sup>34</sup> This data includes only projects with a status of active, under construction, or suspended.  
<sup>35</sup> See PJM, "Manual 14B: PJM Region Transmission Planning Process," Rev. 42 (Aug. 23, 2018).

## Average Time in Queue

Table 12-17 shows the time spent at various stages in the queue process and the completion time for the studies performed. For completed projects, there is an average time of 1,017 days, or 2.8 years, between entering a queue and going into service. For withdrawn projects, there is an average time of 617 days, or 1.7 years, between entering a queue and withdrawing.

**Table 12-17 Project queue times by status (days): December 31, 2018<sup>36</sup>**

Status	Average (Days)	Standard Deviation	Minimum	Maximum
Active	501	609	0	4,211
In-Service	1,017	728	0	4,024
Suspended	1,500	905	366	4,177
Under Construction	1,820	1,073	486	4,933
Withdrawn	617	689	0	4,249

Table 12-18 presents information on the time in the stages of the queue for those projects not yet in service or already withdrawn. Of the 936 projects in the queue as of December 31, 2018, 214 (22.9 percent) had a completed feasibility study and 205 (21.9 percent) were under construction.

**Table 12-18 Project queue times by milestone (days): December 31, 2018**

Milestone Reached	Number of Projects	Percent of Total Projects	Average Days	Maximum Days
Under Review	244	26.1%	142	460
Feasibility Study	214	22.9%	481	1,439
System Impact Study	162	17.3%	868	3,662
Facilities Study	43	4.6%	1,188	3,746
Construction Service Agreement (CSA) or beyond	273	29.2%	1,592	5,208
Total	936	100.0%		

## Completion Rates

The probability of a project going into service increases as each step of the planning process is completed. Table 12-19 shows the historic completion rates (MW energy) by unit type for projects that have completed the system impact study, facilities study and construction service agreement stages. For example, of all wind projects to ever enter the queue and complete the system impact study stage, 16.0 percent of the queued MW have gone into service. The completion rate for wind projects increases to 31.0 percent when wind projects complete the facility study agreement, and further increases to 48.0

percent when wind projects complete the construction service agreement.

**Table 12-19 Historic completion rates (MW energy) by unit type for projects with a completed SIS, FSA and CSA: January 1997 through December 2018**

Unit Type	Completion Rate (SIS)	Completion Rate (FSA)	Completion Rate (CSA)
Battery	22.5%	45.0%	53.5%
CC	29.7%	49.4%	83.5%
CT - Natural Gas	82.0%	85.0%	89.6%
CT - Oil	35.6%	60.2%	90.8%
CT - Other	12.3%	18.7%	29.6%
Fuel Cell	0.0%	0.0%	0.0%
Hydro - Pumped Storage	100.0%	100.0%	100.0%
Hydro - Run of River	40.0%	55.7%	61.1%
Nuclear	34.8%	41.7%	51.1%
RICE - Natural Gas	34.7%	50.5%	59.1%
RICE - Oil	30.6%	55.9%	55.9%
RICE - Other	90.0%	91.7%	92.5%
Solar	15.0%	28.1%	35.8%
Steam - Coal	12.9%	24.2%	35.9%
Steam - Natural Gas	90.1%	90.1%	90.1%
Steam - Oil	0.0%	0.0%	0.0%
Steam - Other	27.9%	37.2%	45.2%
Wind	16.0%	31.0%	48.0%

## Queue Analysis by Fuel Group

The time it takes to complete a study depends on the backlog and the number of projects in the queue, but not on the size of the project. Table 12-20 shows the number of projects that entered the queue by year and by fuel group. The fuel groups are nuclear units, renewable units (including solar, hydro, storage, biomass and wind) and traditional units (all other fuels). The number of queue entries has increased during the past several years, primarily by renewable projects. Of the 1,492 projects entered in 2015, 2016, 2017 and 2018, 1,196 projects, 80.2 percent, were renewable. Of the 429 projects entered in 2018, 380 projects, 88.6 percent, were renewable.

<sup>36</sup> The queue data shows that some projects were withdrawn and a withdrawal date was not identified. These projects were removed for the purposes of this analysis.

**Table 12-20 Number of projects entered in the queue: December 31, 2018**

Year Entered	Fuel Group			Total
	Nuclear	Renewable	Traditional	
1997	2	0	11	13
1998	0	0	18	18
1999	1	5	84	90
2000	2	3	78	83
2001	4	6	81	91
2002	3	15	33	51
2003	1	34	18	53
2004	4	17	33	54
2005	3	75	55	133
2006	9	67	81	157
2007	9	65	145	219
2008	3	109	104	216
2009	10	109	54	173
2010	5	375	61	441
2011	6	268	81	355
2012	2	70	87	159
2013	1	75	78	154
2014	0	121	71	192
2015	0	196	113	309
2016	2	320	77	399
2017	2	300	53	355
2018	1	380	48	429
Total	70	2,610	1,464	4,144

Renewable projects comprise the majority of projects entered in the queue, as well as what is currently active in the queue. Renewable projects make up 53.7 percent of the nameplate MW currently active, suspended or under construction in the queue (Table 12-21).

**Table 12-21 Queue details by fuel group: December 31, 2018**

Fuel Group	Number of Projects	Percent of Projects	MW	
			MW	Percent MW
Nuclear	9	1.0%	167.5	0.1%
Renewable	734	78.4%	61,688.6	53.7%
Traditional	193	20.6%	53,097.7	46.2%
Total	936	100.0%	114,953.7	100.0%

## Queue Analysis by Unit Type and Project Classification

Table 12-22 shows the current status of all generation queue projects by unit type and project classification from January 1, 1997, through December 31, 2018. As of December 31, 2018, 4,144 projects, representing 529,165.5 MW, have entered the queue process since its inception. Of those, 816 projects, representing 61,128.0 MW, went into service. Of the projects that entered the queue process, 2,392 projects, representing 353,083.9 MW (66.7 percent of the MW) withdrew prior to completion. Such projects may create barriers to entry for projects that would otherwise be completed by

taking up queue positions, increasing interconnection costs and creating uncertainty.

A total of 3,375 projects have been classified as new generation and 769 projects have been classified as upgrades. Wind, solar and natural gas projects have accounted for 3,290 projects, or 79.4 percent, of all 4,144 generation queue projects.

**Table 12-22 Status of all generation queue projects: January 1997 through December 2018**

Project Status	Project Classification	Number of Projects																		Total
		CT -						Hydro -		Hydro -		RICE -				Steam -				
		Battery	CC	Natural Gas	Oil	Other	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Steam - Coal	Natural Gas	Steam - Oil	Steam - Other	Wind	
In Service	New Generation	19	54	48	10	24	3	0	11	2	8	0	55	130	8	5	0	3	78	458
	Upgrade	4	75	90	15	5	0	2	16	41	8	1	14	16	51	7	0	7	6	358
Under Construction	New Generation	23	8	1	0	1	0	0	2	0	2	0	0	19	0	0	0	0	12	68
	Upgrade	1	13	2	0	0	0	0	0	0	0	0	1	3	2	0	0	1	3	26
Suspended	New Generation	7	5	3	0	0	0	0	0	0	4	0	0	32	0	0	0	1	10	62
	Upgrade	3	5	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	10
Withdrawn	New Generation	101	406	16	9	81	27	1	39	9	20	12	15	951	55	1	0	34	404	2,181
	Upgrade	14	83	5	13	13	2	0	4	9	0	2	2	28	14	0	0	2	20	211
Active	New Generation	27	39	14	1	0	0	2	1	1	5	0	1	438	0	0	0	0	77	606
	Upgrade	10	41	29	0	0	0	1	2	8	1	1	2	40	5	3	0	1	20	164
Total Projects	New Generation	177	512	82	20	106	30	3	53	12	39	12	71	1,570	63	6	0	38	581	3,375
	Upgrade	32	217	127	28	18	2	3	22	58	9	4	19	87	72	10	0	11	50	769

Table 12-23 shows the totals in Table 12-22 by share of classification as new generation or upgrade. Within a unit type the shares of upgrades add to 100 percent and the shares of new generation add to 100 percent. For example, 72.7 percent of all hydro run of river projects classified as upgrades are currently in service in PJM, 18.2 percent of hydro run of river upgrades were withdrawn and 9.1 percent of hydro run of river upgrades are active in the queue.

**Table 12-23 Status of all generation queue projects as a percent of total projects by classification: January 1997 through December 2018**

Project Status	Project Classification	Percent of Projects																		Total
		CT -						Hydro -		Hydro -		RICE -				Steam -				
		Battery	CC	Natural Gas	Oil	Other	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Steam - Coal	Natural Gas	Steam - Oil	Steam - Other	Wind	
In Service	New Generation	10.7%	10.5%	58.5%	50.0%	22.6%	10.0%	0.0%	20.8%	16.7%	20.5%	0.0%	77.5%	8.3%	12.7%	83.3%	0.0%	7.9%	13.4%	13.6%
	Upgrade	12.5%	34.6%	70.9%	53.6%	27.8%	0.0%	66.7%	72.7%	70.7%	88.9%	25.0%	73.7%	18.4%	70.8%	70.0%	0.0%	63.6%	12.0%	46.6%
Under Construction	New Generation	13.0%	1.6%	1.2%	0.0%	0.9%	0.0%	0.0%	3.8%	0.0%	5.1%	0.0%	0.0%	1.2%	0.0%	0.0%	0.0%	0.0%	2.1%	2.0%
	Upgrade	3.1%	6.0%	1.6%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	5.3%	3.4%	2.8%	0.0%	0.0%	9.1%	6.0%	3.4%
Suspended	New Generation	4.0%	1.0%	3.7%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	10.3%	0.0%	0.0%	2.0%	0.0%	0.0%	0.0%	2.6%	1.7%	1.8%
	Upgrade	9.4%	2.3%	0.8%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	2.0%	1.3%
Withdrawn	New Generation	57.1%	79.3%	19.5%	45.0%	76.4%	90.0%	33.3%	73.6%	75.0%	51.3%	100.0%	21.1%	60.6%	87.3%	16.7%	0.0%	89.5%	69.5%	64.6%
	Upgrade	43.8%	38.2%	3.9%	46.4%	72.2%	100.0%	0.0%	18.2%	15.5%	0.0%	50.0%	10.5%	32.2%	19.4%	0.0%	0.0%	18.2%	40.0%	27.4%
Active	New Generation	15.3%	7.6%	17.1%	5.0%	0.0%	0.0%	66.7%	1.9%	8.3%	12.8%	0.0%	1.4%	27.9%	0.0%	0.0%	0.0%	0.0%	13.3%	18.0%
	Upgrade	31.3%	18.9%	22.8%	0.0%	0.0%	0.0%	33.3%	9.1%	13.8%	11.1%	25.0%	10.5%	46.0%	6.9%	30.0%	0.0%	9.1%	40.0%	21.3%

Table 12-24 shows the nameplate generating capacity of projects in the PJM generation queue by technology type and project classification. For example, the 404 new generation wind projects that have been withdrawn from the queue as of December 31, 2018, (as shown in Table 12-22) constitute 66,353.2 MW of nameplate capacity. The 489 new generation and upgrade combined cycle projects that have been withdrawn in the same time period constitute 205,440.3 MW of nameplate capacity.

**Table 12-24 Status of all generation capacity (MW) in the PJM generation queue: January 1997 through December 2018**

Project Status	Project Classification	Project MW																		Total
		CT -						Hydro -		Hydro -		RICE -				Steam -				
		Battery	CC	Natural Gas	Oil	Other	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	RICE - Oil	RICE - Other	Solar	Steam - Coal	Natural Gas	Steam - Oil	Steam - Other	Wind	
In Service	New Generation	195.4	27,270.0	6,600.5	676.5	148.2	1.9	0.0	471.5	1,639.0	118.2	0.0	440.1	1,399.2	1,343.0	723.0	0.0	60.0	7,562.2	48,648.7
	Upgrade	42.4	5,231.8	2,323.5	127.8	12.3	0.0	356.0	373.6	2,282.8	15.7	23.3	49.9	19.4	883.5	131.5	0.0	605.3	0.5	12,479.3
Under Construction	New Generation	46.1	5,910.5	205.0	0.0	3.2	0.0	0.0	22.7	0.0	21.2	0.0	0.0	343.9	0.0	0.0	0.0	0.0	2,096.8	8,649.4
	Upgrade	0.0	900.1	48.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	13.9	48.0	0.0	0.0	62.5	219.5	1,292.0
Suspended	New Generation	43.3	3,222.0	68.8	0.0	0.0	0.0	0.0	0.0	0.0	79.6	0.0	0.0	424.9	0.0	0.0	0.0	16.0	1,340.3	5,194.9
	Upgrade	43.0	635.1	200.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	16.3	894.4
Withdrawn	New Generation	1,273.7	195,211.1	1,577.5	1,721.0	1,244.2	5.7	0.0	1,986.9	8,161.0	328.3	63.9	86.6	25,863.9	33,511.6	27.0	0.0	1,035.8	66,353.2	338,451.3
	Upgrade	301.1	10,229.3	273.5	589.0	72.5	0.9	0.0	57.1	916.0	0.0	13.0	6.0	835.1	865.0	0.0	0.0	37.1	437.0	14,632.6
Active	New Generation	842.3	31,299.3	3,692.9	14.0	0.0	0.0	1,000.0	15.0	28.0	90.3	0.0	2.0	31,255.8	0.0	0.0	0.0	0.0	20,645.6	88,885.2
	Upgrade	221.0	4,876.8	1,459.0	0.0	0.0	0.0	34.0	5.5	139.5	1.6	4.0	4.8	1,443.3	99.0	94.0	0.0	40.0	1,615.5	10,037.9
Total Projects	New Generation	2,400.7	262,912.9	12,144.7	2,411.5	1,395.6	7.6	1,000.0	2,496.1	9,828.0	637.6	63.9	528.7	59,287.6	34,854.6	750.0	0.0	1,111.8	97,998.1	489,829.4
	Upgrade	607.5	21,873.1	4,304.0	716.8	84.8	0.9	390.0	436.2	3,338.3	17.3	40.3	60.7	2,311.7	1,895.5	225.5	0.0	744.9	2,288.8	39,336.2

Table 12-25 shows the MW totals in Table 12-24 by share by classification as new generation or upgrade. Within a unit type the shares of upgrades add to 100 percent and the shares of new generation add to 100 percent. For example, 67.7 percent of wind project MW classified as new generation have been withdrawn from the queue between January 1, 1997, and December 31, 2018.

**Table 12-25 Status of all generation queue projects as percent of total MW in project classification: January 1997 through December 2018**

Project Status	Project Classification	Percent of Total Projects by Classification																		Total
		CT -		Hydro -		Hydro -		RICE -		RICE -		RICE -		Steam -		Steam -		Wind		
		Battery	CC	Natural Gas	Oil	Other	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	Oil	Other	Solar	Coal	Natural Gas	Oil		Other	
In Service	New Generation	8.1%	10.4%	54.3%	28.1%	10.6%	25.5%	0.0%	18.9%	16.7%	18.5%	0.0%	83.2%	2.4%	3.9%	96.4%	0.0%	5.4%	7.7%	9.9%
	Upgrade	7.0%	23.9%	54.0%	17.8%	14.5%	0.0%	91.3%	85.6%	68.4%	90.8%	57.8%	82.2%	0.8%	46.6%	58.3%	0.0%	81.3%	0.0%	31.7%
Under Construction	New Generation	1.9%	2.2%	1.7%	0.0%	0.2%	0.0%	0.0%	0.9%	0.0%	3.3%	0.0%	0.0%	0.6%	0.0%	0.0%	0.0%	0.0%	2.1%	1.8%
	Upgrade	0.0%	4.1%	1.1%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.6%	2.5%	0.0%	0.0%	8.4%	9.6%	3.3%
Suspended	New Generation	1.8%	1.2%	0.6%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	12.5%	0.0%	0.0%	0.7%	0.0%	0.0%	0.0%	1.4%	1.4%	1.1%
	Upgrade	7.1%	2.9%	4.6%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.7%	2.3%
Withdrawn	New Generation	53.1%	74.2%	13.0%	71.4%	89.2%	74.5%	0.0%	79.6%	83.0%	51.5%	100.0%	16.4%	43.6%	96.1%	3.6%	0.0%	93.2%	67.7%	69.1%
	Upgrade	49.6%	46.8%	6.4%	82.2%	85.5%	100.0%	0.0%	13.1%	27.4%	0.0%	32.3%	9.9%	36.1%	45.6%	0.0%	0.0%	5.0%	19.1%	37.2%
Active	New Generation	35.1%	11.9%	30.4%	0.6%	0.0%	0.0%	100.0%	0.6%	0.3%	14.2%	0.0%	0.4%	52.7%	0.0%	0.0%	0.0%	0.0%	21.1%	18.1%
	Upgrade	36.4%	22.3%	33.9%	0.0%	0.0%	0.0%	8.7%	1.3%	4.2%	9.2%	9.9%	7.9%	62.4%	5.2%	41.7%	0.0%	5.4%	70.6%	25.5%

Table 12-26 shows the project MW that entered the PJM generation queue by unit type and year of entry. Since 2016, 93.1 percent of all new projects entering the generation queue have been either combined cycle (29.3 percent), wind (20.6 percent) or solar projects (43.2 percent).

**Table 12-26 Queue project MW by unit type and queue entry year: January 1997 through December 2018**

Year	Battery	CC	CT -		Hydro -		Hydro -		RICE -		RICE -		RICE -		Steam -		Steam -		Wind	Total
			Natural Gas	Oil	Other	Fuel Cell	Pumped Storage	Run of River	Nuclear	Natural Gas	Oil	Other	Solar	Coal	Natural Gas	Oil	Other			
			1997	0.0	4,148.0	321.0	315.0	0.0	0.0	0.0	0.0	50.0	0.0	0.0	0.0	0.0	0.0	6.0	0.0	0.0
1998	0.0	7,006.0	1,775.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	8,781.0
1999	0.0	29,412.7	2,412.1	0.0	10.0	0.0	0.0	196.0	45.0	0.0	0.0	0.0	0.0	47.0	0.0	0.0	525.0	115.4	32,763.2	
2000	0.0	21,144.8	493.6	31.5	8.8	0.0	0.0	0.0	95.0	0.0	0.0	1.2	0.0	37.0	2.5	0.0	0.0	95.6	21,909.9	
2001	0.0	25,411.7	264.0	0.0	0.0	0.0	0.0	107.0	90.0	0.0	0.0	15.6	0.0	1,244.6	10.0	0.0	0.0	252.9	27,395.8	
2002	0.0	4,154.0	11.7	0.0	70.5	0.0	0.0	293.0	236.0	8.0	23.3	4.5	0.0	1,895.0	0.0	0.0	0.0	790.9	7,486.9	
2003	0.0	2,361.4	10.0	8.0	0.8	0.0	0.0	2.0	0.0	29.0	0.0	27.5	0.0	522.0	0.0	0.0	165.0	997.0	4,122.7	
2004	0.0	3,610.0	43.3	20.0	49.1	0.0	0.0	0.0	1,911.0	0.0	35.5	17.5	0.0	1,187.0	0.0	0.0	0.0	1,613.7	8,487.1	
2005	0.0	5,824.6	961.0	281.0	51.4	0.0	340.0	174.2	242.0	21.5	0.0	65.1	0.0	6,360.0	0.0	0.0	24.0	6,020.0	20,364.9	
2006	0.0	4,188.1	454.3	607.5	73.1	0.0	0.0	159.0	6,894.0	0.0	0.0	93.0	0.0	9,586.0	0.0	0.0	258.5	7,650.7	29,964.2	
2007	0.0	13,944.6	941.2	215.9	149.5	0.0	16.0	255.4	368.0	0.0	0.0	56.5	3.3	9,078.0	190.0	0.0	50.5	18,525.6	43,794.4	
2008	121.0	26,001.0	129.7	1,113.0	488.8	0.0	0.0	1,254.5	105.0	6.0	0.0	32.0	66.3	1,198.0	0.0	0.0	192.3	11,199.7	41,907.3	
2009	34.0	5,548.4	14.0	66.0	214.2	0.0	0.0	133.9	1,933.8	4.5	16.0	15.2	636.5	1,273.0	5.5	0.0	148.0	6,672.6	16,715.6	
2010	72.4	9,185.4	176.0	7.9	117.3	0.0	0.0	132.6	426.0	0.0	2.4	57.8	3,690.0	64.0	0.0	0.0	173.5	9,940.4	24,045.7	
2011	24.1	20,354.5	29.5	0.0	174.6	0.0	0.0	30.0	182.0	0.0	14.0	75.3	2,022.9	357.0	0.0	0.0	49.0	5,576.4	28,889.3	
2012	142.6	18,014.8	282.1	42.5	48.4	0.0	0.0	11.8	369.0	37.2	0.0	4.0	286.6	1,837.0	0.0	0.0	143.1	1,529.8	22,748.8	
2013	217.4	11,168.1	526.8	5.0	11.2	0.0	0.0	89.4	102.0	59.7	0.0	1.6	231.7	158.0	40.0	0.0	44.7	1,407.9	14,063.4	
2014	246.9	11,704.5	1,532.5	401.0	7.7	0.0	0.0	60.5	0.0	48.0	0.0	17.7	1,445.7	1,730.5	27.0	0.0	43.1	1,763.7	19,028.8	
2015	546.9	27,540.8	1,324.5	0.0	0.9	2.3	34.0	0.0	0.0	320.4	13.0	31.4	2,931.6	47.0	606.5	0.0	0.0	2,160.6	35,559.7	
2016	111.1	18,804.5	1,392.0	0.0	0.0	3.4	0.0	12.5	50.3	23.5	0.0	38.9	11,771.5	80.0	77.0	0.0	0.0	3,467.5	35,832.2	
2017	24.6	5,465.8	702.0	0.0	4.1	2.9	0.0	20.5	39.1	97.1	0.0	33.8	13,895.2	14.0	17.0	0.0	0.0	5,602.0	25,918.2	
2018	1,467.2	9,792.4	2,652.4	14.0	0.0	0.0	1,000.0	0.0	28.1	0.0	0.0	0.8	24,617.9	29.0	0.0	0.0	40.0	14,904.5	54,546.3	
Total	3,008.2	284,786.0	16,448.7	3,128.3	1,480.3	8.5	1,390.0	2,932.3	13,166.3	654.9	104.2	589.4	61,599.3	36,750.1	975.5	0.0	1,856.7	100,286.9	529,165.5	

### Combined Cycle Project Analysis

Table 12-27 shows the status of all combined cycle projects by number of projects that entered PJM generation queues from January 1, 1997, through December 31, 2018, by zone. Of the 111 combined cycle projects classified either as new generation or upgrade currently active, suspended or under construction in the PJM generation queue, 48 projects (43.2 percent) are located within AEP, ComEd and APS.

**Table 12-27 Status of all combined cycle queue projects by zone (number of projects): January 1997 through December 2018**

Project Status	Project Classification	Number of Projects																			Total		
		AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC	PECO	PENELEC	Pepeo	PPL		PSEG	RECO
In Service	New Generation	1	4	1	2	2	1	0	2	0	6	2	0	7	3	0	4	1	3	10	5	0	54
	Upgrade	2	8	5	3	0	3	0	0	0	12	5	0	4	1	0	9	3	2	5	13	0	75
Under Construction	New Generation	1	0	1	0	0	0	0	0	0	1	0	0	0	1	0	1	1	1	0	1	0	8
	Upgrade	0	2	0	0	0	1	0	0	0	0	0	0	1	1	0	3	1	1	2	1	0	13
Suspended	New Generation	0	1	1	0	0	0	0	0	0	0	0	0	1	0	0	0	1	1	0	0	0	5
	Upgrade	0	0	1	0	0	0	0	0	0	0	1	0	1	0	0	0	0	2	0	0	0	5
Withdrawn	New Generation	20	18	40	12	8	11	0	1	2	17	17	3	24	25	0	43	39	33	39	52	2	406
	Upgrade	6	7	5	3	0	3	0	1	0	10	4	0	5	7	0	3	5	3	6	15	0	83
Active	New Generation	2	8	7	5	0	7	1	0	0	2	0	0	1	0	0	0	0	0	2	4	0	39
	Upgrade	3	6	8	3	0	5	0	0	0	3	0	0	3	2	0	1	2	1	3	1	0	41
Total Projects	New Generation	24	31	50	19	10	19	1	3	2	26	19	3	33	29	0	48	42	38	51	62	2	512
	Upgrade	11	23	19	9	0	12	0	1	0	25	10	0	14	11	0	16	11	9	16	30	0	217

Table 12-28 shows the status of all combined cycle projects by MW that entered PJM generation queues from January 1, 1997 through December 31, 2018, by zone. Of the 46,843.8 MW of combined cycle projects classified either as new generation or upgrade currently active, suspended or under construction in the PJM generation queue, 22,320.9 MW (47.6 percent) are located within AEP, ComEd and APS.

**Table 12-28 Status of all combined cycle queue projects by zone (MW): January 1997 through December 2018**

Project Status	Project Classification	Project MW													
		AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed
In Service	New Generation	650.0	3,032.0	525.0	1,599.0	140.0	600.0	0.0	533.0	0.0	4,173.1	319.2	0.0	1,665.8	2,107.0
	Upgrade	220.0	230.0	670.0	306.0	0.0	621.0	0.0	0.0	0.0	853.0	102.0	0.0	110.0	10.0
Under Construction	New Generation	452.0	0.0	930.0	0.0	0.0	0.0	0.0	0.0	0.0	1,681.0	0.0	0.0	0.0	450.0
	Upgrade	0.0	100.0	0.0	0.0	0.0	12.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	35.0
Suspended	New Generation	0.0	585.0	1,140.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	440.0	0.0
	Upgrade	0.0	0.0	20.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	451.0	0.0	20.0	0.0
Withdrawn	New Generation	7,144.4	11,249.5	16,982.1	7,471.0	3,122.1	6,225.3	0.0	134.5	665.0	11,261.0	5,436.4	991.8	12,552.6	13,001.0
	Upgrade	115.4	711.0	579.0	86.0	0.0	1,375.0	0.0	36.0	0.0	580.4	668.0	0.0	253.0	1,742.0
Active	New Generation	946.0	6,589.0	4,606.0	5,217.0	0.0	4,954.9	1,150.0	0.0	0.0	2,660.0	0.0	0.0	570.0	0.0
	Upgrade	50.6	742.0	899.7	588.0	0.0	1,741.7	0.0	0.0	0.0	110.0	0.0	0.0	145.0	113.9
Total Projects	New Generation	9,192.4	21,455.5	24,183.1	14,287.0	3,262.1	11,780.2	1,150.0	667.5	665.0	19,775.1	5,755.6	991.8	15,228.4	15,558.0
	Upgrade	386.0	1,783.0	2,168.7	980.0	0.0	3,750.3	0.0	36.0	0.0	1,543.4	1,221.0	0.0	528.0	1,900.9

Project Status	Project Classification	Project MW									Total
		OVEC	PECO	PENELEC	Pepco	PPL	PSEG	RECO			
In Service	New Generation	0.0	1,905.0	850.0	1,540.5	5,750.0	1,880.5	0.0	27,270.0		
	Upgrade	0.0	853.5	92.3	89.1	229.0	845.9	0.0	5,231.8		
Under Construction	New Generation	0.0	760.0	1,050.0	19.5	0.0	568.0	0.0	5,910.5		
	Upgrade	0.0	155.0	50.0	64.5	483.0	0.0	0.0	900.1		
Suspended	New Generation	0.0	0.0	163.0	894.0	0.0	0.0	0.0	3,222.0		
	Upgrade	0.0	0.0	0.0	144.1	0.0	0.0	0.0	635.1		
Withdrawn	New Generation	0.0	23,340.0	15,931.0	20,414.2	16,785.7	22,496.7	6.9	195,211.1		
	Upgrade	0.0	240.0	1,040.6	85.0	500.0	2,217.9	0.0	10,229.3		
Active	New Generation	0.0	0.0	0.0	0.0	1,515.0	3,091.4	0.0	31,299.3		
	Upgrade	0.0	67.0	85.0	75.0	207.8	51.1	0.0	4,876.8		
Total Projects	New Generation	0.0	26,005.0	17,994.0	22,868.2	24,050.7	28,036.6	6.9	262,912.9		
	Upgrade	0.0	1,315.5	1,267.9	457.7	1,419.8	3,114.9	0.0	21,873.1		

### Combustion Turbine - Natural Gas Project Analysis

Table 12-29 shows the status of all combustion turbine natural gas projects by number of projects that entered PJM generation queues from January 1, 1997, through December 31, 2018, by zone. Of the 50 combustion turbine natural gas projects classified either as new generation or upgrade currently active, suspended or under construction in the PJM generation queue, 26 projects (52.0 percent) are located within AEP, ComEd and APS.

**Table 12-29 Status of all combustion turbine - natural gas generation queue projects by zone (number of projects): January 1997 through December 2018**

Project Status	Project Classification	Number of Projects																	Total				
		AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC	PECO	PENELEC		Pepco	PPL	PSEG	RECO
In Service	New Generation	5	0	6	0	3	0	0	0	0	2	7	0	3	1	0	2	4	2	4	9	0	48
	Upgrade	4	7	6	1	0	9	6	0	0	24	7	0	0	1	0	2	2	3	4	14	0	90
Under Construction	New Generation	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	1
	Upgrade	0	0	0	0	0	1	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	2
Suspended	New Generation	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3	0	0	0	0	3
	Upgrade	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0	1
Withdrawn	New Generation	1	3	0	0	0	1	0	0	0	2	0	0	0	0	0	1	2	0	1	5	0	16
	Upgrade	1	1	0	1	0	0	0	0	0	0	0	0	0	1	0	0	1	0	0	0	0	5
Active	New Generation	1	3	0	0	2	2	0	0	0	3	0	1	0	0	0	1	1	0	0	0	0	14
	Upgrade	1	2	5	1	0	13	0	0	0	5	0	0	0	0	1	1	0	0	0	0	0	29
Total Projects	New Generation	7	6	6	0	5	3	0	0	1	7	7	1	3	1	0	4	10	2	5	14	0	82
	Upgrade	6	10	11	3	0	23	6	0	0	29	7	0	2	2	0	3	4	3	4	14	0	127

Table 12-30 shows the status of all combustion turbine natural gas projects by MW that entered PJM generation queues from January 1, 1997 through December 31, 2018, by zone. Of the 5,673.7 MW of combustion turbine natural gas projects classified either as new generation or upgrade currently active, suspended or under construction in the PJM generation queue, 2,849.0 MW (50.2 percent) are located within AEP, ComEd and APS.

**Table 12-30 Status of all combustion turbine – natural gas queue projects by zone (MW): January 1997 through December 2018**

Project Status	Project MW															
	Project Classification	AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC
In Service	New Generation	360.7	0.0	1,176.0	0.0	23.0	0.0	0.0	0.0	0.0	1,015.0	1,491.0	0.0	522.1	10.0	0.0
	Upgrade	43.7	190.0	187.7	40.0	0.0	257.0	60.0	0.0	0.0	887.7	86.0	0.0	0.0	34.1	0.0
Under Construction	New Generation	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	205.0	0.0	0.0	0.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	48.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Suspended	New Generation	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	200.0	0.0	0.0
Withdrawn	New Generation	7.5	66.0	0.0	0.0	0.0	10.0	0.0	0.0	0.0	75.5	0.0	0.0	0.0	0.0	0.0
	Upgrade	7.5	6.0	0.0	25.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Active	New Generation	230.0	1,453.0	0.0	0.0	153.6	230.0	0.0	0.0	0.0	1,061.3	0.0	73.0	0.0	0.0	0.0
	Upgrade	158.0	38.0	120.0	70.0	0.0	960.0	0.0	0.0	0.0	95.0	0.0	0.0	0.0	0.0	0.0
Total Projects	New Generation	598.2	1,519.0	1,176.0	0.0	176.6	240.0	0.0	0.0	205.0	2,151.8	1,491.0	73.0	522.1	10.0	0.0
	Upgrade	209.2	234.0	307.7	135.0	0.0	1,265.0	60.0	0.0	0.0	982.7	86.0	0.0	200.0	34.1	0.0

Project Status	Project MW							
	Project Classification	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total
In Service	New Generation	559.0	361.9	5.0	150.9	925.9	0.0	6,600.5
	Upgrade	13.0	25.0	32.0	252.3	215.0	0.0	2,323.5
Under Construction	New Generation	0.0	0.0	0.0	0.0	0.0	0.0	205.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	48.0
Suspended	New Generation	0.0	68.8	0.0	0.0	0.0	0.0	68.8
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	200.0
Withdrawn	New Generation	0.5	258.0	0.0	19.9	1,140.1	0.0	1,577.5
	Upgrade	0.0	235.0	0.0	0.0	0.0	0.0	273.5
Active	New Generation	29.0	463.0	0.0	0.0	0.0	0.0	3,692.9
	Upgrade	0.0	18.0	0.0	0.0	0.0	0.0	1,459.0
Total Projects	New Generation	588.5	1,151.7	5.0	170.8	2,066.0	0.0	12,144.7
	Upgrade	13.0	278.0	32.0	252.3	215.0	0.0	4,304.0

### Wind Project Analysis

Table 12-31 shows the status of all wind generation projects by number of projects that entered PJM generation queues from January 1, 1997, through December 31, 2018, by zone. Of the 84 wind projects to achieve in service status, 48 projects (57.1 percent) are located within AEP, ComEd and APS. Of the 123 wind projects currently active, suspended or under construction in the PJM generation queue, 94 projects (76.4 percent) are located within AEP, ComEd and APS.

**Table 12-31 Status of all wind generation queue projects by zone (number of projects): January 1997 through December 2018**

Project Status	Project Classification	Number of Projects																					
		AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total
In Service	New Generation	1	13	14	0	0	19	0	0	0	1	0	0	0	0	0	0	22	0	8	0	0	78
	Upgrade	0	0	0	0	0	2	0	0	0	0	0	0	0	0	0	0	4	0	0	0	0	6
Under Construction	New Generation	0	2	3	0	0	3	0	0	0	3	0	0	0	0	0	0	1	0	0	0	0	12
	Upgrade	0	0	1	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	3
Suspended	New Generation	0	4	3	0	0	0	0	0	0	1	0	0	0	0	0	0	1	0	1	0	0	10
	Upgrade	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1
Withdrawn	New Generation	15	95	41	8	0	95	14	0	0	18	10	1	0	0	0	0	63	0	43	1	0	404
	Upgrade	1	0	6	0	0	3	0	0	0	2	0	0	0	0	0	0	6	0	2	0	0	20
Active	New Generation	2	25	4	3	0	30	1	0	0	3	3	0	3	0	0	0	0	0	3	0	0	77
	Upgrade	1	3	4	0	0	10	0	0	0	0	0	0	0	0	0	0	2	0	0	0	0	20
Total Projects	New Generation	18	139	65	11	0	147	15	0	0	26	13	1	3	0	0	0	87	0	55	1	0	581
	Upgrade	2	3	12	0	0	16	0	0	0	3	0	0	0	0	0	0	12	0	2	0	0	50

Table 12-32 shows the status of all wind projects by MW that entered PJM generation queues from January 1, 1997 through December 31, 2018, by zone. Of the 7,562.7 MW of wind generation capacity to achieve the in service status, 6,230.7 MW (84.4 percent) of nameplate capacity is located within AEP, ComEd and APS. Of the 25,934.0 MW of wind generation capacity currently active, suspended or under construction in the PJM generation queue, 17,114.3 MW of generation capacity (66.0 percent) is located within AEP, ComEd and APS.

**Table 12-32 Status of all wind generation queue projects by zone (MW): January 1997 through December 2018**

Project Status	Project MW															
	Classification	AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC
In Service	New Generation	7.5	2,538.7	1,004.0	0.0	0.0	2,688.0	0.0	0.0	0.0	102.5	0.0	0.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Under Construction	New Generation	0.0	350.0	298.0	0.0	0.0	766.5	0.0	0.0	0.0	612.3	0.0	0.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	187.5	0.0	0.0	0.0	32.0	0.0	0.0	0.0	0.0	0.0
Suspended	New Generation	0.0	722.0	343.7	0.0	0.0	0.0	0.0	0.0	0.0	76.6	0.0	0.0	0.0	0.0	0.0
	Upgrade	0.0	0.0	16.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Withdrawn	New Generation	3,626.4	19,653.2	3,134.1	1,295.6	0.0	22,521.7	2,028.0	0.0	0.0	2,588.1	2,816.8	150.3	0.0	0.0	0.0
	Upgrade	0.0	0.0	100.0	0.0	0.0	5.7	0.0	0.0	0.0	82.0	0.0	0.0	0.0	0.0	0.0
Active	New Generation	516.0	5,117.3	350.0	816.1	0.0	7,473.0	100.0	0.0	0.0	2,400.3	599.8	0.0	3,016.0	0.0	0.0
	Upgrade	5.0	500.0	94.4	0.0	0.0	895.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Projects	New Generation	4,149.9	28,381.2	5,129.8	2,111.7	0.0	33,449.1	2,128.0	0.0	0.0	5,779.8	3,416.6	150.3	3,016.0	0.0	0.0
	Upgrade	5.0	500.0	210.7	0.0	0.0	1,088.9	0.0	0.0	0.0	114.0	0.0	0.0	0.0	0.0	0.0

Project Status	Project MW							
	Classification	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total
In Service	New Generation	0.0	995.0	0.0	226.5	0.0	0.0	7,562.2
	Upgrade	0.0	0.5	0.0	0.0	0.0	0.0	0.5
Under Construction	New Generation	0.0	70.0	0.0	0.0	0.0	0.0	2,096.8
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	219.5
Suspended	New Generation	0.0	100.0	0.0	98.0	0.0	0.0	1,340.3
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	16.3
Withdrawn	New Generation	0.0	5,277.0	0.0	3,242.1	20.0	0.0	66,353.2
	Upgrade	0.0	243.4	0.0	6.0	0.0	0.0	437.0
Active	New Generation	0.0	0.0	0.0	257.3	0.0	0.0	20,645.6
	Upgrade	0.0	120.3	0.0	0.0	0.0	0.0	1,615.5
Total Projects	New Generation	0.0	6,442.0	0.0	3,823.9	20.0	0.0	97,998.1
	Upgrade	0.0	364.2	0.0	6.0	0.0	0.0	2,288.8

### Solar Project Analysis

Table 12-33 shows the status of all solar generation projects by number of projects that entered PJM generation queues from January 1, 1997, through December 31, 2018, by zone. Of the 146 solar projects to achieve in service status, 9 projects (6.2 percent) are located within AEP, ComEd and APS. Of the 532 solar projects currently active, suspended or under construction in the PJM generation queue, 154 projects (28.9 percent) are located within AEP, ComEd and APS.

**Table 12-33 Status of all solar generation queue projects by zone (number of projects): January 1997 through December 2018**

Project Status	Project Classification	Number of Projects																						
		AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total	
In Service	New Generation	7	4	4	0	1	1	1	0	0	19	9	0	42	0	0	1	0	0	2	39	0	130	
	Upgrade	0	0	0	0	0	0	0	0	0	2	8	0	6	0	0	0	0	0	0	0	0	0	16
Under Construction	New Generation	0	0	1	0	0	0	0	0	0	4	4	0	4	0	0	0	0	0	0	0	6	0	19
	Upgrade	0	0	0	0	0	0	0	0	0	2	1	0	0	0	0	0	0	0	0	0	0	0	3
Suspended	New Generation	0	4	19	0	0	0	1	0	0	1	0	0	5	1	0	0	0	0	0	0	1	0	32
	Upgrade	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Withdrawn	New Generation	159	83	58	9	12	30	14	12	0	146	116	3	167	12	0	6	13	13	28	70	0	951	
	Upgrade	2	2	1	0	0	2	0	0	0	11	1	0	8	0	0	0	0	0	0	1	0	28	
Active	New Generation	16	80	19	9	0	23	11	3	1	166	40	10	6	13	0	1	8	13	7	11	1	438	
	Upgrade	0	6	1	1	0	1	1	3	1	18	1	0	2	2	0	0	0	1	1	0	1	40	
Total Projects	New Generation	182	171	101	18	13	54	27	15	1	336	169	13	224	26	0	8	21	26	37	127	1	1,570	
	Upgrade	2	8	2	1	0	3	1	3	1	33	11	0	16	2	0	0	0	1	1	1	1	87	

Table 12-34 shows the status of all solar projects by MW that entered PJM generation queues from January 1, 1997 through December 31, 2018, by zone. Of the 1,418.6 MW of solar generation capacity to achieve in service status, 76.7 MW (5.4 percent) of nameplate capacity is located within AEP, ComEd and APS. Of the 33,481.7 MW of solar generation capacity currently active, suspended or under construction in the PJM generation queue, 11,756.1 MW of generation capacity (35.1 percent) is located within AEP, ComEd and APS.

Table 12-34 Status of all solar generation queue projects by zone (MW): January 1997 through December 2018

		Project MW														
Project Status	Project Classification	AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCPL	Met-Ed	OVEC
In Service	New Generation	57.3	14.7	53.0	0.0	1.1	9.0	2.5	0.0	0.0	636.1	118.4	0.0	295.3	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3.1	0.0	0.0	16.3	0.0	0.0
Under Construction	New Generation	0.0	0.0	10.0	0.0	0.0	0.0	0.0	0.0	0.0	194.9	37.0	0.0	71.9	0.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	13.9	0.0	0.0	0.0	0.0	0.0
Suspended	New Generation	0.0	40.0	313.3	0.0	0.0	0.0	20.0	0.0	0.0	5.0	0.0	0.0	37.6	3.0	0.0
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Withdrawn	New Generation	1,665.3	6,470.6	1,486.4	271.1	53.3	1,816.8	523.9	279.4	0.0	8,539.0	1,540.7	189.9	1,348.8	467.0	0.0
	Upgrade	10.0	106.0	0.0	0.0	0.0	20.0	0.0	0.0	0.0	674.0	0.0	0.0	23.8	0.0	0.0
Active	New Generation	311.5	7,359.9	962.4	979.1	0.0	2,598.5	1,096.5	295.0	11.7	13,797.1	1,385.2	986.0	50.9	501.6	0.0
	Upgrade	0.0	377.0	75.0	20.0	0.0	20.0	20.0	85.0	8.3	737.1	20.0	0.0	17.3	40.0	0.0
Total Projects	New Generation	2,034.1	13,885.3	2,825.1	1,250.2	54.4	4,424.3	1,642.9	574.4	11.7	23,172.1	3,081.3	1,175.9	1,804.5	971.6	0.0
	Upgrade	10.0	483.0	75.0	20.0	0.0	40.0	20.0	85.0	8.3	1,428.1	20.0	0.0	57.4	40.0	0.0

		Project MW							Total
Project Status	Project Classification	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total	
In Service	New Generation	3.3	0.0	0.0	15.0	193.5	0.0	1,399.2	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	19.4	
Under Construction	New Generation	0.0	0.0	0.0	0.0	30.1	0.0	343.9	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	13.9	
Suspended	New Generation	0.0	0.0	0.0	0.0	6.0	0.0	424.9	
	Upgrade	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Withdrawn	New Generation	51.4	171.7	128.1	383.7	476.7	0.0	25,863.9	
	Upgrade	0.0	0.0	0.0	0.0	1.3	0.0	835.1	
Active	New Generation	18.0	458.8	172.9	174.6	56.2	40.0	31,255.8	
	Upgrade	0.0	0.0	3.6	0.0	0.0	20.0	1,443.3	
Total Projects	New Generation	72.7	630.5	301.0	573.3	762.5	40.0	59,287.6	
	Upgrade	0.0	0.0	3.6	0.0	1.3	20.0	2,311.7	

## Relationship Between Project Developer and Transmission Owner

A transmission owner (TO) is an “entity that owns, leases or otherwise has a possessory interest in facilities used for the transmission of electric energy in interstate commerce under the tariff.”<sup>37</sup> Where the transmission owner is a vertically integrated company that also owns generation, there is a potential conflict of interest when the transmission owner evaluates the interconnection requirements of new generation which is a competitor to the generation of the parent company and when the transmission owner evaluates the interconnection requirements of new generation which is part of the same company as the transmission owner. There is also a potential conflict of interest when the transmission owner evaluates the interconnection requirements of a merchant transmission developer which is a competitor of the transmission owner. The MMU recommends outsourcing interconnection studies to an independent party to avoid potential conflicts of interest.

Table 12-35 shows the relationship between the project developer and Transmission Owner for all project MW that have entered the PJM generation queue from January 1, 1997, through December 31, 2018, by transmission owner and unit type. A project where the developer is affiliated with the Transmission Owner is classified as related. A project where the developer is not affiliated with the Transmission Owner is classified as unrelated. For example, 36.0 MW of combined cycle generation projects that have entered the PJM generation queue in DEOK were projects developed by Duke Energy or subsidiaries of Duke Energy, the Transmission Owner for DEOK. These project MW are classified as related. There have been 667.5 MW of combined cycle projects that have entered the PJM generation queue in DEOK by developers not affiliated with Duke Energy. These project MW are classified as unrelated.

Of the 529,165.5 MW that have entered the queue during the time period of January 1, 1997, through December 31, 2018, 62,049.7 MW (11.7 percent) have been submitted by Transmission Owners building in their own service territory. PSEG is the Transmission Owner with the highest percentage of affiliates building in their own service territory. Of the 36,399.5 MW that entered the queue during the time period of January 1, 1997, through December 31, 2018, 14,279.0 MW (39.2 percent) have been submitted by PSEG or one of their affiliated companies.

37 See OATT § 1 (Transmission Owner).

**Table 12-35 Relationship between project developer and Transmission Owner for all interconnection queue projects MW by unit type: December 31, 2018**

Parent Company	Transmission Owner	Related to Developer	MW by Unit Type																				Total
			Number of Projects	Battery	CC	CT - Natural Gas	CT - Oil	CT - Other	Fuel Cell	Hydro - Pumped Storage	Hydro - Run of River	Nuclear	RICE - Natural Gas	RICE - Oil	RICE - Other	Solar	Steam - Coal	Steam - Natural Gas	Steam - Oil	Steam - Other	Wind		
AEP	AEP	Related	48	16.0	680.0	0.0	0.0	0.0	0.0	34.0	0.0	214.0	0.0	0.0	0.0	142.7	3,918.0	90.0	0.0	0.0	0.0	0.0	5,094.7
		Unrelated	486	478.0	22,558.5	1,753.0	7.5	127.3	0.0	0.0	448.4	0.0	12.0	0.0	75.4	14,225.6	10,368.0	0.0	0.0	492.0	28,881.2	79,426.8	
AES	DAY	Related	13	20.0	0.0	38.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	21.5	1,347.5	0.0	0.0	0.0	0.0	0.0	1,427.0	
		Unrelated	49	39.9	1,150.0	22.0	0.0	1.9	0.0	0.0	0.0	0.0	0.0	10.0	1,641.4	0.0	0.0	0.0	0.0	0.0	2,128.0	4,993.2	
DLCO	DLCO	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	22	20.0	665.0	205.0	40.0	19.2	0.0	0.0	106.0	1,879.0	0.0	0.0	0.0	20.0	2,810.0	0.0	0.0	0.0	0.0	5,764.2	
Dominion	Dominion	Related	92	0.0	12,274.0	908.7	100.0	0.0	0.0	340.0	0.0	1,944.0	0.0	0.0	60.0	901.6	301.0	0.0	0.0	4.0	146.0	16,979.3	
		Unrelated	472	140.0	9,044.5	2,225.8	0.5	227.3	0.0	0.0	35.0	0.0	10.0	119.4	23,698.6	20.0	0.0	0.0	316.3	5,747.8	41,585.2		
Duke	DEOK	Related	7	23.8	36.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6.4	0.0	0.0	0.0	0.0	0.0	0.0	66.2	
		Unrelated	26	16.0	667.5	0.0	0.0	0.0	0.0	0.0	112.0	0.0	0.0	4.8	653.0	120.0	0.0	0.0	0.0	0.0	0.0	1,573.3	
EKPC	EKPC	Related	2	0.0	821.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	821.8	
		Unrelated	16	0.0	170.0	73.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,175.9	0.0	0.0	0.0	0.0	0.0	150.3	1,569.2	
Exelon	AECO	Related	5	0.0	730.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	8.3	0.0	0.0	0.0	0.0	0.0	0.0	738.3	
		Unrelated	286	141.0	8,848.4	807.4	380.0	20.7	2.8	0.0	0.0	0.0	2.0	5.0	10.3	2,035.8	15.0	5.5	0.0	10.0	4,154.9	16,438.8	
	BGE	Related	14	20.0	250.0	10.0	0.0	0.0	0.0	0.0	0.0	108.5	0.0	0.0	8.5	20.0	10.0	101.0	0.0	0.0	0.0	528.0	
		Unrelated	57	40.6	3,012.1	166.6	18.0	133.0	0.0	0.0	0.4	3,280.0	1.3	0.0	0.0	34.4	0.0	2.5	0.0	25.0	0.0	6,713.9	
	ComEd	Related	16	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,185.0	0.0	0.0	0.0	9.0	0.0	0.0	0.0	0.0	0.0	1,194.0	
		Unrelated	338	411.1	15,530.5	1,505.0	42.0	65.2	0.0	0.0	22.7	0.0	35.0	0.0	67.7	4,455.3	1,926.0	91.0	0.0	90.0	34,538.0	58,779.5	
	DPL	Related	7	0.0	1,365.0	351.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7.4	0.0	0.0	0.0	0.0	0.0	0.0	1,723.4	
		Unrelated	282	143.0	5,611.6	1,226.0	600.9	42.6	0.0	0.0	0.0	0.0	0.0	84.6	3,093.9	653.0	15.0	0.0	65.0	3,416.6	14,952.2		
	PECO	Related	33	40.0	6,965.0	5.0	89.5	0.0	0.0	0.0	265.0	437.8	0.0	0.0	0.0	7.0	0.0	0.0	0.0	0.0	0.0	7,809.3	
		Unrelated	80	5.3	20,355.5	596.5	2.0	15.0	0.0	0.0	0.0	0.0	0.0	17.0	3.7	72.7	0.0	0.0	0.0	0.0	0.0	21,067.7	
	Pepco	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	90	20.0	23,325.9	37.0	30.0	9.0	0.0	0.0	0.0	1,640.0	32.0	0.0	3.5	304.6	0.0	0.0	0.0	0.0	0.0	25,402.0	
First Energy	APS	Related	4	0.0	1,453.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,710.0	0.0	0.0	0.0	0.0	3,163.0	
		Unrelated	355	330.9	24,898.8	1,483.7	0.0	84.4	0.0	0.0	623.3	0.0	140.0	53.8	25.4	2,900.1	4,092.0	0.0	0.0	184.4	5,340.5	40,157.3	
	ATSI	Related	6	0.0	1,678.0	0.0	0.0	0.0	0.0	0.0	0.0	16.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,694.0	
		Unrelated	77	56.1	13,589.0	135.0	5.0	166.4	0.0	0.0	0.0	0.0	59.7	0.0	6.9	1,270.2	0.0	16.5	0.0	0.0	2,111.7	17,416.5	
	JCPL	Related	2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	20.0	0.0	0.0	0.0	12.0	0.0	0.0	0.0	0.0	0.0	0.0	32.0	
		Unrelated	348	382.8	15,756.4	722.1	0.0	4.8	0.8	0.0	1.6	0.0	0.6	0.0	12.8	1,849.8	0.0	0.0	0.0	30.0	3,016.0	21,777.7	
	Met-Ed	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	102	23.0	17,458.9	44.1	1,196.9	52.1	0.0	0.0	0.0	93.0	0.0	8.0	23.2	1,011.6	0.0	0.0	0.0	84.0	0.0	19,994.8	
	PENELEC	Related	4	0.0	534.0	5.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,860.0	0.0	0.0	0.0	0.0	2,399.0	
		Unrelated	245	97.4	18,727.9	1,424.7	0.0	214.4	0.0	16.0	46.3	0.0	341.8	8.0	14.8	630.5	561.0	590.0	0.0	525.0	6,806.2	30,003.8	
OVEC	OVEC	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
PPL	PPL	Related	21	0.0	2,261.0	0.0	0.0	0.0	0.0	0.0	109.0	1,600.0	0.0	0.0	0.0	19.8	111.0	0.0	0.0	0.0	0.0	4,100.8	
		Unrelated	233	528.8	23,209.5	423.1	8.0	234.5	0.0	1,000.0	142.6	388.0	19.9	2.4	44.7	553.5	6,896.6	0.0	0.0	31.0	3,829.9	37,312.5	
PSEG	PSEG	Related	106	0.0	11,836.1	1,818.1	0.0	0.0	0.0	0.0	0.0	381.0	0.0	0.0	0.0	175.8	24.0	44.0	0.0	0.0	0.0	14,279.0	
		Unrelated	196	14.5	19,315.4	462.9	608.0	62.5	4.9	0.0	1,000.0	0.0	10.6	0.0	13.7	588.0	0.0	20.0	0.0	0.0	20.0	22,120.5	
Con Ed	RECO	Related	0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
		Unrelated	4	0.0	6.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	0.0	66.9	
Total		Related	380	119.8	40,883.9	3,135.8	189.5	0.0	0.0	374.0	394.0	5,886.3	0.0	0.0	68.5	1,324.4	9,288.5	235.0	0.0	4.0	146.0	62,049.7	
		Unrelated	3764	2,888.4	243,902.1	13,312.9	2,938.8	1,480.3	8.5	1,016.0	2,538.3	7,280.0	654.9	104.2	520.9	60,274.9	27,461.6	740.5	0.0	1,852.7	100,140.9	467,115.8	

## Combined Cycle Project Developer and Transmission Owner Relationships

Table 12-36 shows the relationship between the project developer and Transmission Owner for all combined cycle project MW that have entered the PJM generation queue from January 1, 1997 through December 31, 2018, by transmission owner and project status. Of the 39,312.4 combined cycle project MW that have achieved in service or under construction status during this time period, 9,156.0 MW (23.3 percent) have been developed by Transmission Owners building in their own service territory. EKPC is the Transmission Owner with the highest percentage of affiliates building combined cycle projects in their own service territory. Of the 991.8 MW that entered the queue during the time period of January 1, 1997, through December 31, 2018, 821.8 MW (82.9 percent) have been submitted by EKPC or one of their affiliated companies.

**Table 12-36 Relationship between project developer and transmission owner for all combined cycle project MW in PJM interconnection queue: December 31, 2018**

Parent Company	Transmission Owner	Related to Developer	MW by Project Status					Total
			Active	In Service	Under Construction	Suspended	Withdrawn	
AEP	AEP	Related	100.0	580.0	0.0	0.0	0.0	680.0
		Unrelated	7,231.0	2,682.0	100.0	585.0	11,960.5	22,558.5
AES	DAY	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	1,150.0	0.0	0.0	0.0	0.0	1,150.0
DLCO	DLCO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	665.0	665.0
Dominion	Dominion	Related	0.0	3,092.0	1,681.0	0.0	7,501.0	12,274.0
		Unrelated	2,770.0	1,934.1	0.0	0.0	4,340.4	9,044.5
Duke	DEOK	Related	0.0	0.0	0.0	0.0	36.0	36.0
		Unrelated	0.0	533.0	0.0	0.0	134.5	667.5
EKPC	EKPC	Related	0.0	0.0	0.0	0.0	821.8	821.8
		Unrelated	0.0	0.0	0.0	0.0	170.0	170.0
Exelon	AECO	Related	0.0	0.0	0.0	0.0	730.0	730.0
		Unrelated	996.6	870.0	452.0	0.0	6,529.8	8,848.4
	BGE	Related	0.0	130.0	0.0	0.0	120.0	250.0
		Unrelated	0.0	10.0	0.0	0.0	3,002.1	3,012.1
	ComEd	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	6,696.6	1,221.0	12.6	0.0	7,600.3	15,530.5
	DPL	Related	0.0	60.0	0.0	0.0	1,305.0	1,365.0
		Unrelated	0.0	361.2	0.0	451.0	4,799.4	5,611.6
	PECO	Related	0.0	0.0	0.0	0.0	6,965.0	6,965.0
		Unrelated	67.0	2,758.5	915.0	0.0	16,615.0	20,355.5
	Pepco	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	75.0	1,629.6	84.0	1,038.1	20,499.2	23,325.9
First Energy	APS	Related	0.0	525.0	0.0	0.0	928.0	1,453.0
		Unrelated	5,505.7	670.0	930.0	1,160.0	16,633.1	24,898.8
	ATSI	Related	0.0	0.0	0.0	0.0	1,678.0	1,678.0
		Unrelated	5,805.0	1,905.0	0.0	0.0	5,879.0	13,589.0
	JCPL	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	715.0	1,775.8	0.0	460.0	12,805.6	15,756.4
	Met-Ed	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	113.9	2,117.0	485.0	0.0	14,743.0	17,458.9
	PENELEC	Related	0.0	0.0	0.0	0.0	534.0	534.0
		Unrelated	85.0	942.3	1,100.0	163.0	16,437.6	18,727.9
OVEC	OVEC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
PPL	PPL	Related	0.0	600.0	0.0	0.0	1,661.0	2,261.0
		Unrelated	1,722.8	5,379.0	483.0	0.0	15,624.7	23,209.5
PSEG	PSEG	Related	51.1	1,920.0	568.0	0.0	9,297.0	11,836.1
		Unrelated	3,091.4	806.4	0.0	0.0	15,417.6	19,315.4
Con Ed	RECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	6.9	6.9
Total		Related	151.1	6,907.0	2,249.0	0.0	31,576.8	40,883.9
		Unrelated	36,025.0	25,594.8	4,561.6	3,857.1	173,863.5	243,902.1

## Combustion Turbine – Natural Gas Project Developer and Transmission Owner Relationships

Table 12-37 shows the relationship between the project developer and Transmission Owner for all CT – natural gas project MW that have entered the PJM generation queue from January 1, 1997 through December 31, 2018, by transmission owner and project status. Of the 9,177.0 CT – natural gas project MW that have achieved in service or under construction status during this time period, 2,107.0 (23.0 percent) have been developed by Transmission Owners building in their own service territory. PSEG is the Transmission Owner with the highest percentage of affiliates building CT – natural gas projects in their own service territory. Of the 2,281.0 MW that entered the queue during the time period of January 1, 1997, through December 31, 2018, 1,818.1 MW (79.7 percent) have been submitted by PSEG or one of their affiliated companies.

**Table 12-37 Relationship between project developer and transmission owner for all CT – natural gas project MW in PJM interconnection queue: December 31, 2018**

Parent Company	Transmission Owner	Related to Developer	MW by Project Status					Total
			Active	In Service	Under Construction	Suspended	Withdrawn	
AEP	AEP	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	1,491.0	190.0	0.0	0.0	72.0	1,753.0
AES	DAY	Related	0.0	38.0	0.0	0.0	0.0	38.0
		Unrelated	0.0	22.0	0.0	0.0	0.0	22.0
DLCO	DLCO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	205.0	0.0	0.0	205.0
Dominion	Dominion	Related	122.7	786.0	0.0	0.0	0.0	908.7
		Unrelated	1,033.6	1,116.7	0.0	0.0	75.5	2,225.8
Duke	DEOK	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
EKPC	EKPC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	73.0	0.0	0.0	0.0	0.0	73.0
Exelon	AECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	388.0	404.4	0.0	0.0	15.0	807.4
	BGE	Related	0.0	10.0	0.0	0.0	0.0	10.0
		Unrelated	153.6	13.0	0.0	0.0	0.0	166.6
	ComEd	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	1,190.0	257.0	48.0	0.0	10.0	1,505.0
DPL	DPL	Related	0.0	351.0	0.0	0.0	0.0	351.0
		Unrelated	0.0	1,226.0	0.0	0.0	0.0	1,226.0
PECO	PECO	Related	0.0	5.0	0.0	0.0	0.0	5.0
		Unrelated	29.0	567.0	0.0	0.0	0.5	596.5
Pepco	Pepco	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	37.0	0.0	0.0	0.0	37.0
First Energy	APS	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	120.0	1,363.7	0.0	0.0	0.0	1,483.7
	ATSI	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	70.0	40.0	0.0	0.0	25.0	135.0
	JCPL	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	522.1	0.0	200.0	0.0	722.1
Met-Ed	Related	0.0	0.0	0.0	0.0	0.0	0.0	
	Unrelated	0.0	44.1	0.0	0.0	0.0	44.1	
PENELEC	PENELEC	Related	0.0	5.0	0.0	0.0	0.0	5.0
		Unrelated	481.0	381.9	0.0	68.8	493.0	1,424.7
OVEC	OVEC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
PPL	PPL	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	403.2	0.0	0.0	19.9	423.1
PSEG	PSEG	Related	0.0	912.0	0.0	0.0	906.1	1,818.1
		Unrelated	0.0	228.9	0.0	0.0	234.0	462.9
Con Ed	RECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
Total	Total	Related	122.7	2,107.0	0.0	0.0	906.1	3,135.8
		Unrelated	5,029.2	6,817.0	253.0	268.8	944.9	13,312.9

## Wind Project Developer and Transmission Owner Relationships

Table 12-38 shows the relationship between the project developer and Transmission Owner for all wind project MW that have entered the PJM generation queue from January 1, 1997 through December 31, 2018, by transmission owner and project status. Of the 9,879.0 wind project MW that have achieved in service or under construction status during this time period, 12.0 MW (0.1 percent) have been developed by Transmission Owners building in their own service territory. Dominion is the Transmission Owner with the highest percentage of affiliates building wind projects in their own service territory. Of the 5,893.8 MW that entered the queue during the time period of January 1, 1997, through December 31, 2018, 146.0 MW (2.5 percent) have been submitted by Dominion or one of their affiliated companies.

**Table 12-38 Relationship between project developer and transmission owner for all wind project MW in PJM interconnection queue: December 31, 2018**

Parent Company	Transmission Owner	Related to Developer	MW by Project Status					Total
			Active	In Service	Under Construction	Suspended	Withdrawn	
AEP	AEP	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	5,617.3	2,538.7	350.0	722.0	19,653.2	28,881.2
AES	DAY	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	100.0	0.0	0.0	0.0	2,028.0	2,128.0
DLCO	DLCO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
Dominion	Dominion	Related	0.0	0.0	12.0	0.0	134.0	146.0
		Unrelated	2,400.3	102.5	632.3	76.6	2,536.1	5,747.8
Duke	DEOK	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
EKPC	EKPC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	150.3	150.3
Exelon	AECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	521.0	7.5	0.0	0.0	3,626.4	4,154.9
	BGE	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
	ComEd	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	8,368.7	2,688.0	954.0	0.0	22,527.3	34,538.0
	DPL	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	599.8	0.0	0.0	0.0	2,816.8	3,416.6
	PECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
	Pepco	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
First Energy	APS	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	444.4	1,004.0	298.0	360.0	3,234.1	5,340.5
	ATSI	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	816.1	0.0	0.0	0.0	1,295.6	2,111.7
	JCPL	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	3,016.0	0.0	0.0	0.0	0.0	3,016.0
	Met-Ed	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
	PENELEC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	120.3	995.5	70.0	100.0	5,520.3	6,806.2
OVEC	OVEC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
PPL	PPL	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	257.3	226.5	0.0	98.0	3,248.1	3,829.9
PSEG	PSEG	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	20.0	20.0
Con Ed	RECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
Total		Related	0.0	0.0	12.0	0.0	134.0	146.0
		Unrelated	22,261.1	7,562.7	2,304.3	1,356.6	66,656.2	100,140.9

## Solar Project Developer and Transmission Owner Relationships

Table 12-39 shows the relationship between the project developer and Transmission Owner for all solar project MW that have entered the PJM generation queue from January 1, 1997 through December 31, 2018, by transmission owner and project status. Of the 1,776.4 solar project MW that have achieved in service or under construction status during this time period, 475.6 MW (26.8 percent) have been developed by Transmission Owners building in their own service territory. BGE is the Transmission Owner with the highest percentage of affiliates building solar projects in their own service territory. Of the 54.4 MW that entered the queue during the time period of January 1, 1997, through December 31, 2018, 20.0 MW (36.8 percent) have been submitted by BGE or one of their affiliated companies.

**Table 12-39 Relationship between project developer and transmission owner for all solar project MW in PJM interconnection queue: December 31, 2018**

Parent Company	Transmission Owner	Related to Developer	MW by Project Status					Total
			Active	In Service	Under Construction	Suspended	Withdrawn	
AEP	AEP	Related	68.0	14.7	0.0	10.0	50.0	142.7
		Unrelated	7,668.9	0.0	0.0	30.0	6,526.6	14,225.6
AES	DAY	Related	0.0	0.0	0.0	0.0	21.5	21.5
		Unrelated	1,116.5	2.5	0.0	20.0	502.4	1,641.4
DLCO	DLCO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	20.0	0.0	0.0	0.0	0.0	20.0
Dominion	Dominion	Related	340.3	309.4	20.0	0.0	231.9	901.6
		Unrelated	14,193.9	329.8	188.8	5.0	8,981.1	23,698.6
Duke	DEOK	Related	0.0	0.0	0.0	0.0	6.4	6.4
		Unrelated	380.0	0.0	0.0	0.0	273.0	653.0
EKPC	EKPC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	986.0	0.0	0.0	0.0	189.9	1,175.9
Exelon	AECO	Related	0.0	0.0	0.0	0.0	8.3	8.3
		Unrelated	311.5	57.3	0.0	0.0	1,667.0	2,035.8
	BGE	Related	0.0	0.0	0.0	0.0	20.0	20.0
		Unrelated	0.0	1.1	0.0	0.0	33.3	34.4
	ComEd	Related	0.0	9.0	0.0	0.0	0.0	9.0
		Unrelated	2,618.5	0.0	0.0	0.0	1,836.8	4,455.3
	DPL	Related	0.0	7.4	0.0	0.0	0.0	7.4
		Unrelated	1,405.2	111.0	37.0	0.0	1,540.7	3,093.9
	PECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	18.0	3.3	0.0	0.0	51.4	72.7
	Pepco	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	176.5	0.0	0.0	0.0	128.1	304.6
First Energy	APS	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	1,037.4	53.0	10.0	313.3	1,486.4	2,900.1
	ATSI	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	999.1	0.0	0.0	0.0	271.1	1,270.2
	JCPL	Related	0.0	0.0	0.0	0.0	12.0	12.0
		Unrelated	68.2	311.6	71.9	37.6	1,360.6	1,849.8
	Met-Ed	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	541.6	0.0	0.0	3.0	467.0	1,011.6
	PENELEC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	458.8	0.0	0.0	0.0	171.7	630.5
OVEC	OVEC	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	0.0	0.0	0.0	0.0	0.0	0.0
PPL	PPL	Related	19.8	0.0	0.0	0.0	0.0	19.8
		Unrelated	154.8	15.0	0.0	0.0	383.7	553.5
PSEG	PSEG	Related	24.3	111.1	4.0	0.0	36.4	175.8
		Unrelated	31.9	82.4	26.1	6.0	441.7	588.0
Con Ed	RECO	Related	0.0	0.0	0.0	0.0	0.0	0.0
		Unrelated	60.0	0.0	0.0	0.0	0.0	60.0
Total		Related	452.4	451.6	24.0	10.0	386.5	1,324.4
		Unrelated	32,246.6	967.0	333.8	414.9	26,312.5	60,274.9

## Regional Transmission Expansion Plan (RTEP)<sup>38</sup>

The PJM RTEP process is designed to identify needed transmission system additions and improvements to continue to provide reliable service throughout the RTO. The objective of the RTEP process is to provide PJM with an optimal set of solutions necessary to solve reliability issues, operational performance issues and transmission constraints.

The RTEP process initially considered only factors such as load growth and the generation interconnection requests in its development of the 15 year plan. Currently, the RTEP process includes a broader range of inputs including the effects of public policy, market efficiency, interregional coordination and the effects of aging infrastructure.

### RTEP Process

The PJM RTEP process is a 24 month planning process that identifies reliability issues for the next 15 year period. This 24 month planning process includes a process to build power flow models that represent the expected future system topology, studies to identify issues, stakeholder input and PJM Board of Manager approvals. The 24 month planning process is made up of overlapping 18 month planning cycles to identify and develop shorter lead time transmission upgrades and one 24 month planning cycle to provide sufficient time for the identification and development of longer lead time transmission upgrades that may be required to satisfy planning criteria.

### Backbone Facilities

PJM baseline transmission projects are implemented to resolve reliability criteria violations. PJM backbone transmission projects are a subset of significant baseline projects, which are intended to resolve multiple reliability criteria violations and congestion issues and which may have substantial impacts on energy and capacity markets. There are currently three backbone projects under development, Surry Skiffes Creek 500kV, and the

conversion of the Marion-Bayonne and Bayway-Linden lines from 138 kV to 345 kV.<sup>39</sup>

### Market Efficiency Process

PJM's Regional Transmission Expansion Plan (RTEP) process includes a market efficiency analysis. The stated purpose of the market efficiency analysis is: to determine which reliability based enhancements have economic benefit if accelerated; to identify new transmission enhancements that result in economic benefits; and to identify economic benefits associated with modification to existing RTEP reliability based enhancements that when modified would relieve one or more economic constraints. PJM identifies the economic benefit of proposed transmission projects based on production cost analyses.<sup>40</sup> PJM presents the RTEP market efficiency enhancements to the PJM Board, along with stakeholder input, for Board approval.

To be recommended to the PJM Board of Managers for approval, the relative benefits and costs of the economic based enhancement or expansion must meet a benefit/cost ratio threshold of at least 1.25:1. The benefit/cost ratio is the ratio of the present value of the total annual benefit for 15 years to the present value of the total annual cost for the first 15 years of the life of the enhancement or expansion.

The market efficiency process is comprised of a 12 month cycle and a 24 month cycle, both of which begin and end on the calendar year. The 12 month cycle is used for analysis of modifications and accelerations to approved RTEP projects only. The 24 month cycle is used for analysis of new economic transmission projects for years five through 15. This long-term proposal window takes place concurrent with the long-term proposal window for reliability projects.<sup>41</sup>

PJM's first market efficiency analysis was performed in 2013, prior to Order 1000. That analysis evaluated the historical sources of congestion on 25 flowgates.<sup>42</sup>

<sup>38</sup> The material in this section is based in part on the PJM Manual 14B: PJM Region Transmission Planning Process. See PJM, "PJM Manual 14B: PJM Region Transmission Planning Process," Rev. 42 (Aug. 23, 2018) <<http://www.pjm.com/-/media/documents/manuals/m14b.ashx?la=en>>.

<sup>39</sup> See PJM, "2017 RTEP Process Scope and Input Assumptions White Paper," at 25. <<http://www.pjm.com/-/media/library/reports-notices/2017-rtep/20170731-rtep-input-assumptions-and-scope-whitepaper.ashx?la=en>>.

<sup>40</sup> See PJM, "PJM Regional Transmission Expansion Plan: 2016" (February 28, 2017). <<http://www.pjm.com/-/media/library/reports-notices/2016-rtep/2016-rtep-books-1-3.ashx?la=en>>.

<sup>41</sup> See PJM, "PJM Market Efficiency Modeling Practices" (February 2, 2017). <<http://www.pjm.com/-/media/planning/rtep-dev/market-efficiency/pjm-market-efficiency-modeling-practices.ashx?la=en>>.

<sup>42</sup> Historical congestion drivers are identified using the historical congestion tables presented in the *State of the Market Report for PJM*, Section 11: Congestion and Marginal Losses, historical analysis of real time constraints, the NERC Book of Flowgates and PROMOD simulations.

The proposal window was open from August 12, 2013, through September 26, 2013. PJM received 38 proposals from six entities. One project was approved by the PJM Board.

The first market efficiency cycle conducted under Order 1000 was performed during the 2014/2015 RTEP long term window. That analysis evaluated the historical sources of congestion on 77 flowgates, 57 of which could be addressed by market efficiency projects. The proposal window was open from October 30, 2014, through February 27, 2015. PJM received 119 proposals, 93 of which addressed the market efficiency issues, with the remaining submissions addressing reliability issues identified by PJM. A total of 14 projects were approved by the PJM Board for this window, 13 of which were market efficiency projects and one of which was for reliability.

The second market efficiency cycle was performed during the 2016/2017 RTEP long term window. That analysis evaluated the historical sources of congestion on a total of four flowgates, all four of which could be addressed by market efficiency projects. The proposal window was open from November 1, 2016, through February 28, 2017. PJM received 96 proposals, all 96 of which addressed market efficiency issues. A total of four projects were approved by the PJM Board for this window, all four of which were market efficiency projects.

The third market efficiency cycle is currently being prepared for the 2018/2019 RTEP long term window. The proposal window will be open from November 1, 2018 through February 28, 2019.

In 2018, the PJM Board of Managers received correspondence from several officials, representing regions in Pennsylvania and Maryland, requesting an updated benefit/cost evaluation and the cancellation of the previously approved Transource AP-South market

efficiency project.<sup>43 44 45 46</sup> Approved market efficiency projects periodically undergo a reevaluation process to ensure that the benefit/cost ratio continues to meet the 1.25:1 threshold. The Transource AP-South project was reevaluated in September 2017, February 2018 and again in September 2018. The project exceeded the 1.25:1 threshold in all reevaluations. PJM also concluded that there would be significant reliability violations with the project removed from the model.<sup>47</sup>

## The Benefit/Cost Evaluation

For an RTEP project to be recommended to the PJM Board of Managers for approval as a Market Efficiency project, the relative benefits and costs of the economic based enhancement or expansion must meet a benefit/cost ratio threshold of at least 1.25:1.

The total benefit of a project is calculated as the sum of the net present value of calculated energy market benefits and calculated reliability pricing model (RPM) benefits for a 15 year period, starting with the projected in service date of the project. Benefits are reductions in estimated load charges and production costs in the energy market and reductions in estimated load capacity payments and in system capacity costs in the capacity market. The method for calculating energy market benefits and reliability pricing model benefits used to measure the benefit of an RTEP project for purposes of the 1.25:1 benefit/cost ratio threshold depends on whether the project is regional or subregional. A regional project is any project rated at or above 230 kV. A subregional project is any project rated at less than 230 kv. For a regional project, the benefit for each modeled year is equal to 50 percent of the change in system energy production costs and generation capacity payments with and without the project plus 50 percent of the change in zonal load energy payments and 50 percent of zonal load capacity payments with and without the project,

43 See Letter from Governor Larry Hogan, State of Maryland, Office of the Governor (July 10, 2018) <<https://www.pjm.com/-/media/about-pjm/who-we-are/public-disclosures/20180828-gov-hogan-transource-july-2018-letter-to-pjm-board.ashx?la=en>>.

44 See Letter from State Representative Kristin Phillips Hill, 93<sup>rd</sup> District, Pennsylvania House of Representatives (September 6, 2018) <<https://www.pjm.com/-/media/about-pjm/who-we-are/public-disclosures/20180906-pa-rep-phillips-hill-letter-re-transource-llc.ashx?la=en>>.

45 See Letter from State Representative Stanley E. Saylor, 94<sup>th</sup> District, Pennsylvania House of Representatives (August 1, 2018) <<https://www.pjm.com/-/media/about-pjm/who-we-are/public-disclosures/20180907-pa-rep-saylor-letter-re-transource-llc.ashx?la=en>>.

46 See Letter from Paula M. Carmody, People Counsel, State of Maryland Office of People's Counsel (September 6, 2018) <<https://www.pjm.com/-/media/about-pjm/who-we-are/public-disclosures/20180907-opc-letter-to-pjm-board-re-sept-2018-transource-retool.ashx?la=en>>.

47 See "Transource AP-South (2014/15\_9A) Project Reevaluation," <<https://www.pjm.com/-/media/committees-groups/committees/teac/20180913/20180913-ap-south-9a-project-reevaluation-sept-2018.ashx>>.

including only those zones where the project reduced the load energy payments and reduced the load capacity payments. For subregional projects, the benefits for each modeled year are equal to the change in zonal energy and capacity payments with and without the project, including only those zones where the project reduced the energy and capacity payments.

The Energy Market Benefit analysis uses an energy market simulation tool that produces an hourly least-cost, security constrained market solution, including total operational costs, hourly LMPs, bus specific injections and bus specific withdrawals for each modeled year with and without the proposed RTEP project. Using the output from the model, PJM calculates changes in Energy Production Costs and Load Energy Payments. Energy Production Costs are the sum of generation payments in the energy market simulation in each modeled year. The change in the Energy Production costs in each modeled year is calculated on a system wide basis Using the modeled changes in LMPs, changes in Load Energy Payments are calculated on a zonal basis and are netted against corresponding changes in the estimated value of any Auction Revenue Rights (ARR) that sink in that zone. Estimated ARR credits are calculated for each simulated year using the most recent planning year's actual ARR MW combined with FTR prices assumed to be equal to the market simulation's CLMP differences between ARR source and sink points. The value of the ARR rights with and without the RTEP project is evaluated based on changes in modeled CLMPs on the latest, historic allocation of ARR rights. ARR MW allocations are not adjusted to reflect any potential changes in ARR allocations which may be allowed by the RTEP upgrade.

The Reliability Pricing Model Benefit analysis is conducted using the Reliability Pricing Model solution software, with and without the proposed RTEP project, using a set of estimated capacity offers.

The definition of the benefit in the RPM benefit analysis depends on whether the project is regional or subregional. For a regional project, the RPM benefit for each modeled year is equal to 50 percent of the change in system-wide Total System Capacity Cost with and without the project plus 50 percent of the change in zonal Load Capacity Payments with and without the project, including only those zones where the project reduced the Load Capacity

Payments. For subregional projects, the reliability pricing model benefits for each modeled year is equal to the change in zonal Load Capacity Payments with and without the project, including only those zones where the project reduced the Load Capacity Payments.

The difference in the benefits calculation used in the regional and subregional cost benefit threshold tests are related to how costs are allocated for approved regional and subregional projects. The costs of an approved regional project are allocated so that 50 percent of the total costs are allocated on a system wide load ratio share basis and the remaining 50 percent of the total costs are allocated to zones with projected energy market benefits and reliability pricing model benefits in proportion to those projected positive benefits. The costs of an approved subregional project are allocated so that the total costs of the project is allocated to zones with projected energy market benefits and reliability pricing model benefits in proportion to those projected positive benefits.

The current rules governing benefit/cost analysis of competing transmission projects do not correctly measure the relative costs and benefits of transmission projects. The current rules explicitly ignore the increased congestion costs that an RTEP project may create in a subset of zones when calculating the energy market benefits. The current rules do not account for the risk associated with the fact that the project costs are nonbinding estimates. All costs should be included in all zones and LDAs.

## PJM MISO Interregional Targeted Market Efficiency Process (TMEP)

PJM and MISO developed a process to facilitate the construction of interregional projects in response to the Commissions concerns about interregional coordination along the PJM-MISO seam, called the Targeted Market Efficiency Process (TMEP).<sup>48</sup>

The allocation of costs to each RTO for TMEPs will be in proportion to the benefits received.<sup>49</sup>

On November 2, 2017, PJM submitted a compliance filing including additional revisions the MISO-PJM JOA

<sup>48</sup> See *PJM Interconnection, LLC*, Docket No. ER17-718-000 (December 30, 2016).

<sup>49</sup> See *PJM Interconnection, LLC*, Docket No. ER17-729-000 (December 30, 2016).

to include stakeholder feedback in the TMEP project selection process.<sup>50 51</sup>

The first TMEP analysis occurred in 2017 and included the investigation of congestion on 50 market to market flowgates. The study resulted in the evaluation of 13 potential upgrades, resulting in the recommendation of five TMEP projects. The five projects address \$59 million in historical congestion, with a TMEP benefit of \$99.6 million. The projects have a total cost of \$20 million, with a 5.0 average benefit/cost ratio. PJM and MISO presented the five recommended projects to their boards in December, 2017, and both boards approved all five projects.<sup>52</sup>

The 2018 TMEP analysis included the investigation of congestion on 61 market to market flowgates. The study resulted in the evaluation of 19 potential upgrades, resulting in the recommendation of two TMEP projects. The two projects address \$25 million in historical congestion, with a TMEP benefit of \$31.9 million. The projects have a total cost of \$4.5 million, with a 7.1 average benefit/cost ratio. PJM and MISO presented the two recommended projects to their boards in December, 2018, and both boards approved the projects.<sup>53</sup>

### Supplemental Transmission Projects

Supplemental projects are “transmission expansions or enhancements that are not required for compliance with PJM criteria and are not state public policy projects according to the PJM Operating Agreement. These projects are used as inputs to RTEP models, but are not required for reliability, economic efficiency or operational performance criteria, as determined by PJM.”<sup>54</sup> Supplemental projects are selected solely by the Transmission Owner and no PJM approval is needed. Supplemental projects are currently exempt from the Order No. 1000 competitive process. Transmission owners have a clear incentive to increase investments in rate base given that transmission owners are paid for these projects on a cost of service basis.

Figure 12-3 shows the latest cost estimate of all supplemental projects by expected in service year. FERC Order 890 was issued on February 16, 2007, and implemented in PJM starting in 2008. Order 890 required Transmission Providers to participate in a coordinated, open and transparent planning process. Prior to the implementation of Order 890, there were transmission projects planned by transmission owners and included in the PJM planning models, that were not included in the totals shown in Figure 12-3, Table 12-40 and Table 12-41. There has been a significant increase in supplemental projects coincident with the coordinated, open and transparent planning process introduced by the implementation of Order 890 starting in 2008 and the competitive planning process introduced by the implementation of FERC Order No. 1000 starting in 2011.

**Figure 12-3 Latest cost estimate of supplemental projects by expected in service year: 1998 through 2018**




Table 12-40 shows the number of supplemental projects by expected in service year for each transmission zone. The average number of supplemental projects in each expected in service year increased by 520.0 percent, from 20 for years 1998 through 2007 (pre Order 890) to 124 for years 2008 through 2018 (post Order 890).

50 See *PJM Interconnection, LLC*, Docket No. ER17-718-000, ER17-721-000 and ER17-729-000 (Not Consolidated) (November 2, 2017).

51 161 FERC ¶ 61,005.

52 See PJM, “MISO PJM IPSAC,” (January 12, 2018) <<http://www.pjm.com/-/media/committees-groups/stakeholder-meetings/ipsac/20180112/20180112-ipsac-presentation.ashx>>.

53 See PJM, “MISO PJM IPSAC,” (January 18, 2019) <<https://www.pjm.com/-/media/committees-groups/stakeholder-meetings/ipsac/20190118/20190118-ipsac-presentation.ashx>>.

54 See PJM, “Transmission Construction Status,” (January 23, 2018) <<http://www.pjm.com/planning/rtep-upgrades-status/construct-status.aspx>>.

Table 12-40 Number of supplemental projects by expected in service year and zone: 1998 through 2040

Year	AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JCLP	Mct-Ed	OVEC	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total
1998	0	0	0	0	0	0	0	0	0	0	3	0	0	0	0	0	0	0	0	0	0	3
1999	0	0	0	0	0	0	0	0	0	0	2	0	0	0	0	0	0	0	0	0	0	2
2000	0	0	0	0	0	0	0	0	0	0	11	0	0	0	0	0	0	0	0	0	0	11
2001	0	0	0	0	0	0	0	0	0	0	14	0	0	0	0	0	0	0	0	0	0	14
2002	0	0	0	0	0	0	0	0	0	0	10	0	0	0	0	0	0	0	0	0	0	10
2003	3	0	0	0	0	0	0	0	0	0	10	0	0	0	0	0	2	0	0	0	0	15
2004	5	0	10	0	0	9	0	0	0	0	12	0	2	0	0	0	0	0	0	2	0	40
2005	4	2	8	0	0	4	0	0	0	1	14	0	1	0	0	1	2	0	0	2	0	39
2006	4	2	5	0	0	6	0	0	0	0	9	0	1	0	0	0	1	0	2	1	0	31
2007	1	1	5	0	4	5	0	0	4	0	6	0	0	0	0	0	2	0	1	6	0	35
2008	3	0	15	0	1	6	0	0	1	7	3	0	0	1	0	0	0	0	3	1	0	41
2009	3	1	6	0	1	8	0	0	3	3	5	0	0	0	0	5	1	0	0	2	0	38
2010	0	6	7	0	3	4	0	0	6	3	0	0	1	2	0	2	0	0	2	5	0	41
2011	0	8	8	0	0	2	0	0	5	2	0	0	1	0	0	4	0	0	3	4	0	37
2012	0	5	6	4	1	2	0	7	3	16	1	0	2	0	0	1	0	0	4	11	0	63
2013	5	21	4	5	0	11	0	6	5	13	1	0	1	1	0	1	0	1	13	19	0	107
2014	2	31	2	8	2	14	0	5	6	18	3	2	2	0	0	1	2	0	9	16	0	123
2015	4	15	2	9	1	37	0	8	4	17	5	4	2	0	0	1	0	4	7	24	0	144
2016	5	13	4	17	0	26	0	6	2	13	4	2	0	1	0	3	2	3	11	30	0	142
2017	8	103	3	26	1	23	0	3	8	35	11	5	0	3	0	0	3	1	21	43	0	297
2018	10	156	4	15	6	26	0	19	7	28	6	4	0	1	0	2	4	1	14	30	0	333
2019	8	180	2	23	1	12	2	18	2	13	8	9	0	0	0	1	13	1	33	25	0	351
2020	9	117	0	15	2	2	0	5	1	11	5	3	0	5	0	0	4	0	19	22	0	220
2021	6	62	0	5	0	2	10	0	1	8	2	2	1	2	0	0	0	0	22	26	1	150
2022	4	5	0	0	2	0	0	1	0	0	4	0	1	0	0	0	0	2	21	16	0	56
2023	2	4	0	0	0	0	0	0	2	1	2	0	1	3	0	0	1	0	12	0	0	28
2024	1	0	1	0	7	0	0	0	0	0	0	0	0	0	0	0	0	0	12	0	0	21
2025	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	0	0	0	6	0	0	8
2026	0	0	0	0	4	0	0	0	0	0	0	0	0	0	0	0	0	0	13	0	0	17
2027	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0	1
2028	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2029	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2030	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4	0	0	4
2031	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2032	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2033	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2034	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2035	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2036	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2037	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2038	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2039	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2040	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4	0	0	4
Total	88	732	92	127	37	199	12	78	60	189	151	31	16	19	0	22	37	13	237	285	1	2,426

Table 12-41 shows the latest cost estimate of supplemental projects by expected in service year for each transmission zone. The average latest cost of supplemental projects in each expected in service year increased by 1,541.6 percent, from \$64.5 million for years 1998 through 2007 (pre Order 890) to \$1,058.8 million for years 2008 through 2018 (post Order 890).

**Table 12-41 Latest cost estimate by expected in service year and zone (\$ millions): 1998 through 2040**

Year	AECO	AEP	APS	ATSI	BGE	ComEd	DAY	DEOK	DLCO	Dominion	DPL	EKPC	JPL	Mct-Ed	OVEC	PECO	PENELEC	Pepco	PPL	PSEG	RECO	Total
1998	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$1.67	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$1.67
1999	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.78	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.78
2000	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$32.95	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$32.95
2001	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$6.79	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$6.79
2002	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$7.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$7.00
2003	\$7.42	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$8.75	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$9.60	\$0.00	\$0.00	\$0.00	\$0.00	\$25.77
2004	\$4.44	\$0.00	\$9.99	\$0.00	\$0.00	\$0.82	\$0.00	\$0.00	\$0.00	\$0.00	\$7.32	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$22.58
2005	\$4.06	\$14.67	\$10.11	\$0.00	\$0.00	\$2.58	\$0.00	\$0.00	\$0.00	\$0.02	\$10.97	\$0.00	\$0.00	\$0.00	\$0.00	\$0.50	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$42.90
2006	\$4.03	\$309.70	\$0.94	\$0.00	\$0.00	\$48.93	\$0.00	\$0.00	\$0.00	\$0.00	\$11.63	\$0.00	\$6.00	\$0.00	\$0.00	\$0.00	\$1.50	\$0.00	\$4.63	\$18.80	\$0.00	\$406.15
2007	\$0.56	\$2.06	\$9.85	\$0.00	\$37.61	\$4.65	\$0.00	\$0.00	\$31.75	\$0.00	\$9.71	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.34	\$2.25	\$0.00	\$98.77
2008	\$2.36	\$0.00	\$12.03	\$0.00	\$0.45	\$7.61	\$0.00	\$0.00	\$7.00	\$14.01	\$2.28	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$1.60	\$0.00	\$0.00	\$47.33
2009	\$0.77	\$0.90	\$12.22	\$0.00	\$5.00	\$21.11	\$0.00	\$0.00	\$19.60	\$2.12	\$7.36	\$0.00	\$0.00	\$0.00	\$48.10	\$2.73	\$0.00	\$0.00	\$0.00	\$17.60	\$0.00	\$137.51
2010	\$0.00	\$34.36	\$12.13	\$0.00	\$18.90	\$1.38	\$0.00	\$0.00	\$34.45	\$14.98	\$0.00	\$0.00	\$0.03	\$4.58	\$0.00	\$31.80	\$0.00	\$0.00	\$1.08	\$17.72	\$0.00	\$171.41
2011	\$0.00	\$37.60	\$9.30	\$0.00	\$0.00	\$1.00	\$0.00	\$0.00	\$16.72	\$85.67	\$0.00	\$0.00	\$1.16	\$0.00	\$0.00	\$113.30	\$0.00	\$0.00	\$0.78	\$34.60	\$0.00	\$300.13
2012	\$0.00	\$46.00	\$5.12	\$0.35	\$2.20	\$12.60	\$0.00	\$26.06	\$11.60	\$165.74	\$0.99	\$0.00	\$6.61	\$0.00	\$0.00	\$12.60	\$0.00	\$0.00	\$8.91	\$223.01	\$0.00	\$521.79
2013	\$3.15	\$134.93	\$1.10	\$33.68	\$0.00	\$59.25	\$0.00	\$9.93	\$81.98	\$25.03	\$0.99	\$0.00	\$0.05	\$4.10	\$0.00	\$22.50	\$0.00	\$2.40	\$75.84	\$503.72	\$0.00	\$958.65
2014	\$8.03	\$387.00	\$5.97	\$58.70	\$21.20	\$60.37	\$0.00	\$2.43	\$14.90	\$88.61	\$5.96	\$0.38	\$5.60	\$0.00	\$0.00	\$13.30	\$1.30	\$0.00	\$33.47	\$309.70	\$0.00	\$1,016.92
2015	\$3.73	\$237.45	\$3.80	\$21.90	\$2.00	\$376.00	\$0.00	\$14.12	\$4.53	\$113.53	\$13.06	\$1.56	\$0.30	\$0.00	\$0.00	\$33.80	\$0.00	\$42.50	\$50.17	\$743.91	\$0.00	\$1,662.36
2016	\$73.54	\$79.98	\$18.40	\$182.70	\$0.00	\$308.15	\$0.00	\$15.13	\$26.95	\$40.68	\$26.60	\$0.25	\$0.00	\$2.37	\$0.00	\$86.40	\$0.40	\$7.80	\$58.76	\$744.18	\$0.00	\$1,672.29
2017	\$66.28	\$642.74	\$8.60	\$142.05	\$0.09	\$145.97	\$0.00	\$65.01	\$3.62	\$106.14	\$92.29	\$2.21	\$0.00	\$14.70	\$0.00	\$0.00	\$8.30	\$12.00	\$261.74	\$988.92	\$0.00	\$2,560.66
2018	\$71.73	\$773.84	\$14.80	\$61.58	\$7.89	\$140.03	\$0.00	\$121.80	\$9.74	\$182.27	\$79.79	\$10.87	\$0.00	\$2.40	\$0.00	\$47.60	\$15.10	\$156.00	\$184.90	\$716.93	\$0.00	\$2,597.27
2019	\$86.45	\$1,325.37	\$0.93	\$177.80	\$67.20	\$95.20	\$7.81	\$74.39	\$10.90	\$35.60	\$46.26	\$33.49	\$0.00	\$0.00	\$0.00	\$0.80	\$77.10	\$70.00	\$414.24	\$703.56	\$0.00	\$3,227.10
2020	\$78.54	\$969.72	\$0.00	\$154.90	\$62.50	\$49.00	\$0.00	\$42.41	\$16.80	\$27.43	\$34.22	\$15.46	\$0.00	\$36.60	\$0.00	\$0.00	\$76.70	\$0.00	\$314.90	\$1,977.08	\$0.00	\$3,856.26
2021	\$33.46	\$1,011.31	\$0.00	\$138.80	\$0.00	\$2.00	\$57.10	\$0.00	\$20.00	\$77.40	\$16.11	\$14.70	\$16.00	\$40.10	\$0.00	\$0.00	\$0.00	\$0.00	\$290.80	\$935.15	\$17.00	\$2,669.93
2022	\$106.40	\$87.60	\$0.00	\$0.00	\$263.00	\$0.00	\$0.00	\$0.12	\$0.00	\$0.00	\$35.00	\$0.00	\$22.00	\$0.00	\$0.00	\$0.00	\$0.00	\$527.00	\$432.30	\$970.00	\$0.00	\$2,443.42
2023	\$12.84	\$54.70	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$40.00	\$32.00	\$29.72	\$0.00	\$8.50	\$16.30	\$0.00	\$0.00	\$200.00	\$0.00	\$148.90	\$0.00	\$0.00	\$542.96
2024	\$0.00	\$0.00	\$3.60	\$0.00	\$223.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$272.43	\$0.00	\$0.00	\$499.03
2025	\$64.00	\$0.00	\$0.00	\$0.00	\$7.50	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$143.00	\$0.00	\$0.00	\$214.50
2026	\$0.00	\$0.00	\$0.00	\$0.00	\$45.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$312.24	\$0.00	\$0.00	\$357.24
2027	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$22.70	\$0.00	\$0.00	\$22.70
2028	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2029	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2030	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$62.00	\$0.00	\$0.00	\$62.00
2031	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2032	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2033	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2034	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2035	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2036	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2037	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2038	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2039	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00
2040	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	\$8.33	\$0.00	\$0.00	\$8.33
Total	\$631.79	\$6,149.93	\$138.89	\$972.46	\$763.54	\$1,336.64	\$64.91	\$371.40	\$350.54	\$1,011.23	\$488.17	\$78.92	\$66.25	\$121.15	\$0.00	\$410.70	\$392.73	\$817.70	\$3,104.05	\$8,907.13	\$17.00	\$26,195.12

The role of supplemental projects in the market efficiency process needs to be modified. It is not clear how a supplemental project can be a market efficiency project that has been identified as a PJM issue based on a cost/benefit analysis and why such a project should not be subject to competition. The MMU recommends, to increase the role of competition, that the exemption of supplemental projects from the Order No. 1000 competitive process be terminated.

### End of Life Transmission Projects

An end of life transmission project is a project submitted for the purpose of replacing existing infrastructure that has, or is approaching, the end of its useful life.<sup>55</sup> End of life transmission projects fall under the Transmission Owner Form 715 Planning Criteria, and are currently exempt from the competitive planning process.<sup>56</sup> End of life transmission projects are already included in the supplemental projects totals or, if included in the transmission owners' reliability plan, will be included in the baseline project list as a reliability criteria project.

<sup>55</sup> The useful life of a transmission investment typically exceeds its depreciable life.

<sup>56</sup> See PJM Operating Agreement Schedule 6 § 1.5.8(o).

## Competitive Planning Process Exclusions

There are several project types that are currently exempt from the competitive planning process. These project types include:

- **Immediate Need Exclusion:** Due to the immediate need of the violation (3 years or less), the timing required for an RTEP proposal window is considered to be infeasible. As a result, the local Transmission Owner is the Designated Entity.<sup>57</sup>
- **Below 200kV:** Due to the lower voltage level of the identified violation(s), the driver(s) for this project are currently excluded from the competitive proposal window process. As a result, the local Transmission Owner is the Designated Entity.<sup>58</sup>
- **FERC 715 (Transmission Owner (TO) Criteria):** Due to the violation need of this project resulting solely from FERC 715 TO Reliability Criteria, the driver(s) for this project are currently excluded from the competitive proposal window process. As a result, the local Transmission Owner is the Designated Entity.<sup>59</sup>
- **Substation Equipment:** Due to identification of the limiting element(s) as substation equipment, the driver(s) for this project are currently excluded from the competitive proposal window process. As a result, the local Transmission Owner is the Designated Entity.<sup>60</sup>

While the PJM Operating Agreement defines who will be the Designated Entity for projects that are excluded from the competitive planning process, neither the PJM Operating Agreement nor the various commission orders on transmission competition prohibit PJM from permitting competition to provide financing for such projects. The MMU recommends that rules be implemented to permit competition to provide financing for transmission projects. This competition could reduce the cost of capital for transmission projects and significantly reduce total costs to customers. In addition, the criteria for and need for all exclusions from the competitive process should be reviewed. There does not appear to be any market reason to exclude transmission projects from competition.

<sup>57</sup> See PJM Operating Agreement Schedule 6 § 1.5.8(m).

<sup>58</sup> See PJM Operating Agreement Schedule 6 § 1.5.8(n).

<sup>59</sup> See PJM Operating Agreement Schedule 6 § 1.5.8(o).

<sup>60</sup> See PJM Operating Agreement Schedule 6 § 1.5.8(p).

## Cost Capping

The MMU recommends that rules be implemented to require that project cost caps on new transmission projects be part of the evaluation of competing projects. On May 24, 2018, the PJM Markets and Reliability Committee (MRC) approved a motion that required PJM, with input from the MMU, to develop a comparative framework to evaluate the quality and effectiveness of binding cost containment proposals versus proposals without cost containment provisions. The proposed comparative framework, along with the advice and recommendation of the MMU, will be presented to the PJM Planning Committee for review and comment prior to an MRC vote. The comparative framework will be presented at the December 2019 meeting of the MRC.

## Board Authorized Transmission Upgrades

The Transmission Expansion Advisory Committee (TEAC) regularly reviews internal and external proposals to improve transmission reliability throughout PJM. These proposals, which include reliability baseline, network, market efficiency and targeted market efficiency projects, are periodically presented to the PJM Board of Managers for authorization.<sup>61</sup>

An RTEP project can be approved by the PJM Board if the project ensures compliance with NERC, regional and local transmission owner planning criteria or to address market efficiency congestion relief. These projects are considered Baseline Projects. PJM Board approved RTEP projects that are necessary to allow new generation to interconnect reliably are considered Network Projects.

In 2018, \$1.98 billion in additional projects were approved by the PJM Board. As of December 31, 2018, the PJM Board has approved \$37.1 billion in system enhancements since 1999.

- On February 13, 2018, the PJM Board of Managers authorized an additional \$328.8 million in transmission upgrades and additions.
- On April 10, 2018, the PJM Board of Managers authorized an additional \$639.0 million in transmission upgrades and additions.

<sup>61</sup> Supplemental Projects, including the end of life subset of supplemental projects, do not require PJM Board of Managers authorization.

- On July 31, 2018, the PJM Board of Managers authorized an additional \$629.2 million in transmission upgrades and additions.
- On October 2, 2018, the PJM Board of Managers authorized an additional \$201.5 million in transmission upgrades and additions.
- On December 4, 2018, the PJM Board of Managers authorized an additional \$183.6 million in transmission upgrades and additions.

## Qualifying Transmission Upgrades (QTU)

A Qualifying Transmission Upgrade (QTU) is: “a proposed enhancement or addition to the transmission system that: (a) will increase the Capacity Emergency Transfer Limit into an LDA by a megawatt quantity certified by the Office of the Interconnection; (b) the Office of the Interconnection has determined will be in service on or before the commencement of the first Delivery Year for which such upgrade is the subject of a Sell Offer in the Base Residual Auction; (c) is the subject of a Facilities Study Agreement executed before the conduct of the Base Residual Auction for such Delivery Year and (d) a New Service Customer is obligated to fund through a rate or charge specific to such facility or upgrade.”<sup>62</sup> If a QTU that was cleared in a BRA is not completed by the start of the Delivery Year, the submitting party is required to provide replacement capacity. Once a QTU is in service, the upgrade is eligible to continue to offer the approved incremental import capability into future RPM Auctions. As of December 31, 2018, no QTUs have cleared a BRA.

QTU projects are submitted and tracked through the PJM queue.<sup>63</sup> A total of 51 QTU projects have entered the queue since 2007. Of the 51 submitted QTU projects, 37 projects (72.5 percent) have been withdrawn, five (10.0 percent) are in service and nine (17.5 percent) are currently in active development.

## Transmission Facility Outages Scheduling Transmission Facility Outage Requests

A transmission facility is designated as reportable by PJM if a change in its status can affect a transmission constraint on any Monitored Transmission Facility or could impede free flowing ties within the PJM RTO and/or adjacent areas.<sup>64</sup> When a reportable transmission facility needs to be taken out of service, the transmission owner is required to submit an outage request as early as possible.<sup>65</sup> The specific timeline is shown in Table 12-43.<sup>66</sup>

Transmission outages have significant impacts on PJM markets, including impacts on FTR auctions, on congestion, and on expected market outcomes in the day-ahead and real-time markets. The efficient functioning of the markets depends on clear, enforceable rules governing transmission outages.

The outage data for the FTR market are for outages scheduled to occur in the planning periods 2017/2018 and 2018/2019, regardless of when they were initially submitted.<sup>67</sup> The outage data for the day-ahead market are for outages scheduled to occur from January 2015 through December 2018.

Transmission outages are categorized by duration: greater than 30 calendar days; less than or equal to 30 calendar days; greater than five calendar days; less than or equal to five calendar days.<sup>68</sup> Table 12-42 shows that 74.4 percent of requested outages were planned for less than or equal to five days and 8.8 percent of requested outages were planned for greater than 30 days in the 2018/2019 planning period. Table 12-42 also shows that 75.9 percent of the requested outages were planned for less than or equal to five days and 7.7 percent of requested outages were planned for greater than 30 days in the 2017/2018 planning period.

<sup>62</sup> See OATT § 1 (Qualifying Transmission Upgrade).

<sup>63</sup> See PJM “New Services Queue,” at <<https://www.pjm.com/planning/services-requests/interconnection-queues.aspx>>.

<sup>64</sup> If a transmission facility is not modeled in the PJM EMS or the facility is not expected to significantly impact PJM system security or congestion management, it is not reportable. See PJM, “Manual 3: Transmission Operations,” Rev. 54 (Dec. 10, 2018).

<sup>65</sup> See PJM, “Manual 3: Transmission Operations,” Rev. 54 (Dec. 10, 2018).

<sup>66</sup> See PJM, “Manual 3: Transmission Operations,” Rev. 54 (Dec. 10, 2018).

<sup>67</sup> The hotline tickets, EMS tripping tickets or test outage tickets were excluded. The analysis includes only the transmission outage tickets submitted by PJM companies which are currently active. The data for the reported was last run on January 31, 2019. The result will change for the 2018/2019 planning period if more outages requests are submitted after the report was created.

<sup>68</sup> *Id.* at 70.

**Table 12-42 Transmission facility outage request summary by planned duration: 2017/2018 and 2018/2019**

Planned Duration (Days)	2017/2018		2018/2019	
	Outage Requests	Percent of Total	Outage Requests	Percent of Total
<=5	16,205	75.9%	12,485	74.4%
>5 &lt;=30	3,489	16.3%	2,821	16.8%
>30	1,652	7.7%	1,484	8.8%
Total	21,346	100.0%	16,790	100.0%

After receiving a transmission facility outage request from a TO, PJM assigns a received status to the request based on its submission date and outage planned duration. The received status can be On Time or Late, as defined in Table 12-43.<sup>69</sup>

The purpose of the rules defined in Table 12-43 is to require the TOs to submit transmission facility outages prior to the Financial Transmission Right (FTR) auctions so that market participants have complete information about market conditions on which to base their FTR bids and PJM can accurately model market conditions.<sup>70</sup>

**Table 12-43 PJM transmission facility outage request received status definition**

Planned Duration (Calendar Days)	Request Submitted	Received Status
<=5	Before the first of the month one month prior to the starting month of the outage	On Time
	After or on the first of the month one month prior to the starting month of the outage	Late
> 5 &lt;=30	Before the first of the month six months prior to the starting month of the outage	On Time
	After or on the first of the month six months prior to the starting month of the outage	Late
>30	The earlier of 1) February 1, 2) the first of the month six months prior to the starting month of the outage	On Time
	After or on the earlier of 1) February 1, 2) the first of the month six months prior to the starting month of the outage	Late

Table 12-44 shows a summary of requests by received status. In the 2018/2019 planning period, 42.8 percent of outage requests received were late. In the 2017/2018 planning period, 49.7 percent of outage requests received were late.

**Table 12-44 Transmission facility outage request summary by received status: 2017/2018 and 2018/2019**

Planned Duration (Days)	2017/2018				2018/2019			
	On Time	Late	Total	Percent Late	On Time	Late	Total	Percent Late
<=5	8,418	7,787	16,205	48.1%	7,375	5,110	12,485	40.9%
>5 &lt;=30	1,712	1,777	3,489	50.9%	1,581	1,240	2,821	44.0%
>30	609	1,043	1,652	63.1%	655	829	1,484	55.9%
Total	10,739	10,607	21,346	49.7%	9,611	7,179	16,790	42.8%

Once received, PJM processes outage requests in priority order: emergency transmission outage request; transmission outage request submitted on time; and transmission outage request submitted late. Transmission outage requests that are submitted late may be approved if the outage does not affect the reliability of PJM or cause congestion in the system.<sup>71</sup>

Outages with emergency status will be approved even if submitted late after PJM determines that the outage does not result in Emergency Procedures. PJM cancels or withholds approval of any outage that results in Emergency Procedures.<sup>72</sup> Table 12-45 is a summary of outage requests by emergency status. Of all outage requests scheduled to occur in the 2018/2019 planning period, 11.2 percent were for emergency outages. Of all outage requests scheduled to occur in the 2017/2018 planning period, 12.6 percent were for emergency outages.

<sup>69</sup> See PJM, "Manual 3: Transmission Operations," Rev. 54 (Dec. 10, 2018).

<sup>70</sup> See "Report of PJM Interconnection, L.L.C. on Transmission Oversight Procedures," Docket No. EL01-122-000 (November 2, 2001).

<sup>71</sup> See PJM, "Manual 3: Transmission Operations," Rev. 54 (Dec. 10, 2018). The following language was removed from Manual 3 Rev. 50: PJM retains the right to deny all jobs submitted after 8 a.m. three days prior to the requested start date unless the request is an emergency job or an exception request (i.e. a generator tripped and the Transmission Owner is taking advantage of a situation that was not available before the unit trip).

<sup>72</sup> PJM, "Manual 3: Transmission Operations," Rev. 54 (Dec. 10, 2018).

**Table 12-45 Transmission facility outage request summary by emergency: 2017/2018 and 2018/2019**

Planned Duration (Days)	2017/2018				2018/2019			
	Emergency	Non Emergency	Total	Percent Emergency	Emergency	Non Emergency	Total	Percent Emergency
<=5	2,051	14,154	16,205	12.7%	1,356	11,129	12,485	10.9%
>5 &lt;=30	399	3,090	3,489	11.4%	314	2,507	2,821	11.1%
>30	249	1,403	1,652	15.1%	205	1,279	1,484	13.8%
Total	2,699	18,647	21,346	12.6%	1,875	14,915	16,790	11.2%

PJM will approve all transmission outage requests that are submitted on time and do not jeopardize the reliability of the PJM system. PJM will approve all transmission outage requests that are submitted late and are not expected to cause congestion on the PJM system and do not jeopardize the reliability of the PJM system. Each outage is studied and if it is expected to cause a constraint to exceed a limit, PJM will flag the outage ticket as “congestion expected.”<sup>73</sup>

After PJM determines that a late request may cause congestion, PJM informs the transmission owner of solutions available to eliminate the congestion. For example, if a generator planned or maintenance outage request is contributing to the congestion, PJM can request that the generation owner defer the outage. If no solutions are available, PJM may require the transmission owner to reschedule or cancel the outage.

Table 12-46 is a summary of outage requests by congestion status. Of all outage requests submitted to occur in the 2018/2019 planning period, 7.5 percent were expected to cause congestion. Of all the outage requests that were expected to cause congestion, 4.3 percent (55 out of 1,267) were denied by PJM in the 2018/2019 planning period and 20.8 percent (264 out of 1,267) were cancelled (Table 12-48). Of all outage requests submitted to occur in the 2017/2018 planning period, 7.5 percent were expected to cause congestion. Of all the outage requests that were expected to cause congestion, 3.6 percent (58 out of 1,602) were denied by PJM in the 2017/2018 planning period and 19.6 percent (314 out of 1,602) were cancelled (Table 12-48).

**Table 12-46 Transmission facility outage request summary by congestion: 2017/2018 and 2018/2019**

Planned Duration (Days)	2017/2018				2018/2019			
	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
<=5	1,094	15,111	16,205	6.8%	848	11,637	12,485	6.8%
>5 &lt;=30	357	3,132	3,489	10.2%	273	2,548	2,821	9.7%
>30	151	1,501	1,652	9.1%	146	1,338	1,484	9.8%
Total	1,602	19,744	21,346	7.5%	1,267	15,523	16,790	7.5%

Table 12-47 shows the outage requests summary by received status, congestion status and emergency status. In the 2018/2019 planning period, 31.7 percent of requests were submitted late and were nonemergency while 1.1 percent of requests (179 out of 16,790) were late, nonemergency, and expected to cause congestion. In the 2017/2018 planning period, 37.1 percent of request were submitted late and were nonemergency while 1.4 percent of requests (297 out of 21,346) were late, nonemergency, and expected to cause congestion.

**Table 12-47 Transmission facility outage request summary by received status, emergency and congestion: 2017/2018 and 2018/2019**

Received Status		2017/2018				2018/2019			
		Congestion Expected	No Congestion Expected	Total	Percent of Total	Congestion Expected	No Congestion Expected	Total	Percent of Total
Late	Emergency	85	2,593	2,678	12.5%	51	1,808	1,859	11.1%
	Non Emergency	297	7,632	7,929	37.1%	179	5,141	5,320	31.7%
On Time	Emergency	3	18	21	0.1%	1	15	16	0.1%
	Non Emergency	1,217	9,501	10,718	50.2%	1,036	8,559	9,595	57.1%
Total		1,602	19,744	21,346	100.0%	1,267	15,523	16,790	100.0%

73 PJM added this definition to Manual 38 in February 2017. PJM, "Manual 38: Operations Planning," Rev. 11 (Feb. 1, 2018).

Once PJM processes an outage request, the outage request is labelled as Submitted, Received, Denied, Approved, Cancelled by Company, PJM Admin Closure, Revised, Active or Complete according to the processed stage of a request.<sup>74</sup> Table 12-48 shows the detailed process status for outage requests only for the outage requests that are expected to cause congestion. Status Submitted and status Received are in the In Process category and status Cancelled by Company and status PJM Admin Closure are in the Cancelled category in Table 12-48. Table 12-48 shows that of all the outage requests that were expected to cause congestion, 4.3 percent (55 out of 1,267) were denied by PJM in the 2018/2019 planning period, 50.5 percent were complete and 20.8 percent (264 out of 1,267) were cancelled. Of all the outage requests that were expected to cause congestion, 3.6 percent (58 out of 1,602) were denied by PJM in the 2017/2018 planning period, 70.8 percent were complete and 19.6 percent (314 out of 1,602) were cancelled.

**Table 12-48 Transmission facility outage requests that might cause congestion status summary: 2017/2018 and 2018/2019**

Received Status	2017/2018						2018/2019					
	Cancelled	Complete	In Process	Denied	Congestion Expected	Percent Complete	Cancelled	Complete	In Process	Denied	Congestion Expected	Percent Complete
Late												
Emergency	11	74	0	0	85	87.1%	5	45	1	0	51	88.2%
Non Emergency	47	220	9	18	297	74.1%	32	104	26	13	179	58.1%
On Time												
Emergency	2	1	0	0	3	33.3%	0	0	1	0	1	0.0%
Non Emergency	254	840	76	40	1,217	69.0%	227	491	266	42	1,036	47.4%
Total	314	1,135	85	58	1,602	70.8%	264	640	294	55	1,267	50.5%

There are clear rules defined for assigning On Time or Late status for submitted outage requests in both the PJM Tariff and PJM Manuals.<sup>75</sup> However, the On Time or Late status only affects the priority that PJM assigns for processing the outage request. Table 12-48 shows that in the 2017/2018 planning period, 297 nonemergency outage requests were submitted late and expected to cause congestion. The expected impact on congestion is the basis for PJM's treatment of late outage requests. But there is no rule or clear definition of this congestion analysis in the PJM Manuals. The MMU recommends that PJM draft a clear definition of the congestion analysis required for transmission outage requests to include in Manual 3 after appropriate review.

## Rescheduling Transmission Facility Outage Requests

A TO can reschedule or cancel an outage after initial submission. Table 12-49 is a summary of all the outage requests planned for the planning periods 2017/2018 and 2018/2019 which were approved and then cancelled or rescheduled by TOs at least once. If an outage request was submitted, approved and subsequently rescheduled at least once, the outage request will be counted as Approved and Rescheduled. If an outage request was submitted, approved and subsequently cancelled at least once, the outage request will be counted as Approved and Cancelled. In the 2018/2019 planning period, 26.3 percent of transmission outage requests were approved by PJM and then rescheduled by the TOs, and 9.8 percent of the transmission outages were approved by PJM and subsequently cancelled by the TOs. In the 2017/2018 planning period, 32.6 percent of transmission outage requests were approved by PJM and then rescheduled by the TO, and 12.5 percent of the transmission outages were approved by PJM and subsequently cancelled by the TO.

<sup>74</sup> See PJM Markets & Operations, PJM Tools "Outage Information," <<http://www.pjm.com/markets-and-operations/ctools/oasis/system-information/outage-info.aspx>> (2017).

<sup>75</sup> PJM Operating Agreement Schedule 1 § 1.9.2.

**Table 12-49 Rescheduled and cancelled transmission outage request summary: 2017/2018 and 2018/2019**

Planned Duration (Days)	Outage Requests	2017/2018			2018/2019					
		Approved and Rescheduled	Percent Approved and Rescheduled	Approved and Cancelled	Percent Approved and Cancelled	Approved and Rescheduled	Percent Approved and Rescheduled	Approved and Cancelled	Percent Approved and Cancelled	
<=5	16,205	3,654	22.5%	2,379	14.7%	12,485	2,401	19.2%	1,468	11.8%
>5 &lt;=30	3,489	2,162	62.0%	233	6.7%	2,821	1,293	45.8%	140	5.0%
>30	1,652	1,141	69.1%	66	4.0%	1,484	722	48.7%	38	2.6%
Total	21,346	6,957	32.6%	2,678	12.5%	16,790	4,416	26.3%	1,646	9.8%

If a requested outage is determined to be late and TO reschedules the outage, the outage will be reevaluated by PJM again as On Time or Late.

A transmission outage ticket with duration of five days or less with an On Time status can retain its On Time status if the outage is rescheduled within the original scheduled month.<sup>76</sup> This rule allows a TO to reschedule within the same month with very little notice.

A transmission outage ticket with a duration exceeding five days with an On Time status can retain its On Time status if the outage is rescheduled to a future month, and the revision is submitted by the first of the month prior to the revised month in which the outage will occur.<sup>77</sup> This rescheduling rule is much less strict than the rule that applies to the first submission of outage requests with similar duration. When first submitted, the outage request with a duration exceeding five days needs to be submitted before the first of the month nine months prior to the month in which the outage was expected to occur. The rescheduling rule allows TOs to avoid the timing requirements associated with outages exceeding five days.

The MMU recommends that PJM reevaluate all transmission outage tickets as On Time or Late as if they were new requests when an outage is rescheduled and apply the standard rules for late submissions to any such outages.

## Long Duration Transmission Facility Outage Requests

PJM rules (Table 12-43) define a transmission outage request as On Time or Late based on the planned outage duration and the time of submission. The rule has stricter submission requirements for transmission

outage requests planned for longer than 30 days. In order to avoid the stricter submission requirement, some transmission owners divided the duration of outage requests longer than 30 days into shorter segments for the same equipment and submitted one request for each segment. The MMU recommends that PJM not permit transmission owners to divide long duration outages into smaller segments to avoid complying with the requirements for long duration outages.

More than one outage request can be submitted for the same transmission equipment. In order to accurately present the results, Table 12-50 shows equipment outages by the equipment instead of by outage request.

Table 12-50 shows that there were 10,659 transmission equipment planned outages in the 2018/2019 planning period, of which 1,520 were longer than 30 days, and of which 221 or 2.1 percent were scheduled longer than 30 days when the duration of all the outage requests are combined for the same equipment.

**Table 12-50 Transmission outage summary: 2017/2018 and 2018/2019**

Planned Duration (Days)	Divided into Shorter Periods	2017/2018		2018/2019	
		Count of Equipment with Planned Outages	Percent of Total	Count of Equipment with Planned Outages	Percent of Total
> 30	No	1,440	11.3%	1,299	12.2%
	Yes	244	1.9%	221	2.1%
<= 30		11,033	86.8%	9,139	85.7%
Total		12,717	100.0%	10,659	100.0%

Table 12-51 shows the details of long duration (> 30 days) outages when combining the duration of the outage requests for the same equipment. The actual duration of scheduled outages would be longer than 30 days if the duration of the outage requests were appropriately combined for the same equipment. An effective duration was calculated for each piece of equipment by subtracting the start date of the earliest outage request from the end date of the latest outage

<sup>76</sup> PJM, "Manual 3: Transmission Operations," Rev. 54 (Dec. 10, 2018).

<sup>77</sup> *Id.*

request of the equipment. In the 2018/2019 planning period, there were 216 outages with a combined duration longer than 30 days.

**Table 12-51 Equipment outages: 2017/2018 and 2018/2019**

Effective Duration of Outage	2017/2018		2018/2019	
	Count of Equipment with Planned Outages	Percent of Total	Count of Equipment with Planned Outages	Percent of Total
<=31	6	2.5%	5	2.3%
>31 &lt;=62	25	10.2%	30	13.6%
>62 &lt;=93	18	7.4%	20	9.0%
>93	195	79.9%	166	75.1%
Total	244	100.0%	221	100.0%

## Transmission Facility Outage Analysis for the FTR Market

Transmission facility outages affect the price and quantity outcomes of FTR Auctions. The purpose of the rules governing outage reporting is to ensure that outages are known with enough lead time prior to FTR Auctions so that market participants can understand market conditions and PJM can accurately model market conditions.

There are Long Term, Annual and Monthly Balance of Planning Period auctions in the FTR Market. For each type of auction, PJM includes a set of outages to be modeled.

### Annual FTR Market

The Annual FTR Market includes the Annual ARR Allocation and the Annual FTR Auction. When determining transmission outages to be modeled in the simultaneous feasibility test used in the Annual FTR Market, PJM considers all outages with planned duration longer than or equal to two months and may consider outages with planned durations shorter than two months. PJM may exercise significant discretion in selecting outages to be modeled. PJM posts an FTR outage list to the FTR web page usually at least one week before the auction bidding opening day.<sup>78</sup>

In the 2018/2019 planning period, 241 outage requests were included in the annual FTR market outage list

and 16,549 outage requests were not included.<sup>79</sup> In the 2017/2018 planning period, 250 outage requests were included in the annual FTR market outage list and 21,096 outage requests were not included. Table 12-52, Table 12-53, Table 12-54 and Table 12-55 show the summary information on the modeled outage requests and Table 12-56 and Table 12-57 show the summary information on outages that were not included in the Annual FTR Market.

Table 12-52 shows that 8.3 percent of the outage requests modeled in the Annual FTR Market for the 2018/2019 planning period had a planned duration of less than two weeks and that 15.8 percent of the outage requests (38 out of 241) modeled in the Annual FTR Market for the planning period were submitted late according to outage submission rules. It also shows that 3.6 percent of the outage requests modeled in the Annual FTR Market for the 2017/2018 planning period had a planned duration of less than two weeks and that 12.8 percent of the outage requests (32 out of 250) modeled in the Annual FTR Market for the planning period were submitted late according to outage submission rules.

**Table 12-52 Annual FTR market modeled transmission facility outage requests by received status: 2017/2018 and 2018/2019**

Planned Duration	2017/2018			2018/2019		
	On Time	Late	Percent of Total	On Time	Late	Percent of Total
<2 weeks	7	2	3.6%	17	3	8.3%
>=2 weeks &lt;=2 months	80	9	35.6%	71	7	32.4%
>=2 months	131	21	60.8%	115	28	59.3%
Total	218	32	100.0%	203	38	100.0%

Table 12-53 shows the annual FTR market modeled outage requests summary by emergency status and received status. Three of the annual FTR market modeled outages expected to occur in the 2018/2019 planning period were emergency outages. None of the modeled outages expected to occur in the 2017/2018 planning period were emergency outages.

<sup>78</sup> PJM Financial Transmission Rights, "Annual ARR Allocation and FTR Auction Transmission Outage Modeling," <<http://www.pjm.com/~media/markets-ops/ftr/annual-ftr-auction/2017-2018/2017-2018-annual-outage-modeling.ashx>> (February 21, 2017).

<sup>79</sup> PJM's treatment of transmission outages in the FTR models is discussed in: See the 2018 State of the Market Report for PJM, Section 13: FTRs and ARRs: Supply and Demand.

**Table 12-53 Annual FTR market modeled transmission facility outage requests by emergency and received status: 2017/2018 and 2018/2019**

Received Status	Planned Duration	2017/2018				2018/2019			
		Emergency	Non Emergency	Total	Percent Non Emergency	Emergency	Non Emergency	Total	Percent Non Emergency
On Time	<2 weeks	0	7	7	100.0%	0	17	17	100.0%
	>=2 weeks & <2 months	0	80	80	100.0%	0	71	71	100.0%
	>=2 months	0	131	131	100.0%	0	115	115	100.0%
	Total	0	218	218	100.0%	0	203	203	100.0%
Late	<2 weeks	0	2	2	100.0%	0	3	3	100.0%
	>=2 weeks & <2 months	0	9	9	100.0%	0	7	7	100.0%
	>=2 months	0	21	21	100.0%	3	25	28	89.3%
	Total	0	32	32	100.0%	3	35	38	92.1%

PJM determines expected congestion for both On Time and Late outage requests. A Late outage request may be denied or cancelled if it is expected to cause congestion. Table 12-54 shows a summary of requests by expected congestion and received status. Overall, none of all the annual FTR market modeled outages expected to occur in the 2018/2019 planning period and submitted late were expected to cause congestion. Of all the annual FTR market modeled outages expected to occur in the 2017/2018 planning period and submitted late, 12.5 percent (4 out of 32) were expected to cause congestion.

**Table 12-54 Annual FTR market modeled transmission facility outage requests by congestion and received status: 2017/2018 and 2018/2019**

Received Status	Planned Duration	2017/2018				2018/2019			
		Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected	Congestion Expected	No Congestion Expected	Total	Percent Congestion Expected
On Time	<2 weeks	3	4	7	42.9%	9	8	17	52.9%
	>=2 weeks & <2 months	21	59	80	26.3%	20	51	71	28.2%
	>=2 months	40	91	131	30.5%	34	81	115	29.6%
	Total	64	154	218	29.4%	63	140	203	31.0%
Late	<2 weeks	0	2	2	0.0%	0	3	3	0.0%
	>=2 weeks & <2 months	1	8	9	11.1%	0	7	7	0.0%
	>=2 months	3	18	21	14.3%	0	28	28	0.0%
	Total	4	28	32	12.5%	0	38	38	0.0%

Table 12-55 shows that 21.8 percent of outage requests modeled in the annual FTR market for the 2018/2019 planning period and with a duration of two weeks or longer but shorter than two months were cancelled after the FTR auction was open, compared to 34.8 percent for the 2017/2018 planning period. Table 12-55 also shows that 21.0 percent of outages requests modeled in the Annual FTR Market for the 2018/2019 planning period and with a duration of two months or longer were cancelled, compared to 12.5 percent for the 2017/2018 planning period.

**Table 12-55 Annual FTR market modeled transmission facility outage requests by processed status: 2017/2018 and 2018/2019**

Planned Duration	Processed Status	2017/2018		2018/2019	
		Outage Requests	Percent	Outage Requests	Percent
<2 weeks	In Progress	0	0.0%	5	25.0%
	Denied	0	0.0%	0	0.0%
	Approved	0	0.0%	0	0.0%
	Cancelled	2	22.2%	2	10.0%
	Revised	0	0.0%	1	5.0%
	Active	0	0.0%	0	0.0%
	Completed	7	77.8%	12	60.0%
	Total	9	100.0%	20	100.0%
>=2 weeks & <2 months	In Progress	7	7.9%	26	33.3%
	Denied	2	2.2%	0	0.0%
	Approved	0	0.0%	1	1.3%
	Cancelled	31	34.8%	17	21.8%
	Revised	0	0.0%	0	0.0%
	Active	0	0.0%	2	2.6%
	Completed	49	55.1%	32	41.0%
	Total	89	100.0%	78	100.0%
>=2 months	In Progress	29	19.1%	41	28.7%
	Denied	0	0.0%	1	0.7%
	Approved	2	1.3%	1	0.7%
	Cancelled	19	12.5%	30	21.0%
	Revised	0	0.0%	1	0.7%
	Active	2	1.3%	31	21.7%
	Completed	100	65.8%	38	26.6%
	Total	152	100.0%	143	100.0%

More outage requests were not modeled in the Annual FTR Market than were modeled in the Annual FTR Market. In the 2018/2019 planning period, 241 outage requests were modeled and 16,549 outage requests were not modeled in the Annual FTR Market. In the 2017/2018 planning period, 250 outage requests were modeled and 21,096 outage requests were not modeled in the Annual FTR Market.

Table 12-56 shows that 6.5 percent of outage requests not modeled in the Annual FTR Auction with duration longer than or equal to two months, labelled On Time according to the rules, were submitted after the Annual FTR Auction bidding opening date for the 2018/2019 planning period compared to 23.0 percent in the 2017/2018 planning period.

**Table 12-56 Transmission facility outage requests not modeled in Annual FTR Auction: 2017/2018 and 2018/2019**

Planned Duration	2017/2018						2018/2019					
	On Time			Late			On Time			Late		
	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After
<2 weeks	1,350	8,019	85.6%	282	8,547	96.8%	1,781	6,375	78.2%	237	5,617	96.0%
>=2 weeks & <2 months	567	411	42.0%	139	1,023	88.0%	680	342	33.5%	163	657	80.1%
>=2 months	134	40	23.0%	215	369	63.2%	215	15	6.5%	213	254	54.4%
Total	2,051	8,470	80.5%	636	9,939	94.0%	2,676	6,732	71.6%	613	6,528	91.4%

Table 12-57 shows that 46.5 percent of late outage requests which were not modeled in the Annual FTR Auction with duration longer than or equal to two months and submitted after the Annual FTR Auction bidding opening date were approved and completed in the 2018/2019 planning period. It also shows that 85.4 percent of late outage requests which were not modeled in the Annual FTR Auction with duration longer than or equal to two months and submitted after the Annual FTR Auction bidding opening date were approved and completed in the 2017/2018 planning period.

**Table 12-57 Late transmission facility outage requests not modeled in Annual FTR Auction and submitted after annual bidding opening date: 2017/2018 and 2018/2019**

Planned Duration	2017/2018			2018/2019		
	Completed Outages	Total	Percent Complete	Completed Outages	Total	Percent Complete
<2 weeks	7,111	8,547	83.2%	4,345	5,617	77.4%
>=2 weeks & <2 months	900	1,023	88.0%	442	657	67.3%
>=2 months	315	369	85.4%	118	254	46.5%
Total	8,326	9,939	83.8%	4,905	6,528	75.1%

Although the definition of late outages was developed in order to prevent outages for the planning period being submitted after the opening of bidding in the Annual FTR Auction, the rules have not functioned effectively because the rule has no direct connection to the date on which bidding opens for the Annual FTR Auction. By requiring all long-duration transmission outages to be submitted before February 1, PJM outage submission rules only prevent long-duration transmission outages from being submitted late. The rule does not address the situation in which long-duration transmission outages are submitted on time, but are rescheduled so that they are late. There is no rule to address the situation in which short-duration outages (duration <= 5 days) are submitted on time, but are changed to long-duration transmission outages after the outages are approved and active. The Annual FTR Auction model may consider transmission outages planned for longer than two weeks but less than two months. Those outages not only include long duration outages but also include outages shorter than 30 days. In those cases, PJM outage submission rules failed to prevent long duration transmission outages from being submitted late. The MMU recommends that PJM modify the rules to eliminate the approval of outage requests submitted or rescheduled after the opening of bidding in the Annual FTR Auction.

## Monthly FTR Market

When determining transmission outages to be modeled in the Monthly Balance of Planning Period FTR Auction, PJM considers all outages with planned duration longer than five days and may consider outages with planned durations less than or equal to five days. PJM exercises significant discretion in selecting outages to be modeled. PJM posts an FTR outage list to the FTR webpage usually at least one week before the auction bidding opening

day.<sup>80</sup> Table 12-58 and Table 12-59 show the summary information on outage requests modeled in the Monthly Balance of Planning Period FTR Auction and Table 12-60 and Table 12-61 show the summary information on outage requests not modeled in the Monthly Balance of Planning Period FTR Auction.

Table 12-58 shows that on average, 27.3 percent of the outage requests modeled in the Monthly Balance of Planning Period FTR Auction were submitted late according to outage submission rules in the 2018/2019 planning period. On average, 30.6 percent of the outage requests modeled in the Monthly Balance of Planning Period FTR Auction were submitted late according to outage submission rules in the 2017/2018 planning period.

**Table 12-58 Monthly Balance of Planning Period FTR Auction modeled transmission facility outage requests by received status: 2017/2018 and 2018/2019**

Month	2017/2018				2018/2019			
	On Time	Late	Total	Percent Late	On Time	Late	Total	Percent Late
Jun	134	116	250	46.4%	208	106	314	33.8%
Jul	83	72	155	46.5%	136	71	207	34.3%
Aug	100	73	173	42.2%	137	78	215	36.3%
Sep	394	125	519	24.1%	465	136	601	22.6%
Oct	598	162	760	21.3%	536	191	727	26.3%
Nov	453	177	630	28.1%	391	129	520	24.8%
Dec	330	142	472	30.1%	363	129	492	26.2%
Jan	194	78	272	28.7%				
Feb	214	125	339	36.9%				
Mar	391	168	559	30.1%				
Apr	444	204	648	31.5%				
May	396	203	599	33.9%				
Avg	311	137	448	30.6%	319	120	439	27.3%

Table 12-59 shows that on average, 21.0 percent of outage requests modeled in the Monthly Balance of Planning Period FTR Auction were cancelled in the 2018/2019 planning period. On average, 19.0 percent of outage requests modeled in the Monthly Balance of Planning Period FTR Auction were cancelled in the 2017/2018 planning period.

<sup>80</sup> PJM Financial Transmission Rights, "2015/2016 Monthly FTR Auction Transmission Outage Modeling," <<http://www.pjm.com/-/media/markets-ops/ftr/ftr-allocation/monthly-ftr-auctions/2015-2016-monthly-transmission-outages-that-may-cause-infeasibilities.ashx?a=en>> (December 9, 2015).

**Table 12-59 Monthly Balance of Planning Period FTR Auction modeled transmission facility outage requests by processed status: 2017/2018 and 2018/2019**

Planning											Percent
Year	Month	In Process	Denied	Approved	Cancelled	Revised	Active	Complete	Total	Cancelled	
2017/2018	Jun	19	5	5	52	0	64	105	250	20.8%	
	Jul	11	2	8	25	0	54	55	155	16.1%	
	Aug	10	0	1	27	0	64	71	173	15.6%	
	Sep	67	8	13	100	3	161	167	519	19.3%	
	Oct	77	2	27	142	0	201	311	760	18.7%	
	Nov	39	5	10	121	2	177	276	630	19.2%	
	Dec	42	4	9	97	0	74	246	472	20.6%	
	Jan	29	6	9	59	0	80	89	272	21.7%	
	Feb	33	1	3	63	1	108	130	339	18.6%	
	Mar	66	5	15	114	3	171	185	559	20.4%	
	Apr	55	1	20	115	0	202	255	648	17.7%	
	May	20	11	16	108	0	145	299	599	18.0%	
	Avg	39	4	11	85	1	125	182	448	19.0%	
2018/2019	Jun	22	11	10	57	0	60	154	314	18.2%	
	Jul	11	4	6	38	0	60	88	207	18.4%	
	Aug	19	3	2	38	1	65	87	215	17.7%	
	Sep	77	11	22	143	1	163	184	601	23.8%	
	Oct	66	7	19	140	0	196	299	727	19.3%	
	Nov	39	2	8	119	1	166	185	520	22.9%	
	Dec	42	5	5	112	0	96	232	492	22.8%	
	Avg	39	6	10	92	0	115	176	439	21.0%	

Table 12-60 shows that on average, 10.5 percent of outage requests not modeled in the Monthly Balance of Planning Period FTR Auction, labeled On Time according to the rules, were submitted after the monthly FTR auction bidding opening dates in the 2018/2019 planning period, compared to 10.6 percent in the 2017/2018 planning period. On average, 70.4 percent of outage requests not modeled in the Monthly Balance of Planning Period FTR Auction, labeled Late according to the rules, were submitted after the Monthly Balance of Planning Period FTR Auction bidding opening dates in the 2018/2019 planning period, compared to 70.3 percent in the 2017/2018 planning period.

**Table 12-60 Transmission facility outage requests that are not modeled in Monthly Balance of Planning Period FTR Auction: 2017/2018 and 2018/2019**

	2017/2018						2018/2019					
	On Time			Late			On Time			Late		
	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After	Before Bidding Opening Date	After Bidding Opening Date	Percent After
Jun	642	96	13.0%	310	847	73.2%	757	120	13.7%	389	830	68.1%
Jul	294	48	14.0%	245	608	71.3%	393	64	14.0%	271	643	70.4%
Aug	341	28	7.6%	211	651	75.5%	484	67	12.2%	260	714	73.3%
Sep	859	84	8.9%	256	599	70.1%	820	144	14.9%	283	712	71.6%
Oct	986	89	8.3%	346	867	71.5%	1,244	104	7.7%	329	945	74.2%
Nov	815	83	9.2%	364	792	68.5%	886	60	6.3%	407	859	67.9%
Dec	610	68	10.0%	324	693	68.1%	676	31	4.4%	323	670	67.5%
Jan	565	74	11.6%	286	746	72.3%						
Feb	593	49	7.6%	340	700	67.3%						
Mar	1,070	217	16.9%	340	802	70.2%						
Apr	1,203	119	9.0%	446	852	65.6%						
May	1,203	149	11.0%	464	1,083	70.0%						
Avg	765	92	10.6%	328	770	70.3%	751	84	10.5%	323	768	70.4%

Table 12-61 shows that on average, 69.2 percent of late outage requests which were not modeled in the Monthly Balance of Planning Period FTR Auction, submitted after the Monthly Balance of Planning Period FTR Auction bidding opening dates, were approved and complete in the 2018/2019 planning period, compared to 68.3 percent in the 2017/2018 planning period.

**Table 12-61 Late transmission facility outage requests that are not modeled in Monthly Balance of Planning Period FTR Auction and submitted after monthly bidding opening date: 2017/2018 and 2018/2019**

	2017/2018			2018/2019		
	Completed Outages	Total	Percent Complete	Completed Outages	Total	Percent Complete
Jun	622	847	73.4%	633	830	76.3%
Jul	410	608	67.4%	449	643	69.8%
Aug	473	651	72.7%	506	714	70.9%
Sep	406	599	67.8%	480	712	67.4%
Oct	595	867	68.6%	614	945	65.0%
Nov	490	792	61.9%	570	859	66.4%
Dec	508	693	73.3%	468	670	69.9%
Jan	493	746	66.1%			
Feb	457	700	65.3%			
Mar	569	802	70.9%			
Apr	560	852	65.7%			
May	731	1,083	67.5%			
Avg	526	770	68.3%	531	768	69.2%

### Transmission Facility Outage Analysis in the Day-Ahead Energy Market

Transmission facility outages also affect the energy market. Just as with the FTR Market, it is critical that outages that affect the operating day are known prior to the submission of offers in the Day-Ahead Energy Market so that market participants can understand market conditions and PJM can accurately model market conditions in the day-ahead market. PJM requires transmission owners to submit changes to outages scheduled for the next two days no later than 09:30 am.<sup>81</sup>

There are three relevant time periods for the analysis of the impact of transmission outages on the energy market: before the day-ahead market is closed; when the day-ahead market save cases are created; and during the operating day. The list of approved or active outage requests before the day-ahead market is closed is available to market participants. The day-ahead market model uses outages included in the day-ahead market save cases as an input. The outages that actually occurred during the operating day are the outages that affect the real-time market. If the three sets of outages are the same, there is no potential impact on markets. If the three sets of outages differ, there is a potential negative impact on markets. For example, if the list of outages before the day-ahead market was closed was different from the list of outages that included in the day-ahead market save cases, the day-ahead market

participant would have inconsistent outage information as what day-ahead market model used.

For example for the operating day of May 5, 2018, Figure 12-4 shows that: there were 443 approved or active outages seen by market participants before the day-ahead market was closed; there were 329 outage requests included in the day-ahead market model; there were 315 outage requests included in both sets of outage; there were 128 outage requests approved or active before the day-ahead market was closed but not included as inputs in day-ahead market model; and there were 14 outage requests included in day-ahead market model but not available to market participants prior to the day-ahead market.

**Figure 12-4 Illustration of day-ahead market analysis: May 5, 2018**





Figure 12-5 compares the weekly average number of active or approved outages available to market participants prior to the close of the day-ahead market with the outages included as inputs to the day-ahead market by PJM.

<sup>81</sup> PJM, "Manual 3: Transmission Operations," Rev. 54 (Dec. 10, 2018).

**Figure 12-5 Approved or active outage requests: January 2015 through December 2018**



**Figure 12-7 Approved or active outage requests: January 2015 through December 2018**




Figure 12-6 compares the weekly average number of outages included as inputs to the day-ahead market by PJM with the outages that actually occurred during the operating day.

**Figure 12-6 Day-ahead market model outages: January 2015 through December 2018**




Figure 12-5, Figure 12-6, and Figure 12-7 show that on a weekly average basis, the active or approved outages available to day-ahead market participants, the outages included as inputs in the day-ahead market model and the outages that actually occurred in real time are not consistent. The active or approved outages available to day-ahead market participants are more consistent with the outages that actually occurred in real time than with the outages included in the day-ahead market model.

Figure 12-7 compares the weekly average number of active or approved outages available to market participants prior to the close of the day-ahead market with the outages that actually occurred during the operating day.

